


Finnish Network Statement 2011



FINNISH RAIL
ADMINISTRATION



Finnish Rail Administration

Finnish Network Statement 2011

ISBN 978-952-445-317-2 (nid.)
ISSN 1459-3831 (nid.)
ISBN 978-952-445-318-9 (pdf)
ISSN 1797-7037 (pdf)

Layout: Proinno Design Oy, Sodankylä
Cover photo: Markku Nummelin
Print: Kopijyvä Oy, Kuopio

Helsinki 2009

Foreword

The Finnish Rail Administration (RHK) publishes this Network Statement for the timetable period 2011. This is the eighth Network Statement prepared in Finland, in accordance with the Finnish Railway Act. The Network Statement describes the access conditions, the state-owned rail network, the allocation capacity, the services supplied to railway undertakings and the principles of determining the infrastructure charge. The Network Statement is published for applicants for capacity for each timetable period separately. The present Network Statement is intended for the timetable period 12.12.2010–10.12.2011.

The Network Statement 2011 has been prepared based on the previous Network Statement taking into account the feedback received from users and the Network Statements of other European Infrastructure Managers.

The structure of the Network Statement follows the common European structure and comprises the following chapters:

- 1 General
- 2 Access conditions
- 3 Rail network
- 4 Capacity allocation
- 5 Services supplied to railway undertakings
- 6 Infrastructure charge

During timetable period 2010 the Finnish Rail Administration, Finnish Road Administration and part of the Finnish Maritime Administration will be united to form the Finnish Transport Infrastructure Agency. The research and foundation work of the new agency are not finished at the time of publishing the Network Statement, and the changes they cause, for example, to different practices cannot be anticipated. Updates will be published on the Network Statement 2010 and 2011 websites.

Also the Finnish Rail Agency, Finnish Vehicle Administration, Finnish Civil Aviation Authority and part of the Finnish Maritime Administration will be united, and become the Finnish Transport Safety Agency in timetable period 2010. The establishment of this new agency will also affect the regulations, instructions and links to information sites mentioned in the Network Statement 2011. These updates can also be found on the Network Statement 2010 and 2011 websites.

In the Network Statement 2011 the new names Finnish Transport Infrastructure Agency and Finnish Transport Safety Agency are used instead of the old names Finnish Rail Administration and Finnish Rail Agency.

Within the Finnish Rail Administration, the Network Statement is the responsibility of the Traffic Management Unit. All the departments of the Finnish Rail Administration and several outside specialists have been involved in the preparation of the Network Statement.

Helsinki, 11 December 2009

Finnish Rail Administration

Traffic System Department,
Traffic Management Unit

Table of Contents

FOREWORD	3
1 GENERAL INFORMATION	7
1.1 Introduction	7
1.2 Objective	7
1.3 Legal Framework	7
1.4 Legal Status	7
1.4.1 General Remarks	7
1.4.2 Liability	7
1.4.3 Appeals Procedure	7
1.5 Structure of the Network Statement	8
1.6 Validity and Updating	8
1.6.1 Validity Period	8
1.6.2 Updating Process	8
1.7 Publishing	8
1.8 Contacts	8
1.9 RailNetEurope - International Co-operation between Infrastructure Managers	10
1.10 Glossary	11
2 ACCESS CONDITIONS	12
2.1 Introduction	12
2.2 General Access Requirements	12
2.2.1 General Requirements for Operating Railway Traffic	13
2.2.2 General Requirements for Access to the Rail Network	13
2.2.3 Operating Licence	14
2.2.4 Safety Certificate	14
2.2.5 Insurance	14
2.3 How to Apply for a Train Path	14
2.4 General Business Conditions	15
2.4.1 Framework Agreement	15
2.4.2 Access Contracts	15
2.5 Operational Rules	15
2.6 Exceptional Transport	15
2.7 Dangerous Goods	15
2.8 Rolling Stock Acceptance Process Guidelines	15
2.9 Staff Acceptance Process	16
3 INFRASTRUCTURE	17
3.1 Introduction	17
3.2 Extent of Network	17
3.2.1 Limits	17
3.2.2 Connected Railway Networks	17
3.3 Network Description	17
3.3.1 Geographic Identification	17
3.3.2 Capabilities	21
3.3.3 Traffic Control and Communications Systems	21
3.4 Traffic Restrictions	22

3.4.1	Specialised Infrastructure	22
3.4.2	Environmental Restrictions	22
3.4.3	Dangerous Goods.....	23
3.4.4	Tunnel Restrictions.....	23
3.4.5	Bridge Restrictions.....	23
3.5	Availability of the Infrastructure.....	23
3.6	Passenger Stations.....	23
3.7	Freight Terminals	23
3.8	Service Facilities	24
3.8.1	Train Formation Yards	24
3.8.2	Storage Sidings.....	24
3.8.3	Maintenance and Service Facilities	24
3.8.4	Refuelling Facilities	24
3.8.5	Technical Equipment.....	24
3.9	Infrastructure Development.....	24
4	CAPACITY ALLOCATION	25
4.1	Introduction	25
4.2	Description of Process	25
4.3	Schedule for Train Path Requests and Allocation Capacity Requests	26
4.3.1	Schedule for Working Timetable	26
4.3.2	Requesting Rail Capacity for Temporary Traffic	26
4.4	Allocation Process	27
4.4.1	Coordination Process.....	27
4.4.2	Dispute Resolution	27
4.4.3	Congested Infrastructure.....	27
4.5	Allocation of Capacity for Maintenance, Renewal and Enhancements	29
4.6	Non-usage Rules.....	29
4.7	Exceptional Transport and Dangerous Goods	29
4.8	Special Measures to be Taken in the Event of Disturbance	29
4.8.1	Principles	29
4.8.2	Operational Regulation.....	30
4.8.3	Foreseen Problems.....	30
4.8.4	Unforeseen Problems	30
5	SERVICES	31
5.1	Introduction	31
5.2	Services Offered by Finnish Transport Infrastructure Agency.....	31
5.3	Services Offered by Others	31
6	CHARGES	32
6.1	Charging Principles and Services Included in the Infrastructure Charge	32
6.2	Infrastructure Charge System	32
6.3	Tariffs	32
6.4	Performance scheme	32
6.5	Changes to Charges	32
6.6	Billing Arrangements	32

Index	33
-------------	----

Appendices

Appendix 1: Infrastructure Register.....	36
Appendix 2: Rail Traffic Operating Point Register	41
Appendix 3: Transport Operating Regulations for the Tornio-Haaparanta Section of Line	91
Appendix 4: Loading Gauge	99
Appendix 5: Structure Gauge	100
Appendix 6: Superstructure Categories, EN Categories and	101
Permitted Speeds for Different Axle Loads	
Appendix 7: Signalling Systems.....	110
Appendix 8: Vibration-related Speed Restrictions	115
Appendix 9: Maximum Train Speeds in Tunnels	116
Appendix 10: Bridge-related Restrictions.....	117
Appendix 11: Significant and Other Track Works Affecting traffic in 2011	118
Appendix 12: Passenger Information at the Stations of	121
the State-owned Rail Network	
Appendix 13: GSM-R (RAILI) Network.....	127
Appendix 14: Network Statements of Other Countries	128

1 General Information

1.1 Introduction

The Network Statement is published in accordance with the Railway Act (555/2006) and Directive 2001/14/EC of the European Parliament and of the Council on the allocation of railway infrastructure capacity and the levying of charges for the use of railway infrastructure and safety certification (hereinafter referred to as the "Capacity and Infrastructure Charge Directive"). The Network Statement for the timetable period 2011 is the eighth Network Statement published in Finland.

1.2 Objective

The Network Statement is published for the use of applicants for capacity for each timetable period separately. The Network Statement describes the access conditions, state-owned rail network, capacity allocation, services supplied to railway undertakings and the basis on which the infrastructure charge is determined. The Network Statement specifies in detail the general rules, deadlines, procedures and grounds applicable to capacity allocation and the charging systems.

Railway undertakings can request capacity for international traffic within the European Economic Area, as well as for domestic freight traffic. Domestic passenger traffic and transit traffic to Russia on the Finnish rail network may be operated only by VR-Group Ltd.

1.3 Legal Framework

Current Legislation

In accordance with the Railway Act, Finnish Transport Infrastructure Agency publishes information on the provisions of the Railway Act, as well as on the provisions issued under this Act and other provisions, concerning

- 1) the right of access to the rail network;
- 2) the principles of determining the infrastructure charges;
- 3) applying for rail capacity and the related deadlines;
- 4) the requirements for and approval of railway rolling stock; as well as
- 5) other conditions concerning operating and starting the operation of rail traffic.

Finnish Transport Infrastructure Agency publishes information on the nature and extent of the rail network in the Network Statement for each timetable period. This information is contained in Chapter 3 of this Network Statement. The provisions issued by Finnish Transport Infrastructure Agency on:

- 1) specialised infrastructure under the Railway Act (point 3.4.1)
- 2) the priority order to be applied to congested infrastructure under the Railway Act (point 4.4.3)
- 3) the threshold quota for the minimum use of railway infrastructure on each train path under the Railway Act (point 4.6) are also published in the Network Statement.

1.4 Legal Status

1.4.1 General Remarks

The Network Statement is not a regulation issued by Finnish Transport Infrastructure Agency but a document providing information.

1.4.2 Liability

Information published in the Network Statement does not affect regulations issued by Finnish Transport Infrastructure Agency or the Finnish Transport Safety Agency. Information on the third parties mentioned in the Network Statement may also change during the timetable period.

1.4.3 Appeals Procedure

A decision taken by Finnish Transport Infrastructure Agency may be appealed against under the Railway Act by filing a claim for rectification with the Regulatory Body, which in Finland is the Finnish Transport Safety Agency. A claim for rectification may be filed if the decision taken by the Regulatory Body concerns:

- 1) priority order for allocating capacity in individual cases
- 2) levying of the infrastructure charge
- 3) capacity allocation
- 4) allocation of urgently needed capacity
- 5) issuance of a safety certificate or
- 6) the access contract.

The claim for rectification shall be filed with the Finnish Transport Safety Agency within 30 days of the date of receipt of notice of the decision. The Finnish Transport Safety Agency shall decide on the claim for rectification within two months of the date on which all relevant information for taking a decision has been delivered to it. The decision shall, however, be taken within ten days of the date on which all relevant information has been delivered if the claim concerns the priority order in individual cases, capacity allocation or a request for urgently needed capacity.

1.5 Structure of the Network Statement

This Network Statement follows the common structure set for Network Statements by RailNetEurope.

The Network Statement consists of five more chapters in addition to this one. The second chapter deals with the requirements for accessing the Rail Network, the third handles the rail network infrastructure, the fourth covers issues related to capacity allocation, the fifth chapter is about services offered to railway undertakings, and the sixth chapter deals with the infrastructure charge and charging principles. The Network Statement includes appendices that provide a more detailed description of the rail network features and other issues related to rail traffic operations.

1.6 Validity and Updating

1.6.1 Validity Period

The Network Statement is valid for one timetable period. It is published four months ahead of the expiry of the deadline for submission of capacity requests that is 12 months ahead of the timetable period. The Network Statement 2011 is intended for the timetable period 2011, that is, for the period 12.12.2010–10.12.2011. The Network Statement for the timetable period 2012 will be published by 10.12.2010 at the latest.

1.6.2 Updating Process

If information contained in item 1.3 changes, Finnish Transport Infrastructure Agency will publish the changes in its publications.

The Appendix 11 of the Network Statement presents an estimate of the railway work that is to be done during the timetable period 2011 and which may affect traffic. The working programme, timing of tasks and the required railway work will change as the funding and plans become more focused. The Finnish Transport Infrastructure Agency will publish the list of railway work and maintain an updated version of the document on Network Statement website.

The agency changes mentioned in the preface may cause updates to the Network Statement and the Appendices after the printed version has been published. Updates will be published on Network Statement website.

1.7 Publishing

The Network Statement is published in three languages: Finnish, Swedish and English. If any discrepancies are found between the different language versions, the Finnish language version will prevail. The Finnish version of the Network Statement can be obtained in printed form from the Finnish Transport Infrastructure Agency and all language versions are available in PDF format on the Finnish Transport Infrastructure Agency's website.

Development plans for the rail network for 2011–2014 are presented in Finnish Transport Infrastructure Agency's action plan (TTS). Statistics concerning the rail network and railway traffic are presented in the annually published Finnish Railway Statistics.

1.8 Contacts

The information on the Finnish Transport Infrastructure Agency and the Finnish Transport Safety Agency, given in this Chapter, may change after the publication of the Network Statement. Any updated information will be available on the websites of the agencies concerned as well as in the Network Statement websites for 2010 and 2011.

Finnish Transport Infrastructure Agency


The Finnish Transport Infrastructure Agency operates under the auspices of the Ministry of Transport and Communications, assuming responsibility for maintaining and developing the state rail network, allocating rail capacity, conducting traffic control and directing traffic. The Finnish Transport Infrastructure Agency is also responsible for maintaining roads and developing and safeguarding the operating prerequisites of merchant shipping and other forms of waterborne traffic.

Finnish Transport Infrastructure Agency
Internet: <http://www.liikennevirasto.fi>

On matters regarding entering the market or railway traffic, e-mail can be sent to oss@liikennevirasto.fi.

Other contact information can be found on Finnish Transport Infrastructure Agency's website.

Finnish Transport Infrastructure Agency Organisation



Picture 1. Finnish Transport Infrastructure Agency's organisational chart.

Ministry of Transport and Communications

PO Box 31 (street address: Yliopistonkatu 5)
FI-00023 Valtioneuvosto


Telephone: +358 9 160 02
Fax. +358 9 160 28596
E-mail: kirjaamo@mintc.fi
Internet: <http://www.mintc.fi>

Finnish Transport Safety Agency

The Finnish Transport Safety Agency is charged with monitoring and developing railway safety and issuing instructions and regulations relating to flight and aviation safety as well as promoting road traffic safety and improving vehicle traffic information services. The Finnish Transport Safety Agency is also responsible for safety matters in connection with merchant shipping and other waterborne traffic.

Internet: <http://www.trafi.fi>

Finnish Transport Safety Agency organisation



Picture 2. Finnish Transport Safety Agency's organisational chart.

Finnish Competition Authority

The Finnish Competition Authority operates under the Ministry of Trade and Industry. Its objective is to protect sound and effective economic competition and increase economic efficiency by promoting competition and abolishing competition restraints.

P.O. Box 332 (street address: Pitkänsillanranta 3 A)
FI-00531 Helsinki

Telephone: +358 9 731 41
Fax.+358 9 7314 3328
E-mail: kirjaamo@kilpailuvirasto.fi
Internet: <http://www.kilpailuvirasto.fi>

1.9 RailNetEurope – International co-operation between Infrastructure Managers

In January 2004, the European railway infrastructure managers established a common organisation to shape the business of European rail infrastructure. RailNetEurope or RNE is an organisation whose goal is to promote international traffic in the European railway infrastructure and sell and market the railway capacity managed by its members.

Instead of engaging in bilateral or multilateral co-operation, the European railway infrastructure managers established a single organisation, RNE, to represent all of its members from the European perspective. The goal is to harmonise regulations and promote European rail traffic, and in so doing benefit every member.

RNE consists of 34 members, either full or associated members or candidates. All in all RailNetEurope partners serve a network of around 230,000 km railway infrastructure. Also a ferry line has joined the association and contributes to lowering the barriers in international rail traffic. RNE's main target group consists of customers engaging in international business. The Infrastructure Managers involved in RailNetEurope today take care of 120 customers dealing with international business and over 300 companies involved in national rail traffic.

The RNE members have set up One Stop Shops (OSS) working as a network of customer contact points. For international path requests, the customer needs to contact only one of these OSS, which will coordinate the whole international path allocation process.

One Stop Shop:

- Offers the customer support and information on the full product and service range of the Infrastructure Managers.
- Supplies all the information required to gain access to the infrastructure of any Infrastructure Manager participating in RNE.
- Handles requests for any international train path within RNE.
- Ensures that requests for the next timetable period are duly taken into account in the annual timetabling process.
- Provides train path offers for the whole international journey.

Each OSS contact is part of the international network aiming at making network access for customers as simple as possible. The OSS also provides information on infrastructure charges and train movements including quality monitoring. The OSS provides competent and efficient assistance across all borders, based on transparent, confidential and non-discriminatory procedures. The contact information of railway infrastructure managers' OSS contacts can be found on the RailNetEurope's Internet pages at <http://www.railneteurope.com>.

RailNetEurope members include:

- Administrador de Infraestructuras Ferroviarias (ADIF) (Spain)
- Banedanmark (Denmark)
- Banverket (BV) (Sweden)
- BLS AG (BLS) (Switzerland)
- Communauté de Transports – Accès Réseau (Luxembourg)
- Compania Natională de Căi Ferate SA (CFR) (Romania)
- DB Netz AG (Germany)
- Eurotunnel (France / England)
- Finnish Transport Infrastructure Agency (Finland)
- HZ Infrastructura d.o.o. (Croatia)
- Infrabel (Belgium)
- Jernbaneverket (JBV) (Norway)
- Keyrail (Netherlands)
- MÁV Magyar Államvasutak Zrt (MAV) (Hungary)
- National Manager of Railway Infrastructure (EDISY S.A.) (Greece)
- National Railway Infrastructure Company (NRIC) (Bulgaria)
- Network Rail (Great Britain)
- PKP Polskie Linie Kolejowe S.A. (PKP PLK) (Poland)
- ProRail B.V. (Netherlands)
- Public Agency for Rail Transport of RS (AŽP) (Slovenia)
- Raaberbahn AG/GYSEV Zrt. (GYSEV/Raaberbahn) (GYSEV/Raaberbahn) (Austria / Hungary)
- Rede Ferroviária Nacional E.P.E. (REFER) (Portugal)
- Réseau Ferré de France (RFF) (France)
- Rete Ferroviaria Italiana SpA (RFI) (Italy)
- Scandlines Deutschland GmbH (Germany/Sweden)
- Société Nationale des Chemins de fer Français (SNCF) (France)
- Správa Železniční dopravní cesty (CD)/SZCD (the Czech Republic)
- Swiss Federal Railways SBB-Infrastructure (SBB CFF FFS) (Switzerland)
- Slovenske zeleznice d.o.o. (ŠŽ) (Slovenia)
- Swiss Train Paths Ltd. (Trasse) (Switzerland)
- TP Ferro Concesionaria SA (Spain/France) Vasúti Pályakapacitás-celosztó Kft. (VPE) (Hungary)
- Železnice Slovenskej republiky (ŽSR) (Slovakia)
- ÖBB Infrastruktur Betrieb AG (Austria).

Network Statements of Other Countries

Internet addresses and names of Network Statements published by other rail network administrators are listed in Appendix 14.

1.10 Glossary

- **Coordination** refers to a procedure by which Finnish Transport Infrastructure Agency and the applicants attempt to solve situations where there are competing requests for rail capacity.
- **Engaging in railway traffic** refers to the traffic conducted by a railway undertaking or a museum train operator on the rail network.
- **Infrastructure maintenance** refers to construction, maintenance and development of tracks, of structures, equipment and systems connected with them, as well as of real property needed for infrastructure maintenance.
- **LIMO** refers to the Finnish Transport Safety Agency orders and instruction on rolling stock.
- **Museum train traffic** refers to traffic operated on a small scale on the rail network by a non-profit association with museum trains. Museum train refers to a stock registered as a museum train on the Finnish Transport Safety Agency's stock register.
- **Private siding** refers to a track other than state-owned track, which is connected to the rail network according to the private siding connection permit. The connection permit is provided by the Finnish Transport Infrastructure Agency.
- **Rail capacity** refers to the capacity of a train path to carry train traffic over a particular period and depending on the characteristics of the rail network.
- **Rail Network Description** refers to the technical characteristics of the Finnish rail network. The information published on the description are up-to-date on the date of publication, and describe the current state. Rail Network Description is published at least twice a year, at the beginning of June and December, on Finnish Transport Infrastructure Agency's website.
- **Railway undertaking** refers to a company or other association under private law whose main activity is to operate rail traffic. The company must have an appropriate operating licence issued in the European Economic Area and possess the rolling stock needed for operating traffic. Undertakings providing only traction services are also regarded as railway undertakings.
- **RATO** refers to railway track's technical instructions, which include basic information on development, inspection and maintenance of a track and its equipment. RATO is published by the Finnish Transport Infrastructure Agency.

- **The Advance Information System (ETJ)** is a system, which includes the advance plans of railway work and information on changes affecting traffic. Otherwise, these would have to be delivered by a traffic control message.
- **Traffic control** is the management of traffic on individual train paths. In addition traffic control duties include issuing permits and notices required for train traffic. Traffic control also includes protecting the railway work areas, issuing permits for railway work and receiving information on the termination of such work. If so required due to the volume of traffic and safety apparatus a signals or turnout worker, shunting foreman, engine driver or a worker responsible for the safety of work done near the tracks or other person appointed in due order for the task may participate in traffic control to the extent required by their task.
- **TURO** refers to safety instructions in track maintenance. The Finnish Transport Infrastructure Agency publishes the instructions on its website.

Other, more detailed, definitions can be found in RATO (Railway track technical instructions).

2 Access Conditions

2.1 Introduction

Access requirements to the rail network are listed in this chapter. The prerequisites for operating railway traffic are an operating licence, safety certificate or museum traffic operator's licence, allocated capacity and an access contract. In addition, for example, the rolling stock acceptance process and traffic safety staff qualifications are described in this chapter.

2.2 General Access Requirements

The legal framework of access to infrastructure is described in the Railway Act (555/2006). The provisions issued by the Finnish Transport Safety Agency and Finnish Transport Infrastructure Agency shall be observed on the state-owned rail network. Information on the provisions and instructions issued by the Finnish Transport Safety Agency and Finnish Transport Infrastructure Agency currently in force is available from the Finlex Data Bank, <http://www.finlex.fi>.

The Act on safety and interoperability of the rail system (750/2006) lays down, for example, the essential requirements for the rail system. The essential requirements can be supplemented with separate provisions.

ATP engine equipment must be used in train traffic or, if operating without ATP engine equipment, an exceptional permit as referred to in section 28(5) of the Railway Act (555/2006) is compulsory. The Finnish Transport Safety Agency may grant an exceptional permit provided that it does not endanger the safety of the railway system. In cases concerning the use of ATP engine equipment, a fixed-term exceptional permit may be granted if the case involves a need for exceptional and temporary train operation or if ATP engine equipment or spare parts are not available. An exceptional permit may not be granted for a train unit or engine which is used in passenger or commercial freight traffic, when it is not directly connected with track maintenance. ATP engine equipment is not required in stock that is used for shunting only. Museum stock can be operated on part of the rail network without automatic train safety equipment. The sections of line, on which the automatic train safety equipment is obligatory, are listed in Finnish Transport Safety Agency's museum train traffic regulation (RVI/295/411/2008). Further information is given by the Finnish Transport Safety Agency.




Figure 2. Phases for entering the market

2.2.1 General Requirements for Operating Railway Traffic

Operation of rail traffic on the state-owned rail network requires that the railway undertaking meet the following conditions:

- 1) The railway undertaking or international grouping of railway undertakings shall have an operating licence in accordance with the Railway Act or a corresponding operating licence issued in the European Economic Area, unless the question is of museum train traffic referred to in the Railway Act.
- 2) The licence holder shall have a safety certificate in accordance with the Railway Act, issued or approved by the Finnish Transport Safety Agency, which covers all the train paths on which traffic will be operated.
- 3) Capacity in accordance with the Railway Act has been allocated to the railway undertaking for its traffic.
- 4) The licence holder shall make an access contract with Finnish Transport Infrastructure Agency on necessary practical arrangements concerning the operating of railway traffic.
- 5) Other conditions for operating rail traffic, laid down in or under the Railway Act are in all respects fulfilled.

Access conditions and phases for entering the market are presented in Figure 2.

Museum Traffic

The same requirements described in this Network Statement are applied to museum train traffic as to other rail traffic, except with regard to the operating licence. The law provides that a museum traffic operator must have an operating licence granted by the Finnish Transport Safety Agency, and that the licence corresponds with the railway undertaking's safety certificate. The operating licence will be granted upon application for a maximum of five years at a time. The prerequisite for granting the operating licence is that the museum traffic operator has sufficient liability insurance and risk management system, their rolling stock has been approved by the Finnish Transport Safety Agency, and the persons attending to the traffic operation possess the required competence.

Capacity may be requested only as ad hoc capacity. Finnish Transport Infrastructure Agency has drawn up instructions for museum train traffic operators for attending to certain matters regarding access to the network.

ATP engine equipment must be used in train traffic or, if operating without ATP engine equipment, an exceptional permit as referred to in section 28(5) of the Railway Act (555/2006) is compulsory. The Finnish Transport Safety Agency may grant an exceptional permit provided that it does not endanger the safety of the railway system. In cases concerning the use of ATP engine equipment, a fixed-term exceptional permit may be granted if the case involves a need for exceptional and temporary train operation or if ATP engine equipment or spare parts are not available. An exceptional permit may not be granted for a train unit or engine which is used in passenger or commercial freight traffic, when it is not directly connected with track maintenance. ATP engine equipment is not required in stock that is used for shunting only. Museum stock can be operated on part of the rail network without automatic train safety equipment. The sections of line, on which the automatic train safety equipment is obligatory, are listed in Finnish Transport Safety Agency's museum train traffic regulation (RVI/295/411/2008). Further information can be obtained from the Finnish Transport Safety Agency.

2.2.2 General Requirements for Access to the Rail Network

The following railway undertakings or international groupings of railway undertakings may access the state rail network to operate train traffic:

- 1) the railway undertakings and international groupings of railway undertakings referred to in the Railway Act providing domestic freight services or passenger services in international rail traffic between states belonging to the European Economic Area
- 2) the rail transport operating subsidiary of the limited company referred to in the Act on the Incorporation of the Finnish State Railways (20/1995) for providing services in domestic passenger traffic, as well as in traffic between Finland and Russia.

These railway undertakings and international groupings of railway undertakings may use the rail network in accordance with the Railway Act and the traffic operating points on the state-owned rail network for their traffic operating on separately agreed conditions (access contract). Other undertakings or associations may also use individual traffic operating points on the rail network for their rail services, provided that this traffic serves a private siding connected to a traffic operating point and that an agreement on traffic operating has been made with Finnish Transport Infrastructure Agency.

2.2.3 Operating Licence

The Ministry of Transport and Communications issues an operating licence for the operation of rail traffic to applicants established in Finland. The granted operating licence is valid for the time being and the Ministry reviews the operating licence and its conditions every five years. An operating licence issued in one state belonging to the European Economic Area is valid throughout the territory of the European Economic Area. An operating licence granted elsewhere must be delivered to the Ministry of Transport and Communications for information.

The prerequisite for granting the operating licence is that the main activity of the undertaking is to operate rail traffic. The undertaking must also have a safety certificate issued or approved by the Finnish Transport Safety Agency, a solid financial standing, a competent management team and a sufficient liability insurance. The application for an operating licence is delivered to the Ministry of Transport and Communications.

2.2.4 Safety Certificate

The safety certificate is issued by the national safety authority. In Finland, it is issued by the Finnish Transport Safety Agency.

If a railway undertaking has been granted part A of the safety certificate in another country belonging to the European Economic Area, it must apply to the Finnish Transport Safety Agency for part B of the safety certificate before it can commence train operations or track maintenance in Finland.

The safety certificate will be granted or approved for a maximum of five years at a time. The undertaking must apply for a new safety certificate as soon as its old certificate is no longer valid.

The safety certificate comprises two parts. Part A approves the safety management system, while part B accepts the documents and arrangements that the holder of the safety certificate has issued and put in place that indicates that the set requirements are fulfilled.

The purpose of the safety certificate is to ensure that the applicant fulfills the safety requirements for its operations and that the undertaking has the necessary qualifications to operate safely on the rail network. These requirements are presented in the Railway Act. It is also possible to include other requirements in the safety certificate regarding railway

safety. The purpose of these requirements is to ensure railway safety while taking into consideration the nature and scope of the railway traffic of the applicant. The aforementioned requirements are presented in more detail and explained in the instructions on how to apply for a safety certificate drawn up by the Finnish Transport Safety Agency.

The Finnish Transport Safety Agency requires information on:

- the applicant's safety management system's compliance with regulations
- the applicant proves that it fulfils those rules and regulations on the use of the rail network that concern that part of the network where it intends to operate or engage in traffic operation and the applicant shows that it can safeguard compliance with the rules and regulations,
- the applicant proves that its staff groups and the staff groups of the subcontractor that it uses are appropriately trained and competent in their duties in accordance with the relevant regulations [concerning the network];
- the applicant proves that the rolling stock that it uses complies with the relevant regulations [concerning the network] and that the maintenance and servicing of the rolling stock are in order.

The Finnish Transport Safety Agency has drawn up instructions on how to apply for a safety certificate. The form used to apply for the safety certificate can be obtained from the Finnish Transport Safety Agency. The written application shall be submitted to the Finnish Transport Safety Agency. The Finnish Transport Safety Agency shall consider the application and if necessary request further information. The Finnish Transport Safety Agency shall decide on the issuance or approval of the safety certificate within four months after the request has been filed. However, the matter shall be resolved within twelve months of the application even if all the necessary information has not been lodged. The Finnish Transport Safety Agency may grant a safety certificate for the entire state rail network or individual train paths. If the rules or regulations on the safety of the railway system are essentially amended, the agency may review the certificate or part thereof. If the operation of the holder of the safety certificate alters essentially in nature or extent, it shall re-apply for approval of the safety certificate insofar as the change has an effect on the terms and conditions of the safety certificate.

2.2.5 Insurance

A rail transport operator shall have sufficient liability insurance or other corresponding arrangement in case of such damage incurred by a party due to rail transport operations for which the operator is by law or contract responsible. The nature and scope of operations and risks related to the operations must be taken into account in evaluating the sufficiency of the insurance or a similar arrangement. The insurance or other corresponding arrangement shall be in force for the duration of the entire period during which rail transport is operated.

2.3 How to Apply for a Train Path

A railway undertaking has to meet the following criteria to apply for rail capacity:

- The undertaking shall have an operating licence in conformity with the Railway Act or a corresponding licence issued in the European Economic Area unless it is a question of museum traffic referred to in the Railway Act.
- The undertaking shall, in compliance with the Railway Act, have a safety certificate for all the train paths on which the undertaking is planning to operate.

Applying for rail capacity and capacity allocation are described in Chapter 4 of the Network Statement.

2.4 General Business Conditions

2.4.1 Framework Agreement

Finnish Transport Infrastructure Agency may make a framework agreement on the use of capacity with applicants for capacity. The purpose of such an agreement is to specify the characteristics of the capacity requested by the applicant. The framework agreement does not, however, entitle the applicant to obtain such capacity as is specified in the agreement.

Railway undertakings shall request the capacity specified in the framework agreement for each timetable period separately. If requested, Finnish Transport Infrastructure Agency allocates the capacity specified in the framework agreement following the procedure laid down in the Railway Act. Correspondingly, the access contract shall be concluded for each timetable period separately regardless of the framework agreement. The framework agreement does not, however, impede the application of the provisions of the Railway Act to other applicants for capacity.

The framework agreement is made for a maximum of five years. For special reasons, Finnish Transport Infrastructure Agency may, however, also conclude framework agreements for a longer period. Conclusion of an agreement for more than five years can, however, be justified only by contracts, special investments or special business risks connected with the transport business of the party with which the agreement is concluded, as well as by the large-scale and long-term investments of the party with which the agreement is concluded or the contractual obligations connected with such activities.

2.4.2 Access Contracts

Railway undertaking and museum traffic operator shall make an access contract with Finnish Transport Infrastructure Agency on the use of necessary services with regard to the state rail network and operating railway traffic. These services include, for example, the use of marshalling yards, storage sidings and other tracks, as well as use of traffic control services. It is also possible to agree on other practical arrangements concerning railway traffic operations.

The railway traffic operator shall contact Finnish Transport Infrastructure Agency to prepare the access contract and contractual negotiations as early as possible, preferably before applying for capacity. Finnish Transport Infrastructure Agency makes this contract with each licence holder while taking into account the nature and scale of capacity allocated. The access contract is made for each timetable period and can be changed if decisions made during the timetable period concerning the allocation of capacity or other facts, for example, concerning the condition of the rail network so require. The access contract can only be concluded after all conditions stipulated in the Railway Act for operating railway traffic have been fulfilled. After the contract has been concluded, traffic may begin.

2.5 Operational Rules

Operational rules drafted by Finnish Transport Infrastructure Agency can be viewed on the Finnish Transport Infrastructure Agency website and legislative information on the Finlex website.

2.6 Exceptional Transport

Traffic restrictions are dealt with in item 3.4 and in Appendix 6. Regulations concerning railway traffic and rolling stock can be viewed on the Finlex website and other instructions on the Finnish Transport Safety Agency and Finnish Transport Infrastructure Agency websites.

An exceptional transport permit is granted by the Finnish Transport Infrastructure Agency. For more information, please visit the agency's website.

2.7 Dangerous Goods

Transport of dangerous goods is dealt with in item 3.4.3. Regulations concerning railway traffic and rolling stock can be viewed on the Finlex website and other instructions on the Finnish Transport Safety Agency and Finnish Transport Infrastructure Agency websites.

2.8 Rolling Stock Acceptance Process Guidelines

An authorisation issued by the Finnish Transport Safety Agency is required for placing rolling stock in service. This authorisation can be issued for rolling stock that meets the requirements valid in Finland, which is laid down in legislation.

The requirements are based on the interoperability requirements for the rail system in accordance with Community law and the Finnish Transport Safety Agency has issued complementary and more detailed instructions. Conformity can be proved by the EC Declaration of Conformity or a corresponding declaration issued within the European Economic Area. Before issuing the authorisation, the Finnish Transport Safety Agency will ask for the Finnish Transport Infrastructure Agency's statement on stock type's or unit's suitability for rail network, in order to define possible restrictions.

The Finnish Transport Safety Agency maintains a register used to monitor the validity and traffic safety of rolling stock. The purpose is to promote railway system safety and identify rolling stock. The rolling stock is recorded in a register maintained by the Finnish Transport Safety Agency, if the rolling stock has been granted a commissioning licence in Finland. Rolling stock that will be used on the state's rail network and has been granted a commissioning licence elsewhere within the European Economic Area or in a country outside the EEA must also be recorded in the register. Any rolling stock used on private sidings will also be recorded in the register.

The Finnish Transport Safety Agency can also register rolling stock for a limited time upon request. A fixed-period registration is also possible for any rolling stock that has been granted a commissioning licence in another country, if it has been granted a commissioning licence in Finland and is used on the state's railway network only temporarily.

The rolling stock register must include information on the owner, holder and renter of the rolling stock. The more detailed regulations on related information on other rolling stock to be recorded in the register will be set forth in a Council of State decree.

With regards to any rolling stock used for rail traffic between Finland and Russia, the register must include information on the vehicle owner or renter, any possible limitations on the vehicle use and information on the vehicle's maintenance plan in so far as is essential to the vehicle safety.

The Finnish Transport Safety Agency provides more detailed information about the requirements and other matters related rolling stock.

As from 1 January 2010, the Finnish Transport Infrastructure Agency shall approve any rolling stock that is used solely for track work. If at any stage the rolling stock is used as a train, the stock shall be approved by the Finnish Transport Safety Agency.

2.9 Staff Acceptance Process

Traffic safety staff shall meet the health, training and other qualification requirements laid down in Finnish legislation. Specific provisions on qualifications are laid down in the Traffic Safety Tasks Act which came into force on 1.1.2005. The Act lays down qualification requirements for personnel working with traffic safety tasks which have a direct impact on rail traffic safety. Those working in these tasks shall also meet the Finnish Transport Safety Agency requirements concerning health, training and other qualifications. The qualification requirements vary depending on the job.

Before the Finnish Transport Safety Agency issues or approves a safety certificate, the railway operator shall provide it with information on the qualifications of its traffic safety staff. A museum traffic operator must provide the Finnish Transport Safety Agency with the corresponding information for issuing the operating licence. If necessary, the Finnish Transport Safety Agency may upon issuing the safety certificate or operating licence examine in other ways and in more detail whether a person or persons employed by the railway traffic operator or otherwise connected to his or her operation meets the set qualifications.

3 Infrastructure

3.1 Introduction

The infrastructure refers to the state-owned rail network managed by Finnish Transport Infrastructure Agency. Finnish Transport Infrastructure Agency is responsible for infrastructure maintenance that is, for the construction and maintenance of tracks, of structures and equipment connected with them, as well as of real property needed for infrastructure maintenance.

3.2 Extent of Network

3.2.1 Limits

The available network is presented graphically in Figure 3 (state-owned rail network in the beginning of timetable period 2011) and in Appendix 1 (Infrastructure Register).

The following line sections are closed to traffic:

- Kankaanpää–Niinisalo
- Kihniö–Aitoneva
- Pesiökylä–Taivalkoski
- Kolari–Äkäsjoki
- Niesa–Rautuvaara.

Maintenance has been cancelled until further notice:

- Lautiosaari–Elijärvi
- Kiukainen–Säkylä

All changes will be published on the Finnish Transport Infrastructure Agency website.

3.2.2 Connected Railway Networks

There is a rail connection from Finland to Sweden via Tornio. The main outlines of traffic operating on the Tornio–Haaparanta line section are presented in Appendix 3. The Swedish infrastructure manager is Banverket.

Appendix 3 will be updated. The updated appendix will be published on the Network Statement website and Finlex.

A rail connection exists from Finland to Russia via Vainikkala, Imatranksi, Niirala and Vartius. Rail traffic between Finland and Russia is based on the Rail Traffic Agreement between Finland and Russia. Traffic between Finland and Russia is not internal international traffic within the European Economic Area. Only VR-Group Ltd has access to the Finnish rail network in traffic between Finland and Russia.

3.3 Network Description

3.3.1 Geographic Identification

3.3.1.1 Track Typologies

The network is presented in Figure 3 (rail network map) and in the infrastructure register (Appendix 1).

3.3.1.2 Track Gauges

The nominal track gauge on the rail network 1,524 mm. The speed-dependent limit values for the track gauge are indicated in the Rata tekniset ohjeet (RATO) publication, part 13 "Radan tarkastus" (Track inspection).

3.3.1.3 Stations and Nodes

The available traffic operating points (stations) are presented in Figure 4 (rail traffic operating points) and in Appendix 2 (Rail Traffic Operating Point Register).




Figure 3. State-owned rail network at the beginning of timetable period 2011.

- Liikennepaikka tai sen osa
Trafikplats eller dess del
Station or its part
 - Linjavaihde
Linjeväxel
Turnout in the open line
 - Seisake
Hållplats
Stopping point
 - Yksityinen rata
Privat bana
Private line
 - Museorata
Museibana
Museum line




Figure 4. Traffic operating points on the state-owned rail network at the beginning of timetable period 2011.




Figure 5. Trans-European Rail Network in Finland (The Finnish TEN network)

3.3.2 Capabilities

3.3.2.1 Loading Gauge

The loading gauge (KU), Appendix 4, and the structure gauge (ATU), Appendix 5, are used throughout the state-owned rail network. On private industrial sidings, there may be both loading and structure gauge limitations, which railway undertakings shall clarify separately for carrying out transportation.

The vehicle gauge (LKV) is specified in the Finnish Transport Safety Agency's LIMO publication, point 1 "Yleiset määritykset" (General rules).

3.3.2.2 Weight Limits

Axle Loads

22.5 ton axle loads are permitted on most of the rail network. The maximum permitted axle loads per line section are indicated in Appendix 6 (Superstructure Categories, EN Categories and Permitted Speeds for Different Axle Loads).

The same appendix specifies the axle loads and restrictions in connection with overweight loads and the wagons used in the rail connection to the east.

Metre Loads

The permitted metre load of rolling stock throughout the state-owned rail network is 8.0 tons/m.

3.3.2.3 Line Gradients

The maximum gradient is 20 mm/m on the main lines and 22.5 mm on the secondary lines. The maximum gradient of sections of line measured over a distance of 1,200 metres is presented in Appendix 1 (Infrastructure Register).

3.3.2.4 Line Speeds

The maximum speed is 220 km/h for passenger trains and 120 km/h for freight trains. The speeds permitted for passenger and freight trains on the rail network are indicated in Appendix 6 (Superstructure Categories, EN Categories and Permitted Speeds for Different Axle Loads).

3.3.2.5 Maximum Train Lengths

The maximum train length permitted on a line section shall be such that trains can also use secondary tracks at the traffic operating points. Trains need not, however, be capable of using all secondary tracks at all traffic operating points. The train lengths used for dimensioning line sections are 550, 625, 725, 825 and 925 metres. The longest secondary tracks at each traffic operating points are indicated in Appendix 2 (Rail Traffic Operating Point Register).

3.3.2.6 Power Supply

The nominal voltage of the electrification is 25 kV/50 Hz AC. On all electrified lines, power is taken from the contact line above the track. One or both of the running rails and return conductors form a return circuit. The neutral sections will be located at the overhead line near substations. Rolling stock cannot collect current from these neutral sections. The main switch of locomotive/electric train must be opened at the neutral sections. The train is not allowed to stop at a neutral section.

The maximum zigzag of the contact wire is 400 mm. The contact wire height can vary from 5600 to 6500 mm. The normal height is 6150 mm the electrified line sections are indicated in Appendix 1 (Infrastructure Register).

For fixed installations, electrification is described in part 5 "Sähköistetty rata" (Electrified railway) of the Ratatekniset ohjeet (RATO) publication, and for the electric equipment of rolling stock in the LISO publication.

3.3.3 Traffic Control and Communications Systems

3.3.3.1 Signalling Systems

The signalling systems in use are indicated in Appendix 1 (Infrastructure Register) and graphically in Appendix 7 (Signalling Systems).

A line with section block is a line divided into block sections. Only one train may be in a block section at a time. Issues related to section blocks are presented in RATO publication, part 6 "Turvalaitteet" (Signalling systems).

Hot box detectors have been placed on the rail network at 50 km intervals on line sections on which the greatest speed is or can be over 160 km/h. In addition hot box detectors have been placed near the busiest junction stations. A map of the location of the hot box detectors is presented in Appendix 7.

3.3.3.2 Traffic Control Systems

The line sections equipped with an automated traffic control system are indicated in Appendix 1 (Infrastructure Register) and in Appendix 7 (Signalling Systems). The following automated traffic control systems are used: centralised traffic control and radio control. On the CTC- and radio-controlled lines, all routes are equipped with the remote control of points and routes. On the secondary, loading and storage sidings of these line sections, however, local route setting may also be necessary. On radio-controlled lines, routes shall be set locally if it is necessary to operate on secondary, loading or storage sidings.

3.3.3.3 Communications Systems

The Finnish Transport Safety Agency sets regulations on, for example, traffic operation, railway work and communications. The valid regulations can be obtained at the Finnish Transport Safety Agency website.

Finnish Transport Infrastructure Agency provides working instructions that deal with traffic control, traffic operation, railway work and communications, and complement the regulations. The valid working instructions can be obtained at the Finnish Transport Infrastructure Agency website. Contact information for traffic control can be obtained at the Finnish Transport Infrastructure Agency Extranetsite.

Information of abnormal events or situations will be provided via the Advance Information System, maintained by Finnish Transport Infrastructure Agency, and through notifications given by the traffic control. Drivers and persons responsible for the railway work must have knowledge of the advance plans that are valid for the duration of the work/journey and in the working area/track sections of the journey. They must also have the contact information for the traffic control.

Finnish Transport Infrastructure Agency tries to record the verbal communication between the traffic control, traffic operators and railway workers, i.e. permits and notifications, in the most comprehensive manner possible. The authorities will use these recordings for examining accidents and dangerous situations.

A new communications system, RAILI Network, was taken into use on the state-owned rail network at the end of 2008. Its key element is a new GSM-R radio network, which complies with the technical railway interoperability specifications of the European Union. The old analogue radio networks (railway yard and line radio networks) will be abandoned once RAILI is fully implemented. The GSM-R radio network will cover most of the state-owned rail network. Some track sections will remain outside the RAILI network. Detailed quality information can be found in the map of the RAILI network design standards and appendix 13. More information can be found on the Finnish Transport Infrastructure Agency's website.

Traffic control, railway undertakings and contractors must use the RAILI network as their primary communications channel. If RAILI network cannot be used for a technical reason or poor GSM-R radio network reception, the parties must use other available phone or mobile phone networks. The traffic control, and also train drivers, shunting managers and persons responsible for the railway work must be informed of any faults preventing or hindering the use of RAILI network, and alternative contact information in accordance with the communications instructions.

3.3.3.4 Other systems

Many of the larger stations have camera surveillance. The system allows traffic controllers to monitor the movement of trains and the Information Centre to observe the movement of passengers on platforms as well as the technical functioning of the information equipment. The Safety Centre is able to monitor passenger safety and control vandalism. Property maintenance, for its part, can use the system to check on the tidiness of platform areas and spot any need for maintenance work.

3.3.3.5 ATP Systems

Automatic train protection (ATP) is a system that controls the speed of a train.

ATP engine equipment must be used in train traffic or, if operating without ATP engine equipment, an exceptional permit as referred to in section 28(5) of the Railway Act (555/2006) is compulsory. The Finnish Transport Safety Agency may grant an exceptional permit provided that it does not endanger the safety of the railway system. In cases concerning the use of ATP engine equipment, a fixed-term exceptional permit may be granted if the case involves a need for exceptional and temporary train operation or if ATP engine equipment or spare parts are not available. An exceptional permit may not be granted for a train unit or engine which is used in passenger or commercial freight traffic, when it is not directly connected with track maintenance. ATP engine equipment is not required in stock that is used for shunting only. Further information can be obtained from the Finnish Transport Safety Agency.

3.4 Traffic Restrictions

3.4.1 Specialised Infrastructure

Finnish Transport Infrastructure Agency may designate a train path or a part of it as specialised infrastructure, if there are sufficiently alternative routes for other traffic. Specialised infrastructure refers to a train path or a part of it on which priority is given to the type of traffic for which the infrastructure is specialised. So far Finnish Transport Infrastructure Agency has not designated any line section in Finland as specialised infrastructure.

3.4.2 Environmental Restrictions

The requirements laid down in the Finnish Transport Safety Agency's LIMO publication are applied when registering rolling stock. LIMO sets out general and special requirements for rolling stock concerning noise, vibration, electromagnetic interferences, emissions, environmentally dangerous substances and the use of recycled construction materials.

Vibration-related speed restrictions are imposed on parts of the railway line on fifteen line sections throughout Finland. The restrictions mainly apply to over 3,000 ton gross weight heavy trains (Appendix 8).

3.4.3 Dangerous Goods

Finland has signed the intergovernmental OTIF Convention, which regulates international rail traffic. Russia and other CIS countries have not acceded to the OTIF Convention. Carriage of dangerous goods by rail between Finland and Russia as well as transport of such goods via Russia to CIS countries and from those countries to Finland is subject to the regulations specified in appendix 8 of the transportation tariff included in the agreement (Treaty Series 1/1948 of the Finnish Statute Book) concluded for the rail traffic between Finland and Russia.

Appendix C of the OTIF Convention lays down the provisions on the carriage by rail of dangerous goods (RID). As they stand, the RID regulations govern the international rail transportation of dangerous goods within the territories of member states that have acceded to the OTIF Convention. Rail transport of dangerous goods within Finland is subject to the national statutes which enforce the RID framework directive (2008/68/EC) in Finland.

The most important differences compared to the RID regulations are as follows: cold resistance requirement for certain packaging and tanks in domestic traffic is -40°C (RID -18 and -20°C); as well as the regulations concerning protection wagons and the bringing of wagons loaded with explosives to traffic operating points and the temporary storage of explosives. The decree of the Ministry of Transport and Communications also takes into account the requirements of the VOC directive (94/63/EC) concerning the recovery of vapours from petrol in connection with rail transport.

No absolute restrictions have been imposed on the transport of dangerous goods if carried out according to the regulations. It is recommended that wagons loaded with dangerous goods should not be parked in densely populated or groundwater areas. The transport of dangerous goods on tracks with spike fastening or laid with 43 kg rails shall be avoided.

It is prescribed by Government decree that railway undertakings shall carry out a safety analysis for railway yards through which considerable quantities of dangerous goods are carried. The decree defines, for example, the following: The Finnish Transport Safety Agency defines those rail yards for which the safety analysis must be carried out. The Finnish Transport Infrastructure Agency may define the form of the safety analysis. The Finnish Transport Infrastructure Agency organises co-operation between railway companies in order to carry out the safety analysis. The safety analysis shall be submitted to the local rescue and environmental authorities

for an opinion. The safety analysis shall be submitted to the Finnish Transport Infrastructure Agency, which delivers it further for approval. The safety plan is approved by the Finnish Transport Safety Agency.

3.4.4 Tunnel Restrictions

There are tunnel restrictions on the Helsinki–Turku and Orivesi–Jyväskylä line sections. The restrictions are indicated in Appendix 9.

Only freight trains and stock required in track work are allowed to operate in tunnels on the Vuosaari line. It is forbidden to take passengers through the tunnels on Vuosaari track. Only electric freight traffic is allowed. Individual diesel engine transfers are permitted.

In the Savio tunnel the train driver must have an oxygen apparatus and the machinery must be fitted with oxygen equipment.

3.4.5 Bridge Restrictions

Bridge restrictions are described in Appendix 10.

3.4.6 Overweight load transport

Appendix 6 details the axle loads and restrictions applicable to the carriage of overweight loads and wagons used in rail connections to the east.

3.5 Availability of the Infrastructure

Other restrictions than those listed in item 3.4 are described in Rail Network Description and in the Advance Notification System. Track work causing traffic restrictions is presented in Appendix 11. The Rail Network description can be found on Finnish Transport Infrastructure Agency's website.

The substations of the electric railway have a limited capacity for supplying power to the contact line. The power supply will shut down automatically in overload situations, which will cause a temporary power failure in the contact line.

3.6 Passenger Stations

The lengths of passenger platforms (shortest/longest) are indicated in Appendix 2 (Rail Traffic Operating Point Register). The platforms not maintained by Finnish Transport Infrastructure Agency are indicated in brackets.

3.7 Freight Terminals

Loading possibilities are indicated in Appendix 2 (Rail Traffic Operating Point Register). K means "yes" and Y "private". For loading platforms, the register lists their available length.

Private siding connections at traffic operating points are indicated by the marking "Private sidings" in Appendix 2 (Rail Traffic Operating Point Register).

3.8 Service Facilities

3.8.1 Train Formation Yards

Train formation yards are railway yards in which the layout and size of the track system make it possible to form trains. The train formation yards are indicated by the marking "Shunting" in Appendix 2 (Rail Traffic Operating Point Register).

All train formation yard tracks have not been electrified. If necessary, Finnish Transport Infrastructure Agency's Rail Data Unit provides more information on the electrified tracks.

3.8.2 Storage Sidings

Storage sidings are yard tracks primarily intended for the parking of wagons and coaches waiting for a transport task. Storage sidings can also be used for other purposes required by traffic operating. The local traffic control centre determines which tracks are used as storage sidings.

3.8.3 Maintenance and Service Facilities

The 400 and 1,500 V power supply facilities for rolling stock are indicated in Appendix 2 (Rail Traffic Operating Point Register). Also for the 400 V power supply, the maximum current available is indicated in amperes. The use of maintenance and service facilities requires an agreement with their owner.

3.8.4 Refuelling Facilities

The Finnish Transport Infrastructure Agency does not own refuelling equipment or provide refuelling services. The Appendix 2 (Rail Traffic Operating Point Register) shows the refuelling facilities on traffic operating points. The use of refuelling facilities requires an agreement with their owner.

3.8.5 Technical Equipment

The use of other technical equipment (e.g. scales, cranes, etc.) must be agreed with their respective owners. The Finnish Transport Infrastructure Agency does not provide this equipment for railway companies to use. The Appendix 2 (Rail Traffic Operating Point Register) shows the cranes located on traffic operating points.

3.9 Infrastructure Development

Rail network development plans are presented in Finnish Transport Infrastructure Agency's Action and Financial plan for the years 2011–2014. The Action and Financial Plan period will see a focus on the enhancement of traffic control safety and flexibility in railway yards by introducing new automation technology. Old traffic control safety equipment will be replaced in Kuopio, Siilinjärvi and Iisalmi. Old remote control systems will be replaced on line sections Pieksämäki–Iisalmi and Seinäjoki–Ylivieska. Work will be commenced to replace the remote control mechanism on the Parikkala–Joensuu line section. Rail network development projects in the Action and Financial Plan period will include Phase I of Seinäjoki–Oulu (possibly including the continuation project), Keski-Pasila, Ring Rail, Kokkola–Ylivieska double track and the electrification of the Rovaniemi–Kemijärvi line section.

The development plans for the years beyond the period covered by the Action and Financial Plan are presented in the “Rail Network 2030” report. The publication was in the process of being updated when the Network Statement went into print. For more information, please visit the Finnish Transport Infrastructure Agency's website.

The Finnish Transport Infrastructure Agency adopted a new environmental strategy in 2009. It outlines the focuses of environmental work from 2009 to 2013. Climate and energy issues will be emphasised more than before. Noise and vibration issues together with protection of soil and groundwater are still significant. Finnish Transport Infrastructure Agency aims at improving its eco-efficiency by better follow-up of material use and further developing recycling. Part of the strategy work is developing extensive, organisation-wide instructions on environmental issues.

4 Capacity Allocation

4.1 Introduction

The legal framework of capacity allocation is described in the Railway Act (555/2006) and in the Government Decree on the Timetable Period in Rail Traffic and Applying for Infrastructure Capacity (751/2006).

4.2 Description of Process

Capacity for operating regular train services on the state-owned rail network shall be requested from Finnish Transport Infrastructure Agency for each timetable period within the time defined. Capacity for regular train services can also be requested during the timetable period. The schedule for train path requests and for allocation is shown in a diagrammatic form in Figure 6. It is also possible to make ad hoc requests for capacity for other than regular traffic.

Requesting Rail Capacity

The principles of capacity requests are described in the Railway Act (555/2006) and in the Council of State Decree on the Timetable Period in Rail Traffic and Applying for Infrastructure Capacity (751/2006). In order to specify the Act and Decree, the Finnish Transport Infrastructure Agency has drawn up a regulation for requesting rail capacity. The regulation and its detailed schedule and information on possible changes to rail capacity request procedures can be obtained from the Finnish Transport Infrastructure Agency's Railway Department. The same information is available also on the Finnish Transport Infrastructure Agency's website.

The LIIKE information system shall be deployed to apply for rail capacity and for alterations to regular services. Apart from the LIIKE system, data on rail capacity (=trains) can be generated via the interface specified by the Finnish Transport Infrastructure Agency. The Agency will provide further information on the requirements for and access to the interface. For example, the Finland version of the Viriato timetable planning software meets the relevant interface requirements. It is possible to link timetables produced using the software to a rail capacity application generated in the LIIKE system.

At the time of the publication of this Network Statement, any urgent application for rail capacity is still submitted in writing. The intention is, however, that in the 2011 timetable period even urgent applications will go via the LIIKE information system.

All applicants for rail capacity must use the underlying information for timetable planning supplied by the Finnish Transport Infrastructure Agency, in order to ensure that the timetabling of trains in connection with rail capacity applications is harmonised. The Finnish Transport Infrastructure Agency maintains these data and up-to-date data are available on the agency's Extranet.




Figure 6. Diagrammatic presentation of the schedule for train path requests and for allocation process.

4.3 Schedule for Train Path Requests and Allocation Capacity Requests

4.3.1 Schedule for Working Timetable

The timetable period in rail traffic starts annually at the second weekend of December, at 00.00 hrs on the night between Saturday and Sunday, and ends at the corresponding time the following year. The timetable period 2011 will start on 12.12.2010 and end on 10.12.2011. Correspondingly, the timetable period 2012 will start on 11.12.2011 and end on 8.12.2012. Applicants for capacity shall request capacity no earlier than 12 and no later than 8 months ahead of the timetable period. One request may include all the changes in traffic to be made during the timetable period.

Decisions on the allocation of capacity for regular services may be changed for the rest of the timetable period during the timetable period concerned at specified dates, provided that these changes do not affect the capacity allocated to other railway undertakings or to international traffic within the European Economic Area. The changes may take effect at 00.00 hrs on the night between Saturday and Sunday in the beginning of the timetable period and at the weekend following the end of the school year. In addition to the above dates, the Finnish Transport Infrastructure Agency may for special reasons decide on other dates on which changes can take place. At the time of publishing the Network Statement, the parties have had the chance to apply for changes in the capacity allocated for regular services on given dates, which have been six weeks apart on average. The Finnish Transport Infrastructure Agency shall inform all railway undertakings of possible new dates on which the capacity for regular services may be changed. The decision on the dates for applying changes will also be published in Finlex at <http://www.finlex.fi>.

Requests for changing capacity allocated for regular services must be submitted no later than four weeks before the date on which the change shall take effect. When the date on which the changes may take effect, is Sunday or a public holiday, the request shall be made on the first weekday.

4.3.2 Requesting Rail Capacity for Temporary Traffic

Applicants for capacity may request capacity from Finnish Transport Infrastructure Agency regardless of the prescribed period if they urgently need capacity for one or more provisional train paths. Ad hoc capacity requests for the time period between the change dates can be made after the capacity application period has ended. Rail capacity for museum traffic can be applied no earlier than four months before the scheduled departure. The Finnish Transport Infrastructure Agency will announce its decision concerning the capacity request within five working days of receiving the application. The more detailed application instructions can be found in Finnish Transport Infrastructure Agency's regulation on its website.

4.4 Allocation Process

4.4.1 Coordination Process

Based on the applications, Finnish Transport Infrastructure Agency draws up the capacity allocation proposal (called "draft working timetable" in the Railway Act) for the next timetable period no later than four months after the deadline for the submission of requests for capacity. It has, however, been agreed by European railway infrastructure managers that no more than 2.5 months shall be used for the coordination of requests. The capacity allocation proposal contains information on the capacity that Finnish Transport Infrastructure Agency proposes to allocate to an applicant only to such an extent and with such restrictions as is necessary for implementing traffic control for the use of this capacity.




Figure 7. Dates on which the capacity for regular services may be changed during the timetable period 2011.

The capacity allocation proposal is primarily based on the assumption that the requested capacity will be allocated, provided that the different train paths enable railway traffic to be operated in accordance with the technical and safety requirements. In order to improve the use of rail capacity, Finnish Transport Infrastructure Agency may, however, offer applicant's capacity that does not essentially differ from the capacity they have requested. Finnish Transport Infrastructure Agency may also decide not to allocate capacity, provided that reserve capacity is needed for the timetable period as a result of the priority order applied to rail traffic.

Finnish Transport Infrastructure Agency sends the capacity allocation proposal to applicants for information within the prescribed period of time and gives them the opportunity to comment. Comments shall be presented within 30 days after receipt of the capacity allocation proposal. Customers purchasing freight transport services and associations representing purchasers of rail transport services also have the right to present comments on the capacity allocation proposal within 30 days, counted from the date on which Finnish Transport Infrastructure Agency publishes an announcement in its collection of regulations that the capacity allocation proposal has been prepared.

Coordination for the Timetable Period

If there are several applicants for the same capacity or the requested capacity affects the capacity requested by another applicant, Finnish Transport Infrastructure Agency will attempt to coordinate the requests between the applicants. In such cases, Finnish Transport Infrastructure Agency may offer the applicants capacity that does not essentially differ from the capacity they have requested.

If the coordination of the requests between the applicants does not lead to a satisfactory result, Finnish Transport Infrastructure Agency decides on the priority order in each individual case on the grounds laid down in the Railway Act. Finnish Transport Infrastructure Agency shall decide on an individual priority order no later than ten days after coordination has ended.

Confirmation of the Capacity Allocation Proposal

Based on the capacity allocation proposal and the comments presented by the parties involved, Finnish Transport Infrastructure Agency shall decide on the allocation of rail capacity on a fair and non-discriminatory basis. In deciding, Finnish Transport Infrastructure Agency shall pay particular attention to the needs of passenger and freight traffic and infrastructure maintenance, as well as to efficient use of the

rail network. The priority order determined for specialised and congested infrastructure shall also be taken into account, unless otherwise provided in this chapter.

Allocating Ad Hoc Rail Capacity

Finnish Transport Infrastructure Agency allocates the requested ad hoc capacity if there is sufficient capacity for the use specified in the request. Unless otherwise provided in the Railway Act, the ad hoc capacity is allocated on a first-come first-served basis.

4.4.2 Dispute Resolution

Railway undertakings may appeal against a capacity allocation decision by Finnish Transport Infrastructure Agency by filing a claim for rectification with the Finnish Transport Safety Agency's Regulatory Body. For further information, see 1.4.3.

4.4.3 Congested Infrastructure

The guidelines of transport policy for the priority order

The main guidelines of the Finnish transport policy are presented in the Government transport policy report to Parliament on 27 March 2008. The main challenge of the transport policy is preventing climate change. The climate targets set for transport are promoted by supporting public transport and solutions for pro-environmental passenger and freight traffic. Another main target is to promote logistical competence in Finland by creating conditions for smooth and cost-efficient transport.

Rail traffic is an energy efficient and pro-environmental way of transporting large numbers of passengers. An efficient traffic system based on railway traffic promotes the integration of urban community structure and Finland's regional structure. The popularity of railway traffic can be guaranteed by providing passengers with fast, regular, punctual train connections with the help of a traffic system based on regular timetables. Such system can only work on congested tracks, if fast passenger and long-distance trains receive priority over other traffic. In local traffic local commuter should have priority over those, which stop more often. The smooth operation of fast trains is also important in the international Eastern traffic, which offers considerable growth potential in passenger traffic. For climate reasons, it is important that most of this growth potential is directed towards pro-environmental railway traffic instead of its competitors, air and road traffic.

It is important to develop competence in product and raw material transport for basic industry for the environmental impacts of freight traffic and Finland's logistical competence. The prioritisation of freight trains on congested tracks can affect the competence of railway transport and the number and length of freight trains' non-profit stops and their waiting times at stations. Such extra delays will increase costs, when the circulation of stock and crew is slower. Extra stops will also increase energy consumption and emissions. The logistical benefits achieved by prioritising freight trains are most significant in regular and continuous whole train and car group transportation, connected to carefully controlled industry processes. The savings achieved by prioritisation of trains in irregular traffic are smaller.

The most significant new potential in railway transport is long-distance, thin streams of goods, which are now mainly delivered as road transports. Transferring this to railway traffic is possible by creating keen scopes for action for the combined transports. This requires that fast and punctual connections of fast freight trains, which suit the timetables, are provided for transporting trailers and containers. On congested tracks this requires high prioritisation of trains compared to other traffic.

Priority order in Finland

Finnish Transport Infrastructure Agency declares an element of infrastructure or a part of it to be congested infrastructure if the coordination of several requests for the same infrastructure has not led to a satisfactory result. Finnish Transport Infrastructure Agency may also designate an element of infrastructure as congested if it is evident that it will become congested during the timetable period.

If there are several applications for the same infrastructure, the priority order is as presented in Table 1. Application of this priority order is based on the assumption that each train can be defined during its whole journey by one of the terms listed in the table. The term by which the train is defined may change during the journey of the train.

Table 1. Priority order on congested infrastructure.

Priority	Traffic
1.	Synergic passenger traffic entity ¹
2.a	Express train traffic ²
2.b	Transport for the processing industry ³
3.a	Local and other passenger traffic
3.b	Other regular freight traffic
4.	Freight traffic not requiring strict transport times
5.	Other traffic ⁴

¹ The term "synergic passenger traffic entity" refers in passenger traffic to the whole of trains which form a transport system producing clear added value for customers. A system of this kind is, for example, traffic operated according to the basic interval timetable

² The term "express train traffic" refers to traffic which in some respect does not belong within the scope of the synergy-producing traffic system. International passenger traffic may belong in this category.

³ The term "transport for the processing industry" mainly refers to transport whose immediate place of destination or origin is a port or a private siding. This transport is essentially connected with total logistics management. This group includes, in particular, combined transport, transport for the wood-processing industry and transport to ports.

⁴ For example, traffic connected with track work or museum train traffic.

Derogation from the Priority Order Laid Down in the Network Statement

Finnish Transport Infrastructure Agency may by a separate decision make derogation from the general priority order laid down in the Railway Act and the Network Statement in favour of an applicant operating international traffic or such traffic as otherwise maintains or improves the functioning of the rail transport system or public transport. The same applies to cases where the rejection of the application would cause unreasonable damage to applicants, railway undertakings, international groupings of railway undertakings or to the business activities of their customers.

4.5 Allocation of Capacity for Maintenance, Renewal and Enhancements

The rail network may also be used for transferring track machines from bases to worksites, between worksites, and for maintenance purposes. Certain tracks are mainly used for maintenance purposes. A list of these tracks can be requested from Finnish Transport Infrastructure Agency's Railway Department Rail Data Unit. Under the Railway Act, a safety certificate granted by the Finnish Transport Safety Agency is required for traffic operation, if it is by train or shunting, outside the area reserved for track maintenance. The safety certificate is granted upon application for a maximum of five years at a time. The requirements for obtaining a safety certificate are that the traffic operator engaged in track maintenance has sufficient liability insurance and an adequate risk management system, its stock has been approved by the Finnish Transport Safety Agency and that the persons conducting the traffic operation are competent to do so. Moreover, track machine movements shall be agreed upon separately with Finnish Transport Infrastructure Agency. The TURO system contains detailed instructions on the maintenance machinery used on the track as well as on the persons and undertakings charged with traffic safety duties.

Track works which will probably be carried out during the timetable period 2011 and which are likely to have an impact on train traffic are indicated in Appendix 11. The working programme, timing of tasks, and the breaks required for the work will change as the funding and plans become more focused. Once the Network Statement is published, Finnish Transport Infrastructure Agency will maintain up-to-date information on the working programme for the upcoming timetable period, and regularly inform the rail capacity applicants about the programme. Finnish Transport Infrastructure Agency will decide separately on all railway work and breaks required for their completion. The decision will be made prior to the upcoming timetable period that is in December 2010 for the timetable period 2011.

Any required maintenance breaks or changes to an earlier decision, arising after the decision has been made, can be discussed separately, if necessary. The basic rule is that breaks requiring traffic arrangements are no longer arranged at this stage, but instead the work requested after the decision will be carried out according to (or in between) the traffic.

In addition to the aforementioned, the person or group applying for the working break must contact the Finnish Transport Infrastructure Agency's traffic planner separately for each request and agree on the working break and its details in accordance with the Finnish Transport Infrastructure Agency's working break decision no later than two months before the work is scheduled to start.

The party performing the work must have permission for track work, and if necessary, a voltage cut-off prior to starting the work in the agreed work breaks.

4.6 Non-usage Rules

Finnish Transport Infrastructure Agency has the right to cancel the capacity allocated to an applicant, or a part of it, if the applicant has used this capacity over a period of not less than 30 days less than required by the threshold quota specified below. In Finland, the threshold quota for the minimum use of capacity is 80 %, except on the line sections Helsinki–Kerava, Helsinki–Vantaankoski and Helsinki–Leppävaara, where the threshold quota for the minimum use is 95 %.

Finnish Transport Infrastructure Agency may not, however, cancel the capacity if the failure to use it is due to non-economic reasons beyond the applicant or the railway operator's control. Finnish Transport Infrastructure Agency always cancels the capacity for such a period during which the railway undertaking does not have a safety certificate for operating rail services.

4.7 Exceptional Transport and Dangerous Goods

For information on the transport of dangerous goods, see point 3.4.3, Dangerous Goods. Regulations concerning railway traffic and rolling stock are available on the Internet pages of the Finlex Data Bank and other instructions on the Finnish Transport Safety Agency and Finnish Transport Infrastructure Agency website.

All special permits are granted by the Finnish Transport Infrastructure Agency. Guidelines on special permits can be found on the agency's website.

4.8 Special Measures to be taken in the Event of Disturbance

4.8.1 Principles

Finnish Transport Infrastructure Agency has the right to cancel the capacity completely or partially on a train path provisionally out of service due to a technical failure in the railway network, an accident or other incident.

In such case, Finnish Transport Infrastructure Agency offers the operator alternative train paths, as far as possible. Finnish Transport Infrastructure Agency is, however, not obliged to compensate for damage that may be caused to the operator, unless otherwise is agreed upon with the operator in conformity with the Railway Act.

4.8.2 Operational Regulation

The Finnish Transport Infrastructure Agency determines the rules on the management of disturbances between railway undertakings. The Traffic Management Centre of the Finnish Transport Infrastructure Agency resolves instances of disruption and provides guidelines on the correct action to take in such situations. Railway undertakings have the right to present their own proposals for instructions how to handle disturbances connected with their own trains. The liability for harm and damages caused by disturbances shall be agreed with Finnish Transport Infrastructure Agency.

4.8.3 Foreseen Problems

In cases of disruption the guidelines issued by the Finnish Transport Infrastructure Agency's Traffic Management Centre shall apply.

4.8.4 Unforeseen Problems

Finnish Transport Infrastructure Agency, railway undertakings and railway maintenance undertakings shall be prepared for railway accidents in their fields of activity. The principle is that railway undertakings and railway track contractors shall be prepared to clear their own vehicles and the transported freight off the track, as well as remedy the damage caused to the environment within a reasonable time after the accident. Each undertaking shall draw up an emergency preparedness plan, which Finnish Transport Infrastructure Agency shall approve. The preparedness measures included in the plan shall be taken before traffic operating is started. The undertakings themselves bear the costs caused by the creation and maintenance of the emergency preparedness system. Liability in cases of accident is determined in line with the Act on liability in rail traffic and the Tort Liability Act.

The Finnish Transport Infrastructure Agency is prepared to restore the track quickly to operable condition and within a reasonable time to the condition it had before the accident. Finnish Transport Infrastructure Agency agrees thereupon when making the rail network maintenance agreements.

The Ministry of Transport and Communications provides guidelines for and supervises the preparedness of the different rail sector operators for accidents and exceptional circumstances.

5 Services

5.1 Introduction

The legal framework of capacity allocation is described in the Railway Act (555/2006).

The Council of State is currently drafting its decree on the services offered to the rail traffic operators. Services concerning the usability of the rail network are described in Appendix 2 (Rail Traffic Operating Point Register) of the Network Statement. These services may be supplied by Finnish Transport Infrastructure Agency or other parties.

5.2 Services Offered by Finnish Transport Infrastructure Agency

Finnish Transport Infrastructure Agency offers rail traffic operators on the state-owned rail network the right against payment to utilise the train paths in accordance with the capacity granted to it by Finnish Transport Infrastructure Agency, marshalling yards, storage sidings, loading tracks and other tracks and passenger platforms. Finnish Transport Infrastructure Agency also offers train traffic control passenger information and public address systems at the railway stations specified in the Network Statement (Appendix 12).

Traffic control in connection with shunting is a chargeable service. It is not included in the infrastructure charge.

Use of capacity includes the right of the traffic operator to use of Finnish Transport Infrastructure Agency's electricity supply network for traffic on the electrified line sections specified in the Network Statement. Finnish Transport Infrastructure Agency does not, however, provide the electricity but the traffic operator shall conclude an agreement with a service provider. Finnish Transport Infrastructure Agency also does not provide refuelling facilities.

Finnish Transport Infrastructure Agency can offer services on a commercial basis for the use of railway operators. The additional services could comprise, for example, the use of buildings and land areas owned by Finnish Transport Infrastructure Agency.

The use of services provided by Finnish Transport Infrastructure Agency is agreed upon between the parties in the access contract or in a separate lease agreement.

5.3 Services Offered by Others

Railway undertakings are obliged to supply certain services and track access to services facilities for the use of railway operators if only one undertaking provides these services and it is not possible to otherwise arrange them. The availability of services shall be negotiated and an agreement shall be concluded with the service provider. The service provider has the right to charge a payment for its services. The payment shall be equitable for all railway undertakings and reasonable with respect to the costs incurred from providing the service.

Services supplied by others may include, for example:

- use of electrical supply equipment
- use of refuelling equipment
- use of passenger stations
- use of freight terminals
- use of train formation yards
- use of train formation equipment
- use of depot sidings
- premises and equipment needed for the servicing and maintenance of rolling stock
- use of other technical devices (e.g. sand distributors, water and electrical connections for rolling stock, radiation measurement devices, tank wagon filling gauges, wagon scales, and brake testing equipment), and
- training services for those involved in traffic safety tasks
- training services for those involved in traffic safety tasks.

6 Charges

6.1 Charging Principles and Services Included in the Infrastructure Charge

The legal framework of the basic infrastructure charge is described in the Railway Act (555/2006), Railway Infrastructure Tax (605/2003) and the Ministry of Transport and Communications Decree on the basic infrastructure charge (756/2006).

The basic infrastructure charge covers the minimum access package (the minimum access package is described under 5.2.), including track access to service facilities on the state-owned rail network.

6.2 Infrastructure Charge System

The infrastructure charge system will be changed. The basic principle remains that Finnish Transport Infrastructure Agency shall collect a basic infrastructure charge from railway operators on a fair and non-discriminatory basis for the minimum access package and track access to service facilities, calculated on the actual level of use. The basic infrastructure charge shall always be based on the costs directly caused by the operation of railway traffic. The infrastructure tax consists of a charge for external costs and a supplementary charge in accordance with the Capacity and Infrastructure Charge Directive. In the charge for external costs, the environmental effects caused by the operation of rail traffic can be taken into account. The supplementary charge can be collected for covering the full amount of the costs caused by the use of the infrastructure. Furthermore, investment tax will be collected for the Kerava–Lahti line section until 31 August 2021 in order to cover the long-term expenses of the investment.

6.3 Tariffs

The infrastructure charge consists of the charges mentioned in Table 2.

Table 2. Infrastructure charge.

Basic charge	Freight traffic 0.1350 cent/ gross tonne-kilometre Passenger traffic 0.1308 cent/ gross tonne-kilometre
Infrastructure tax	Freight traffic - electric 0.05 cent/ gross tonne-kilometre - diesel 0.1 cent/ gross tonne-kilometre Passenger traffic 0.01 cent/ gross tonne-kilometre
Investment tax (for line section Kerava–Lahti)	Freight traffic 0.5 cent/ gross tonne-kilometre Passenger traffic 0.5 cent/ gross tonne-kilometre

6.4 Performance scheme

In order to promote the effective use of the rail network and improve the timeliness of rail services and to minimise operational disruptions to the rail network caused by rail traffic and track maintenance, rail traffic operators and the Finnish Transport Infrastructure Agency are encouraged to limit disruptions arising from their activities and increase the effective use of the rail network by means of performance incentive schemes.

A rail operator shall compensate the Finnish Transport Infrastructure Agency if the operation of the rail operator essentially differs from the rail capacity allocated to it for a reason due to the operator, and such a deviation impedes the functioning of the railway system. The Finnish Transport Infrastructure Agency shall compensate a rail operator if, for reasons due to the Finnish Transport Infrastructure Agency, the availability of the rail network essentially differs from the rail capacity allocated to the operator, and such a deviation impedes the functioning of the railway system.

6.5 Changes to Charges

Infrastructure charge system is about to change. The principles of the valid infrastructure charge system and the amount of infrastructure charge are published on Finnish Transport Infrastructure Agency website.

6.6 Billing Arrangements

Finnish Transport Infrastructure Agency invoices the infrastructure charge each calendar month based on the realised performances of the previous month. For invoicing, railway operators shall provide the Finnish Transport Infrastructure Agency contact person with information each month on the rail services operated by them.

At the time of the publication of this Network Statement, detailed instructions for the payment of the infrastructure charge and the address details of the Finnish Transport Infrastructure Agency's department where the rail operator is due to notify traffic volumes were not yet available. The information will be posted on the agency's website.

Finnish Transport Infrastructure Agency does not require any guarantee for the payment of infrastructure charges. The infrastructure charge and other charges connected with it are, however, subject to distract without sentence or decision.

Index

- Access requirements 13–17
Access contract 13–14, 16
Accidents 23, 32
Ad hoc request 29
Allocation process 27–32
Axe loads 22, 99–107
Border stations 18, 88
Capacity allocation proposal 29
Congested capacity 29–31
Dangerous goods 24, 31
Draft working timetable 29
Environmental restrictions 24
Electrification 22, 24–25, 98, 107
Event of disturbance 32
Finnish Transport Safety Agency 7–10, 13–17, 23, 29
Framework agreement 16
Gradient 22
Infrastructure 18–26
Infrastructure capabilities 22
Infrastructure charge 33–34
Infrastructure development 26
Infrastructure tax 34
Metre loads 22
Ministry of Transport and Communications 8, 14, 24, 32
Museum train traffic 12–14, 17, 28
Operating licence 14
OSS activities 8, 11
Priority order for rail capacity 29–31
RAILI 23, 125
RailNetEurope 10–11
Regulatory body 7, 29
Requesting rail capacity 15, 27–28
Safety certificate 15, 17
Services 25, 33
Signalling systems 22, 108–112
Specialised infrastructure 24
Speed 22, 100–106, 113–115
TEN (Trans-European) Network 21
Timetable period 3, 8, 28
Track gauge 18
Track works 8, 31, 116–118
Traffic control 12, 16, 22–23, 25
Traffic operating points 18, 20, 37–88
Traffic restrictions 24–25, 113–115
Traffic safety communication 23
Train paths 11, 18
Urgently needed capacity 14, 27–28

Appendix 1

Infrastructure Register

Markings:

On	"yes"
—	"no"
AC2	electrification voltage 25 kV / 50 Hz
ATP	Automatic train protection

Chart columns:

- **Traffic operating points (Node of the network)** indicates all traffic operating points where the route of the train can be changed.
- **Length of line** is the distance between traffic operating points (Nodes of the network).
- **Max gradient** is the maximum gradient measured in a distance of 1,200 m.
- **Electrification system** indicates that the section of line is electrified.
- **Section blocking or radio-controlled section** indicates that an automatic safety device system is in use in order to protect the railway traffic.
- **ATP** indicates that the section of line is equipped with pan-European safety device system and GSM-R radio network.
- **ERTMS** indicates that the section of line is equipped with pan-European safety device system and GSM-R radio network.
- **ATP coding for tilting trains** indicates the sections on which ATP allows higher speeds for tilting trains.
- **Radio system** indicates that the digital (GSM-R) communication equipment is in use between the driver and traffic control in mention traffic operating points.

Liikenneympäikkä (verkon solmupiste)	Liikenneympäikkä (verkon solmupiste)	Radan pituus	Määrävä kaltevuus	Sähköistys- järjestelmä	Suojaistettu tai radio-ohjattu osuuus	Junan kulun- valvontajärjestelmä	ERTMS	Kallistuvakoristen junien JKV-koodaus	Radio- järjestelmä
Trafikplats (bannätets knutpunkt)	Trafikplats (bannätets knutpunkt)	Banans längd	Största lutningen	Elektrififi- nings-systemet	Linjeblockerad eller radiostyrd sträcka	Automatisk tågkontroll	ATC-kodning av lutande tåg	Radio system	Radio system
Traffic operating point (Node of the network)	Traffic operating point (Node of the network)	Length of line [km]	Max. gradient %	Electrification system	Section blocking or radio controlled section	ATP	ATP-coding for tilting trains	ATP system	ATP system
Helsingin päärautatieasema	Kerava asema	29	10,0	AC2	On	ATP	-	GSM-R	GSM-R
Kerava asema	Hyvinkää	29	7,5	AC2	On	ATP	-	GSM-R	GSM-R
Hyvinkää	Riihimäki asema	12	7,5	AC2	On	ATP	-	GSM-R	GSM-R
Kerava asema	Vuosaari	19	10,0	AC2	On	ATP	-	GSM-R	GSM-R
Kerava asema	Sköldvik	27	10,0	AC2	On	ATP	-	GSM-R	GSM-R
Kerava asema	Hakosilta	65	10,0	AC2	On	ATP	-	GSM-R	GSM-R
Hyvinkää	Lohja	64	10,5	-	On	ATP	-	GSM-R	GSM-R
Lohja	Karjaa	35	10,0	-	On	ATP	-	GSM-R	GSM-R
Lohja	Lohjanjärvi	4	15,0	-	-	-	-	GSM-R	GSM-R
Helsingin päärautatieasema	Huopalahti	6	10,0	AC2	On	ATP	-	GSM-R	GSM-R
Huopalahti	Vantaankoski	9	11,5	AC2	On	ATP	-	GSM-R	GSM-R
Huopalahti	Kirkkonummi	31	10,5	AC2	On	ATP	-	GSM-R	GSM-R
Kirkkonummi	Karjaa	49	12,0	AC2	On	ATP	-	GSM-R	GSM-R
Karjaa	Hanko asema	50	10,5	-	On	ATP	-	GSM-R	GSM-R
Karjaa	Turku päärautatieasema	107	12,7	AC2	On	ATP	-	GSM-R	GSM-R
Turku päärautatieasema	Turku satama	3	7,0	AC2	On	ATP	-	GSM-R	GSM-R
Riihimäki asema	Toijala	76	10,0	AC2	On	ATP	-	GSM-R	GSM-R
Toijala	Turku päärautatieasema	128	10,5	AC2	On	ATP	-	GSM-R	GSM-R
Toijala	Tampere asema	40	10,0	AC2	On	ATP	-	GSM-R	GSM-R
Toijala	Valkeakoski	18	8,0	-	-	-	-	GSM-R	GSM-R
Turku päärautatieasema	Raisio	8	7,0	-	-	-	-	GSM-R	GSM-R
Raisio	Naantali	6	9,0	-	-	-	-	GSM-R	GSM-R
Uusikaupunki	Uusikaupunki	57	9,0	-	On	ATP	-	GSM-R	GSM-R
Tampere asema	Hangonsaari	3	11,5	-	-	-	-	GSM-R	GSM-R
Lielaiti	Lielaiti	6	9,0	AC2	On	ATP	-	GSM-R	GSM-R
Kokemäki	Kokemäki	91	12,5	AC2	On	ATP	-	GSM-R	GSM-R
Kukainen	Kukainen	13	9,0	AC2	On	ATP	-	GSM-R	GSM-R
Kukainen	Rauma	34	9,0	AC2	On	ATP	-	GSM-R	GSM-R
Kukainen	Säkylä	19	9,0	-	-	-	-	GSM-R	GSM-R
Kokemäki	Pori	38	9,5	AC2	On	ATP	-	GSM-R	GSM-R
Pori	Mäntyluoto	21	5,5	-	-	-	-	GSM-R	GSM-R
Mäntyluoto	Ruosniemi	8	10,0	-	-	-	-	GSM-R	GSM-R
Lielaiti	Tahkoluoto	11	5,5	-	On	ATP	-	GSM-R	GSM-R
	Parkano	69	10,5	AC2	On	ATP	-	GSM-R	GSM-R

Liikennepaikka (verkon solmupiste)	Liikennepaikka (verkon solmupiste)	Radan pituus	Määritävä kaltevuus	Suojaistettu tai radio-ohjattu osuuus	Junan kulun- valvontajärjestelmä	ERTMS	Kallistuvakoristen junien JKV-koodaus	Radio- järjestelmä
Trafikplats (bannärets knutpunkt)	Trafikplats (bannärets knutpunkt)	Banans längd	Största lutningen	Elektrifie- nings-systemet	Linjeblockerad eller radiostyrd sträcka	Automatisk tågkontrol	ATC-kodning av lutande tåg	Radio system
Traffic operating point (Node of the network)	Traffic operating point (Node of the network)	Length of line [km]	Max. gradient %	Electrification system	Section blocking or radio controlled section	ATP	ATP-coding for tilting trains	Radio system
Niinisalo	Parkano	42	10,0	—	—	—	—	—
Parkano	Kihniö	17	9,5	—	—	—	—	—
Parkano	Seinäjoki asema	84	10,0	AC2	On	ATP	ATP	GSM-R
Riihimäki asema	Hakosilta	48	8,0	AC2	On	ATP	ATP	GSM-R
Hakosilta	Lahti	11	10,0	AC2	On	ATP	ATP	GSM-R
Lahti	Loviisan satama	77	12,0	—	—	—	—	—
Lahti	Henola	38	12,0	—	—	—	—	—
Lahti	Mukkula	7	15,0	—	—	—	—	—
Lahti	Kouvola asema	61	10,0	AC2	On	ATP	ATP	GSM-R
Kouvola asema	Luumäki	59	10,0	AC2	On	ATP	ATP	GSM-R
Juurikorpi	Juurikorpi	33	10,0	AC2	On	ATP	ATP	GSM-R
Kotka asema	Kotka asema	18	8,5	AC2	On	ATP	ATP	GSM-R
Kotka satama	Kotkan satama	1	0,0	AC2	On	ATP	ATP	GSM-R
Kotka Muussalo	Kotka Muussalo	5	6,0	AC2	—	ATP	ATP	GSM-R
Juurikorpi	Hamina	19	10,0	AC2	On	ATP	ATP	GSM-R
Kouvola asema	Kuusankoski	10	9,0	AC2	—	—	—	—
Kouvola asema	Mynttilä	86	12,0	AC2	On	ATP	ATP	GSM-R
Mynttilä	Ristiina	21	12,5	—	—	—	—	—
Mynttilä	Otava	20	10,0	AC2	On	ATP	ATP	GSM-R
Otava	Otavan satama	2	22,5	—	—	—	—	—
Otava	Pielsämäki asema	86	11,0	AC2	On	ATP	ATP	GSM-R
Luumäki	Vainikkala asema	33	8,0	AC2	On	ATP	ATP	GSM-R
Luumäki	Lappeenranta	27	9,5	AC2	On	ATP	ATP	GSM-R
Lappeenranta	Mustolan satama	18	10,0	—	—	—	—	—
Lappeenranta	Imatra tavara	39	9,0	AC2	On	ATP	ATP	GSM-R
Imatra tavara	Imatrankoski-raja	10	11,0	—	—	—	—	—
Imatra tavara	Parikkala	60	10,0	AC2	On	ATP	ATP	GSM-R
Pieksämäki asema	Huutokoski	31	11,0	—	On	ATP	ATP	GSM-R
Huutokoski	Savonlinna	75	12,0	—	On	ATP	ATP	GSM-R
Savonlinna	Parikkala	59	12,0	—	On	ATP	ATP	GSM-R
Parikkala	Säkäniemi	93	10,0	AC2	On	ATP	ATP	GSM-R
Niiralä-raja	Säkäniemi	33	10,5	—	On	ATP	ATP	GSM-R
Säkäniemi	Joensuu asema	37	10,5	AC2	—	—	—	—
Joensuu asema	Ilomantsi	71	12,0	—	—	—	—	—
Joensuu asema	Viniäjärvi	32	9,0	—	On	—	—	GSM-R

Liikennepaikka (verkon solmupiste)	Liikennepaikka (verkon solmupiste)	Radan pituus	Määritävä kaltevuus	Sähköistys- järjestelmä	Suojaistettu tai radio-ohjattu osuuus	Junan kulun- valvontajärjestelmä	ERTMS	Kallistuvakoristen junien JKV-koodaus	Radio- järjestelmiä
Trafikplats (bannätets knutpunkt)	Trafikplats (bannätets knutpunkt)	Banans längd	Största lutningen	Elektrific- nings-systemet	Linjeblockerad eller radiostyrd sträcka	Automatisk tågkontroll	ATC-kodning av lutande tåg	Radio system	Radio system
Traffic operating point (Node of the network)	Traffic operating point (Node of the network)	Length of line [km]	Max. gradient %	Electrification system	Section blocking or radio controlled section	ATP	ATP-coding for tilting trains	Radio system	Radio system
Huutokoski	Varkaus	18	10,0	—	On	ATP	—	GSM-R	GSM-R
	Kommila	6	10,0	—	—	—	—	GSM-R	GSM-R
	Viinijärvi	101	11,0	—	On	ATP	ATP	GSM-R	GSM-R
	Uimaharju	50	17,6	—	On	ATP	ATP	GSM-R	GSM-R
	Lieksta	54	11,5	—	On	ATP	ATP	GSM-R	GSM-R
	Pankakoski	6	10,0	—	—	—	—	GSM-R	GSM-R
	Nurmes	56	12,5	—	On	ATP	ATP	—	—
	Vuokatti	85	11,5	—	—	—	—	—	—
	Lahnaslampi	12	10,0	—	—	—	—	GSM-R	GSM-R
	Kontiomäki	24	10,5	AC2	On	ATP	ATP	GSM-R	GSM-R
	Lieksta	38	9,0	—	—	—	—	—	—
	Nurmes	6	10,0	—	—	—	—	—	—
	Vuokatti	76	12,0	AC2	On	ATP	ATP	GSM-R	GSM-R
	Vuokatti	99	10,5	—	On	ATP	ATP	GSM-R	GSM-R
	Pieksämäki asema	60	12,0	AC2	On	ATP	ATP	GSM-R	GSM-R
	Suonenjoki	62	12,7	AC2	On	ATP	ATP	GSM-R	GSM-R
	Suonenjoki	25	11,0	—	—	—	—	—	—
	Siilinjärvi	20	12,0	AC2	On	ATP	ATP	GSM-R	GSM-R
	Siilinjärvi	95	11,0	AC2	On	ATP	ATP	GSM-R	GSM-R
	Ilsalmi	2	10,0	AC2	On	ATP	ATP	GSM-R	GSM-R
	Murtomäki	62	12,7	—	—	—	—	—	—
	Otanmäki	25	11,0	—	—	—	—	—	—
	Kajaani	20	12,0	AC2	On	ATP	ATP	GSM-R	GSM-R
	Vartius	95	11,0	AC2	On	ATP	ATP	GSM-R	GSM-R
	Vartius	2	10,0	AC2	On	ATP	ATP	GSM-R	GSM-R
	Vartius-rata	74	12,0	—	—	—	—	—	—
	Pesiökylä	18	12,0	AC2	On	ATP	ATP	GSM-R	GSM-R
	Ämmänsaari	40	12,0	—	—	—	—	GSM-R	GSM-R
	Orivesi	47	12,5	—	—	—	—	GSM-R	GSM-R
	Vilppula	8	5,0	—	—	—	—	GSM-R	GSM-R
	Vilppula	26	12,5	—	On	ATP	ATP	GSM-R	GSM-R
	Haapamäki	118	12,0	—	On	ATP	ATP	GSM-R	GSM-R
	Haapamäki	77	12,0	—	On	ATP	ATP	GSM-R	GSM-R
	Haapamäki	56	12,5	AC2	On	ATP	ATP	GSM-R	GSM-R
	Orivesi	7	12,0	—	—	—	—	GSM-R	GSM-R
	Jämsä	4	10,0	AC2	On	ATP	ATP	GSM-R	GSM-R
	Jämsä	52	10,5	AC2	On	ATP	ATP	GSM-R	GSM-R
	Jyväskylä	47	10,5	—	—	—	—	—	—
	Äänekoski	164	10,5	—	—	—	—	—	—
	Haapajärvi								

Liikenepaikka (verkon solmupiste)	Liikenepaikka (verkon solmupiste)	Radan pituus	Määärävä kaltevuus	Sähköistys- järjestelmä	Suojaistettu tai radio-ohjattu osuus	Junan kulun- valvontajärjestelmä	ERTMS	Kaistustuvakoristen junien JKV-koodaus	Radio- järjestelmä
Trafikplats (bannätets knutpunkt)	Trafikplats (bannätets knutpunkt)	Banans längd	Största lutningen	Elektrifi- erings-systemet	Linjeblockerad eller radiostyrd sträcka	Automatisk tågkontroll		ATC-kodning av lutande tåg	Radio system
Traffic operating point (Node of the network)	Traffic operating point (Node of the network)	Length of line [km]	Max. gradient %	Electrification system	Section blocking or radio controlled section	ATP		ATP-coding for tilting trains	Radio system
Jyväskylä	Pieksämäki asema	80	12,5	AC2	On	ATP	On	GSM-R	
Seinäjoki asema	Kaskinen	112	10,0	—	On	ATP	—	GSM-R	
Seinäjoki asema	Vaasa	75	12,0	—	On	ATP	—	GSM-R	
Vaasa	Vaskiluoto	5	1,0	—	—	—	—	GSM-R	
Isalmi	Pyhäkumpu erakanemisvaihde	63	10,0	—	On	ATP	—	GSM-R	
Pyhäkumpu erakanemisvaihde	Pyhäkumpu	3	3,0	—	—	ATP	—	GSM-R	
Pyhäkumpu erakanemisvaihde	Haapavesi	36	9,5	—	On	ATP	—	GSM-R	
Haapavesi	Ylivieska	55	8,0	—	On	ATP	—	GSM-R	
Seinäjoki asema	Päinänen	101	10,0	AC2	On	ATP	—	GSM-R	
Päinänen	Pietarsaari	10	6,0	—	—	ATP	—	GSM-R	
Päinänen	Alholma	4	3,0	—	—	ATP	—	GSM-R	
Päinänen	Kokkola	33	7,0	AC2	On	ATP	—	GSM-R	
Kokkola	Yksphlaja	5	10,0	AC2	—	—	—	GSM-R	
Kokkola	Ylivieska	79	10,0	AC2	On	ATP	—	GSM-R	
Ylivieska	Tuomiola	68	10,0	AC2	On	ATP	—	GSM-R	
Tuomiola	Raahe	28	10,0	AC2	On	ATP	—	GSM-R	
Raahe	Rautaruukki	9	10,0	AC2	—	ATP	—	GSM-R	
Tuomiola	Oulu asema	54	10,0	AC2	—	ATP	—	GSM-R	
Oulu asema	Kontiomäki	166	10,0	AC2	On	ATP	—	GSM-R	
Oulu asema	Kemi	105	10,0	AC2	On	ATP	—	GSM-R	
Kemi	Ajos	9	10,0	—	—	ATP	—	GSM-R	
Kemi	Laurila	7	10,0	AC2	—	ATP	—	GSM-R	
Laurila	Tornio	19	7,5	—	On	ATP	—	GSM-R	
Laurila	Rovaniemi	106	10,0	AC2	On	ATP	—	GSM-R	
Rovaniemi	Kemijärvi	85	12,0	AC2	On	ATP	—	GSM-R	
Kemijärvi	Isokylä	7	5,5	—	—	ATP	—	GSM-R	
Isokylä	Kelloselkä	72	12,5	—	—	ATP	—	GSM-R	
Tornio	Tornio-rajat	3	4,0	—	On	ATP	—	GSM-R	
Tornio	Röyttä	8	8,0	—	—	ATP	—	GSM-R	
Tornio	Kolari	183	10,5	—	On	ATP	—	GSM-R	
Sysmäjärvi	Vuonos	7	10,0	—	—	ATP	—	GSM-R	
Viiñjärvi	Sysmäjärvi	13	7,5	—	On	ATP	—	GSM-R	
Murtomäki	Talvivaara	24	12,5	AC2	On	ATP	—	GSM-R	
Kajaani	Lammimäki	3	10,0	—	—	ATP	—	GSM-R	
Kajaani	Kontiomäki	26	12,0	AC2	On	ATP	—	GSM-R	

Appendix 2

Rail Traffic Operating Point Register

Legend

() in columns	platform not maintained by Finnish Transport Infrastructure Agency
regarding platforms	
K	yes
Y	private
K in columns regarding traffic control	remote control
M in columns regarding traffic control	manual

Chart Columns:

- **Name** refers the official name of the station and is used in traffic safety work.
- **Another name** is the name of a traffic operating point in Finland's second official language. Another name is usually a Swedish name and only in Sköldvik is the Finnish name Kilpilahti used as another name, contrary to what the present language situation in the municipality would imply.
- **Km Hki** describes the distance of a traffic operating point to the old station hall of Helsinki (already torn down), measured by a track kilometre system. According to the system, the location of all elements on tracks is fixed to landmarks.
- **Municipality** refers to the municipality in which the traffic operating point is located.
- **Traffic control** describes whether the traffic operating point has the technical equipment to control the train traffic manually or remote. It does not mean that traffic control services are regularly provided.
- **Private sidings** indicates that the traffic operating point has at least one connection to a e siding, owned or managed by a private owner (includes everyone except the Finnish Transport Infrastructure Agency).
- **Shunting** indicates that the form of the tracks at a traffic operating point is such that it is possible to move at least a locomotive to the other end of a line of rolling stock without having to go through the main line of the traffic operating point.

- **Minimum and maximum platform length** indicates the minimum and maximum length of platforms used by passenger trains at the traffic operating point. A passenger train should not be longer than the platform at which it stops. If the platform length is in brackets (), the platform is not maintained by the Finnish Transport Infrastructure Agency and services are operated at the responsibility of the railway undertaking.
- **Platform height** indicates the nominal height of platforms used by passenger trains, calculated from the surface of the rail.
- **Design train length** indicates the longest track of a traffic operating point, other than the main line going through it. The length is measured in such a way that it is usable in both directions.
- **Power supply** indicates at which traffic operating point it is possible to get 400 V or 1500 V electric current mainly for rolling stock or track machinery power supply purposes.
- **Side loading platform** indicates at which traffic operating point it is possible to load freight cars from the side, and shows the maximum platform length at the traffic operating point.
- **End loading platform** indicates at which traffic operating point it is possible load freight rolling stock from the end of the platform (combined transports).
- **Loading site** indicates at which traffic operating point it is possible to load freight rolling stock at rail level. A typical example is loading of raw timber from a vehicle or an intermediate depot at a rail yard onto flatcars.
- **Crane** indicates at which traffic operating point it is possible to use a crane to load wagons, and states the maximum capacity of the crane. This service is no provided by the Finnish Transport Infrastructure Agency.
- **Fuel** indicates at which traffic operating point there is a fuel distribution point. This service is not provided by the Finnish Transport Infrastructure Agency.
- **The Passenger traffic column** shows the operating points where passenger traffic can be operated.
- **The Freight transport column** shows the operating points where freight transport can be operated.

Nimi	Toinen nimi	Lyhenne	Km Hki	Rataosuu	Banavsnitt	Kunta	Likenteen-ohjaus	Yksityisraiteita	Vaihtoy-mahdolisuu
Namn	Annat namn	Förkortning				Kommun	Trafikledning	Privata spåraniäggningsar	Möjlighet till växning
Name	Another name	Abbr.		Section		Municipality	Traffic control	Private sidings	Shunting
Ahyenus		Ahv	270+960	Lielathi-Kokemäki		Kokemäki	K		
Airkseila		Arl	436+985	Pieksämäki-Kontiomäki		Kuopio	K		K
Aittaluoto		Atl	328+220	Pori-Ruosniemi		Pori	K		
Ajös		Ajo	887+100	Kemi-Ajos		Kemi	K		K
Alapitkä		Apt	505+840	Pieksämäki-Kontiomäki		Lapinlahti	K		K
Alavus		Alv	373+445	Orivesi-Seinäjoki		Alavus	K		K
Alholma		Alh	532+570	Pietarsaari-Alholma		Pietarsaari			
Alvajärvi		Avi	551+033	Äänekoski-Haapavesi		Pihlajavesi	K		
Arola		Aro	707+668	Kontiomäki-Vartius-raja		Hyrjysalmi	K		
Dragsvik		Dra	171+180	Karjaa-Hanko		Raasepori	K		
Dynamilifttivaihde		Dmv	199+185	Karjaa-Hanko		Hanko	K		
Elijärvi		Eli	870+536	Lautiosaari-Elijärvi		Keminmaa	K		
Eläinpuisto-Zoo		Epz	338+751	Orivesi-Seinäjoki		Ähtäri	K		
Eno		Eno	660+170	Joensuu-Nurmnes		Joensuu	K		
Ervälä		Erv	118+777	Helsinki päärautatieasema-Turku satama		Salo	K		
Eskola		Ela	603+762	Seinäjoki-Oulu		Kannus	K		
Espoo		Espo	20+600	Helsinki päärautatieasema-Turku satama		Espoo	K		
Esso		Esso	267+417	Uusikaupunki-Hangonsaari		Uusikaupunki	K		
Haapavesi		Hpj	649+205	Iisalmi-Ylivieska, Äänekoski-Haapavesi		Haapavesi	K		
Haapakoski		Hps	393+460	Pieksämäki-Kontiomäki		Pieksämäki	K		
Haapamäen kylilästämö		Hmk	304+940	Orivesi-Seinäjoki		Keuruu	K		
Haapamäki		Hpk	300+235	Haapavesi-Jyväskylä, Orivesi-Seinäjoki		Keuruu	K		
Haarajoki		Haa	39+567	Kerava-Hakosilta		Järvenpää	K		
Hakosilta		Hit	119+540	Riihimäki-Kouvola, Kerava-Hakosilta		Hollola	K		

Nimi	Toinen nimi	Lyhenne	Km Hki	Rataosus	Kunta	Likenteen-ohjaus	Yksityisraiteita	Vaihtotyö-mahdollisuus
Namn	Annat namn	Förkortning		Banavsnitt	Kommun	Trafikledning	Privata spåränläggningar	Möjlighet till växning
Name	Another name	Abbr.		Section	Municipality	Traffic control	Private sidings	Shunting
Haksi	Hax	Hsi	56+737	Olli-Porvoo	Porvoo		K	K
Hamina	Fredrikshamn	Hma	243+626	Juurikorpi–Hamina	Hamina	M	K	K
Hammarslähti		Hsl	602+199	Kouvola–Joensuu	Joensuu	K		
Hanala	Hanaböle	Hna	21+394	Helsingi päärautatieasema–Riihimäki	Vantaa	K		K
Hangonsaari		Hgs	269+655	Uusikaupunki–Hangonsaari	Uusikaupunki			
Hanhikoski		Hhh	1047+083	Laurila–Kemijärvi	Kemijärvi	K		K
Hankasalmi		Hks	418+089	Jyväskylä–Pieksämäki	Hankasalmi	K		K
HANKO		Han	–	Karjaa–Hanko	M			
Hanko asema	Hangö	Hnk	207+119		Hanko	K	K	K
Hanko tavaratila		Hnkt	206+350		Hanko	K	K	K
Hanko-Pohjoinen		Hkp	205+935	Kokemäki–Pori	Harjavalta	K		
Harjavalta	Hangö Norra	Hva	295+542	Kouvolan Pieksämäki	Kouvolan	K		K
Hariju		Hj	201+643	Kouvolan Pieksämäki	Janakkala	K		K
Harviala		Hrv	99+456	Riihimäki–Tampere	Haukipudas	K		K
Haukipudas		Hd	775+159	Oulu–Laurila	Mikkeli	K		K
Haukkivuori		Hau	344+437	Kouvolan Pieksämäki	Riihimäki–Kouvolan	K		
HAUSJÄRVI		Hjr	–		Hausjärvi			
Hausjärvi tavaratila		Has	85+765		Hausjärvi			
Oitti		Oi	86+809		Hausjärvi			
Haviseva		Hvs	208+135	Tampere–Jyväskylä	Kangasala	K		
Heikkilä		Hek	34+856	Helsingi päärautatieasema–Turku satama	Kirkkonummi	K		
Heinola		Ha	167+607	Lahti–Heinola	Heinola	M		K
Heino		Hno	237+965	Lielaiti–Kokemäki	Sastamala	K		
Heinävaara		Häv	648+408	Joensuu–Ilomantsi	Joensuu	K		K
Heinävesi		Hnv	468+143	Pieksämäki–Joensuu	Heinävesi	K		

Nimi	Toinen nimi	Lyhenne	Km Hki	Rataosuuus	Kunta	Likenteen-ohjaus	Yksityisraiteita	Vaihtoyö-mahdolisuus
Namn	Annat namn	Förkortning		Banavsnitt	Kommun	Trafikledning	Privata spåraniäggningsar	Möjlighet till växning
Name	Another name	Abbr.		Section	Municipality	Traffic control	Private sidings	Shunting
HELSINKI		Hel	-	Helsinki päärautatieasema-Turku satama, Helsinki päärautatieasema-Riihimäki	M			
<i>Helsingfors Central Station</i>		Hki	0+159		Helsinki			K
<i>Pasila alapihä</i>		Psi	3+193		Helsinki			K
<i>Pasila asema</i>		Psi	3+230		Helsinki			
<i>Ilmalan asema</i>		Ila	4+434		Helsinki			
<i>Helsingi Kivihaka</i>		Khk	4+701		Helsinki			
<i>Pasila tavara</i>		Psit	4+748		Helsinki			
<i>Ilmalan ratapiha</i>		Ir	4+950		Helsinki			
<i>Käpylä</i>		Käp	5+685		Helsinki			
<i>Oulunkylä</i>		Olk	7+399		Helsinki			
<i>Herrala</i>		Hr	115+790	Riihimäki–Kouvola	Hollola			
<i>Hiekkaharju</i>		Hkh	17+109	Helsinki päärautatieasema–Riihimäki	Vantaa			
<i>Sandkulla</i>		Hir	318+957	Kouvola–Pieksämäki	Mikkeli			
<i>Hirrola</i>		Hk	79+743	Riihimäki–Kouvola	Hausjärvi			
<i>Hillosensalmi</i>		His	233+344	Kouvola–Pieksämäki	Kouvola			
<i>Hinthaara</i>		Hn	52+150	Olli–Porvoo	Porvoo			
<i>Hirvineva</i>		Hvn	715+500	Seinäjoki–Oulu	Liminka			K
<i>Humpilla</i>		Hp	188+776	Toijala–Turku päärautatieasema	Humpila			K
<i>Huopalahti</i>		Hpl	6+375	Huopalahti–Vantaankoski, Helsinki päärautatieasema–Turku satama	Helsinki			
<i>Huutokoski</i>		Hko	406+988	Huutokoski–Savonlinna, Pieksämäki–Joensuu	Joroinen	K		K
<i>Hyrynsalmi</i>		Hys	704+601	Kontiomäki–Ämmänsaari	Hyrynsalmi	M		K
<i>Hyvinkää</i>		Hy	58+792	Hyvinkää–Karjaan, Helsinki päärautatieasema–Riihimäki	Hyvinkää			K
<i>Hämeenlinna</i>		Hi	107+559	Riihimäki–Tampere	Hämeenlinna	K		K
<i>Härmä</i>		Hm	472+940	Seinäjoki–Oulu	Kauhava	K		K

Nimi	Toinen nimi	Lyhenne	Km Hki	Rataosuuus	Kunta	Likenteen-ohjaus	Yksityisraiteita	Vaihtotyö-mahdollisuus
Namn	Annat namn	Förkortning		Banavsnitt	Kommun	Trafikledning	Privata spårsläggningar	Möjlighet till växning
Name	Another name	Abbr.		Section	Municipality	Traffic control	Private sidings	Shunting
Höijäkkä		Höi	765+261	Joensuu–Nurmekoski	Nurmekoski			
Li		li	789+165	Oulu–Laurila	Lielahti			
lisalmen teollisuuskyrö		ltk	553+182	lisalmi–Ylivieska	Ylivieska			
lisalmen teollisuusraiteet		ltr	548+611	Pieksämäki–Kontiomäki	Pieksämäki			
lisalmi		ilm	550+371	Pieksämäki–Kontiomäki, lisalmi–Ylivieska	Kontiomäki			
lisvesi		lsv	420+124	Suonenjoki–lisvesi	Suonenjoki			
littala		ita	129+253	Riihimäki–Tampere	Riihimäki			
llomantsi		ilo	695+203	Joensuu–llomantsi	Ilomantsi			
IMATRA		Ima	326+542	Imatra tavara–Imatrakoski-raja, Kouvolaa–joensuu	Imatra	M	K	K
		<i>Imr</i>	323+977	<i>Imatra asema</i>	<i>Imatra</i>			
		<i>Imt</i>	326+542	<i>Imatra tavara</i>	<i>Imatra</i>			
		<i>Imk</i>	331+267	<i>Imatrakoski</i>	<i>Imatra</i>			
		<i>Pa</i>	335+672	<i>Pelkola</i>	<i>Imatra</i>			
		<i>Imkr</i>	337+095	Imatra tavara–Imatrakoski-raja	Imatra			
		<i>In</i>	341+367	Imatrakoski–raja	Ähtäri			
		<i>Ikr</i>	212+842	Inha	Kouvolaa			
		<i>Iko</i>	70+620	Inkeroinen	Inkoo			
		<i>Ingå</i>		Ingå				
		<i>Isg</i>	431+759	Isokangas	Niinisalo–Parkano–Kihniö			
		<i>Ikä</i>	1062+829	Isokylä	Kemijärvi–Kelloselkää	Kemijärvi		
		<i>Iky</i>	447+488	Isokyrö	Seinäjoki–Vaasa	Isokyrö		
		<i>Jal</i>	309+871	Jalasjärvi	Tampere–Seinäjoki	Jalasjärvi		
		<i>Jpa</i>	495+784	Jepua	Seinäjoki–Oulu	Uusikaarlepyy		
		<i>Joe</i>	–	JOENSUU	Pieksämäki–Joensuu, Kouvolaa–Joensuu, Joensuu–Nurmekoski			
		<i>Sul</i>	622+650		Joensuu	M	K	K

Nimi	Toinen nimi	Lyhenne	Km Hki	Rataosuuus	Kunta	Liikenteen-ohjaus	Yksityisraiteita	Vaihtotö-mahdolisuus
Namn	Annat namn	Förkortning		Banavsnitt	Kommun	Trafikledning	Privata spåranläggningar	Möjlighet till växning
Name	Another name	Abbr.		Section	Municipality	Traffic control	Private sidings	Shunting
<i>Joensuu Peltola</i>		Plt	623+540		<i>Joensuu</i>		K	
<i>Joensuu asema</i>		Jns	624+313		<i>Joensuu</i>		K	
Jokela		Jk	47+937	Helsingi päärautatieasema–Riihimäki	Tuusula		K	
Joroinen		Jor	414+617	Huutokoski–Savonlinna	Joroinen		K	
Jorvas		Jrs	32+322	Helsingi päärautatieasema–Turku satama	Kirkkonummi		K	
Joutseno		Jts	305+826	Kouvola–Joensuu	Lappeenranta		K	
Joutsjärvi		Jsj	1082+855	Kemijärvi–Kelloselkä	Kemijärvi	M	K	
Juankoski		Jki	532+005	Silinjärvi–Viinijärvi	Juankoski	K	K	
Jukajärvi		Jkj	637+876	Joensuu–Ilomantsi	Joensuu		K	
Juttila		Jut	94+620	Riihimäki–Kouvola	Kätkölä		K	
Juupajoki		Jj	246+580	Orivesi–Seinäjoki	Juupajoki		K	
Juurikorpi		Jri	224+898	Juurikorpi–Hamina, Kouvola–Kotka	Kotka		K	
Jyränkö		Jyr	165+774	Lahti–Heinola	Heinola		K	
Jyväskylä		Jy	377+435	Jyväskylä–Äänekoski, Tampere–Jyväskylä, Jyväskylä–Pieksämäki, Haapavesi–Jyväskylä	Jyväskylä		K	
Jämsä		Jäs	284+084	Jämsä–Kaipola, Tampere–Jyväskylä	Jämsä	K	K	
Jämsänkoski		Jsk	288+645	Tampere–Jyväskylä	Jämsä	K	K	
Järvelä		Jr	103+606	Riihimäki–Kouvola	Kätkölä	K	K	
JÄRVENPÄÄ		Jvp	–	Helsinki päärautatieasema–Riihimäki		K		
<i>Järvenpää asema</i>		Jp	36+802		<i>Järvenpää</i>		K	
<i>Seunakallio</i>		Sau	38+846		<i>Järvenpää</i>		K	
Purola		Pur	40+665		Järvenpää	K	K	
Kaipiainen		Kpa	214+451		Kouvola	K	K	
Kaipola		Kla	290+303		Jämsä–Kaipola	K	K	
Kairokoski		Kko	423+184		Niinisalo–Parkano–Kinniö	Parkano	K	

Nimi	Toinen nimi	Lyhenne	Km Hki	Rataosus	Kunta	Liikenteen-ohjaus	Yksityisraiteita	Vaihtoyö-mahdollisuus
Namn	Annat namn	Förkortning		Banavsnitt	Kommun	Trafikledning	Privata spårsläggningar	Möjlighet till växning
Name	Another name	Abbr.		Section	Municipality	Traffic control	Private sidings	Shunting
Kaittjärvi		Kir	228+609	Kouvola–Joensuu	Luumäki	K		
Kajaani	Kajaani	Kaj	633+491	Pieksämäki–Kontiomäki, Kajaani–Lammintieni	Kajaani	K		K
Kaleton		Ktn	320+875	Haapavesi–Jyväskylä	Keuruu	K		
Kalkku		Kau	199+471	Lielaiti–Kokemäki	Tampere	K		K
Kalliovarasto		Kao	644+770	Pieksämäki–Kontiomäki	Kajaani	K		
Kallisahti		Kli	465+822	Huutokoski–Savonlinna	Savonlinna	K		
Kalvitса		Ksa	330+605	Kouvola–Pieksämäki	Mikkeli	K		
Kangas		Kgs	642+466	Seinäjoki–Oulu	Ylivieska	K		
Kannelmäki	Gamlas	Kan	9+300	Houpalahti–Vantaankoski	Helsinki	K		
Kannonkoski		Ksi	488+694	Äänekoski–Haapavesi	Kannonkoski	M		
Kannus		Kns	591+582	Seinäjoki–Oulu	Kannus	K		
Karhejärvi		Krr	224+902	Tampere–Seinäjoki	Ylöjärvi	K		
Karhukangas		Khg	621+508	Seinäjoki–Oulu	Ylivieska	K		
Karjaa	Karis	Kr	87+058	Hyvinkää–Karihaa, Karjaa–Hanko, Helsinki päärautatieasema–Turku satama	Raasepori	K		
Karkku		Kru	230+733	Lielaiti–Kokemäki	Sastamala	K		
Karviainen		Kar	247+320	Toijala–Turku päärautatieasema	Aura	K		
Kaskinen		Ksk	530+522	Seinäjoki–Kaskinen	Kaskinen	K		
Kattilaajarju		Kth	205+556	Kouvola–Joensuu	Kouvolta	K		
Kauhajoki		Kji	472+720	Seinäjoki–Kaskinen	Kauhajoki	K		
Kauhava		Kha	455+728	Seinäjoki–Oulu	Kauhava	K		
KAUKLAHTI		Kal	–	Helsingin päärautatieasema–Turku satama		K		
Kauklahti asema	Kökä	Klh	24+277		Esbo	K		
Mankki	Mankby	Mnk	25+401		Kirkkonummi	K		
Kaulinranta		Klr	963+350		Ylitornio	K		

Nimi	Toinen nimi	Lyhenne	Km Hki	Rataosuuus	Kunta	Liikenteen-ohjaus	Yksityisrakenteita	Vaihtoyö-mahdollisuus
Namn	Annat namn	Förkortning	Banavsnitt	Kommun	Trafikledning	Privata spåranläggningar	Möjlighet till växning	
Name	Another name	Abbr.	Section	Municipality	Traffic control	Private sidings	Shunting	
Kauniainen	Grankulla	Kni	16+054	Helsingi päärautatieasema-Turku satama	Kauniainen	K	K	K
Kaupilanmäki		Kpl	568+751	Pieksämäki–Kontiomäki	Iisalmi	K	K	K
Kausala		Ka	169+425	Riihimäki–Kouvola	Iitti	K	K	K
Kauttua		Ktu	310+423	Kiukainen–Säkylä	Eura	M	K	K
Keitelepohja		Ktp	519+256	Äänekoski–Haapavesi	Viitasari	M	K	K
Kekomäki		KeK	79+288	Riihimäki–Kouvola	Hausjärvi	K	K	K
Keijo		KeJ	336+692	Tampere–Jyväskylä	Jyväskylä	K	K	K
Keikkamäki		Klk	399+992	Jyväskylä–Pieksämäki	Laukaa	M	K	K
Kelloselkä		Kls	1135+115	Kemijärvi–Kelloselkä	Salla	M	K	K
Kemi		Kem	858+300	Oulu–Laurila, Kemi–Ajos	Kemi	K	K	K
Kemijärvi		Kjä	1056+399	Laurila–Kemijärvi, Kemijärvi–Kelloselkä	Kemijärvi	K	K	K
Kemira		Ker	495+600	Silinjärvi–Viinijärvi	Silinjärvi	K	K	K
Kempeli		Kml	741+075	Seinäjoki–Oulu	Kempeli	K	K	K
Kera		Kea	14+536	Helsingi päärautatieasema-Turku satama	Esbo			
KERAVA								
Kerava asema	Kervo	Ke	28+869	Kerava–Vuosaari, Kerava–Stöldvik, Kerava–Hakosilta, Helsinki päärautatieasema–Riihimäki	Kerava	K	K	K
Kytömaa		Kyt	31+274		Kerava	K	K	K
Kerimäki		Kiä	495+532	Savonlinna–Parikkala	Kerimäki	K	K	K
Kesälähti		Kti	428+003	Kouvola–Joensuu	Kesälähti	K	K	K
Keuruu		Keu	316+041	Haapavesi–Jyväskylä	Keuruu	K	K	K
Kihniö		Kiö	444+460	Niinisalo–Parkano–Kihniö	Kihniö	M	M	K
Kiiala		Kia	60+013	Olli–Porvoo	Porvoo			
Kilo		Kil	13+035	Helsinki päärautatieasema–Turku satama	Espoo			
Kilpua			668+910	Seinäjoki–Oulu	Qulainen	K	K	K

Nimi	Toinen nimi	Lyhenne	Km Hki	Rataosuuus	Kunta	Liikenteen-ohjaus	Yksityisraiteita	Vaihtotyö-mahdollisuus
Namn	Annat namn	Förkortning	Banavsnitt		Kommun	Trafikledning	Privata spårarläggningar	Möjlighet till växning
Name	Another name	Abbr.		Section	Municipality	Traffic control	Private sidings	Shunting
Kinahni		Knh	508+922	Silinjärvi–Viinijärvi	Niisiä		K	
Kinni		Kii	247+982	Kouvola–Pieksämäki	Mäntyharju	K		
Kirkkonummi	Kyrkstätt	Kkn	37+504	Helsingin päärautatieasema–Turku satama	Kirkkonummi	K		K
Kirkniemi	Gerknäs	Krn	136+261	Hyvinkää–Karjaa	Lohja	K		K
Kitee		Kit	460+016	Kouvola–Joensuu	Kitee	K		K
Kiuainen		Kn	297+395	Kokemäki–Rauma, Kiukainen–Säkylä	Eura	K		
Kiuruvesi		Krv	583+990	Iisalmi–Ylivieska	Kiuruvesi	K		K
Kivesjärvi		Kvj	878+147	Oulu–Kontiomäki	Paltamo	K		
Kohtavaara		Köh	776+308	Joensuu–Nurmes	Nurmes	K		
Koivu		Kvu	923+373	Laurila–Kemijärvi	Tervola	K		K
Kotuhovi	Björkgård	Kvh	17+861	Helsingin päärautatieasema–Turku satama	Esbo			
Koivukylä	Björkdby	Kvy	19+440	Helsingin päärautatieasema–Riihimäki	Vantaa			
Kokemäki	Kumo	Kki	284+442	Kokemäki–Rauma, Lielaiti–Kokemäki, Kokemäki–Pori	Kokemäki	K		
Kokkola	Karleby	Kok	551+441	Seinäjoki–Oulu, Kokkola–Yksipihaja	Kokkola	K		K
Kolari		Kli	1067+206	Tornio–Kolari	Kolari	K		K
Kolho		Klo	286+265	Orivesi–Seinäjoki	Mänttä–Vilppula	K		K
Koppi		Kpi	525+100	Seinäjoki–Oulu	Pedersöre	K		K
Kommila		Kmm	429+700	Varkaus–Kommila	Varkaus	K		K
Komu		Kom	607+179	Iisalmi–Ylivieska	Pyhäjärvi	K		K
Kontiolahti		Khi	640+295	Joensuu–Nurmes	Kontiolahti	K		
Kontiomäki	Källby	Kon	658+785	Pieksämäki–Kontiomäki, Kontiomäki–Ammänsaari, Nurmes–Kontiomäki, Kontiomäki–Vartiusraja, Oulu–Kontiomäki	Paltamo	K		K
Koppnäs		Kop	203+540	Karjaa–Hanko	Hanko	K		K
Koria		Kra	185+374	Riihimäki–Kouvolala	Kouvolala	K		K

Nimi	Toinen nimi	Lyhenne	Km Hki	Rataosuuus	Kunta	Liikenteen-ohjaus	Yksityisraiteita	Vaihtotyö-mahdollisuus
Namn	Annat namn	Förkortning	Banavsnitt	Kommun	Trafikledning	Privata spåranläggningar	Möjlighet till växning	
Name	Another name	Abbr.	Section	Municipality	Traffic control	Private sidings	Shunting	
Korkeakoski		Kas	247+910	Orivesi-Seinäjoki	Juupajoki	K	K	K
Korsö		Krs	22+669	Helsingi päärautatieasema–Riihimäki	Vantaa	K		
Korvensuo		Ksu	50+500	Kerava–Hakosilta	Mäntsälä	K		
Koskenkorva		Kos	442+447	Seinäjoki–Kaskinen	Ilmajoki	M	K	K
KOTKA		Kot	–	Kouvola–Kotka, Kotka Hovinsaari–Kotka Mussalo	M			
<i>Kotka Hovinsaari</i>		<i>Hos</i>	240+400		<i>Kotka</i>		K	K
<i>Kotka tavara</i>		<i>Ktt</i>	240+870		<i>Kotka</i>		K	K
<i>Paimenportti</i>		<i>Pti</i>	241+450		<i>Kotka</i>			
<i>Kotka asema</i>		<i>Kta</i>	242+775		<i>Kotka</i>		K	
<i>Kotkan satama</i>		<i>Kts</i>	243+579		<i>Kotka</i>		K	
<i>Kotka Mussalo</i>		<i>Mss</i>	247+057		<i>Kotka</i>		K	
KOUVOLA		Kvl	–	Kouvola–Pieksämäki, Riihimäki–Kouvola, Kouvola–Kotka, Kouvola–Kuussankoski	M			
<i>Kouvola asema</i>		<i>Kv</i>	191+540		<i>Kouvola</i>		K	K
<i>Kouvola lajittelu</i>		<i>Kvla</i>	192+570		<i>Kouvola</i>		K	K
<i>Kouvola tavara</i>		<i>Kvt</i>	194+050		<i>Kouvola</i>		K	K
<i>Kouvola Oikoraide</i>		<i>Oik</i>	194+460		<i>Kouvola</i>			
<i>Kullasvaara</i>		<i>Kuv</i>	197+300		<i>Kouvola</i>			
Kovjoki		Koi	508+925	Seinäjoki–Oulu	Uusikaarlepyy	K		
Kruunupyy		Kpy	537+585	Seinäjoki–Oulu	Kruunupyy	K		
Kuivasjärvi		Kis	276+327	Tampere–Seinäjoki	Parkano	K	K	K
KUOPIO		Kpo	–	Pieksämäki–Kontiomäki	M		K	K
<i>Kuopio asema</i>		<i>Kuo</i>	464+590		<i>Kuopio</i>		K	K
<i>Kuopio tavara</i>		<i>Kuot</i>	465+500		<i>Kuopio</i>		K	K
Kurkimäki		Krm	444+074	Pieksämäki–Kontiomäki				
Kursu		Kuu	1095+034	Kemijärvi–Kelloselkä	Salla	M		

Nimi	Toinen nimi	Lyhenne	Km Hki	Rataosuuus	Kunta	Liikenteen-ohjaus	Yksityisraiteita	Vaihtoyö-mahdollisuus
Namn	Annat namn	Förkortning		Banavsmitt	Kommun	Trafikledning	Privata spåränläggningar	Möjlighet till växning
Name	Another name	Abbr.		Section	Municipality	Traffic control	Private sidings	Shunting
Kuurila		Ku	138+769	Riihimäki–Tampere	Hämeenlinna	K		
Kuusankoski		Kuk	199+290	Kouvolan–Kuusankoski	Kouvolan	M	K	K
Kylälahti		Kyn	742+945	Joensuu–Nurmeksen	Lieksa	K		
Kymi	Kymmenen	Ky	233+449	Kouvolan–Kotka	Kotka	M	K	K
Kyminiinna		Kln	237+352	Kouvolan–Kotka	Kotka	K		
Kyrö		Kö	232+878	Toijala–Turku päärautatieasema	Karinainen	K		
Kyrölä		Krö	34+387	Helsingin päärautatieasema–Riihimäki	Järvenpää	K		
Kälviä		Klv	568+144	Seinäjoki–Oulu	Kokkola	K		
Köykkäri		Kök	486+491	Seinäjoki–Oulu	Kauhava	K		
Lahdenperä		Lpr	267+080	Tampere–Jyväskylä	Jämsä	K		
Lahnaslampi		Lhn	881+053	Vuokatti–Lannastampi	Sotkamo	K		
Lahti	Lantis	Lh	130+335	Lahti–Loviisan satama, Riihimäki–Kouvolan, Lahti–Heinola	Lahti	K		
Laihia	Laihela	Lai	468+916	Seinäjoki–Vaasa	Laihia	K		
Lakiala		Lak	209+214	Tampere–Seinäjoki	Ylöjärvi	K		K
Lamminkoski		Lmk	268+785	Tampere–Seinäjoki	Parkano	K		
Lamminniemi		Lam	636+664	Kajaani–Lamminniemi	Kajaani	K		
Lapinjärvi		Lpj	185+432	Lahti–Loviisan satama	Lapinjärvi	M		
Lapinlahti		Lna	525+606	Pieksämäki–Kontiomäki	Lapinlahti	K		
Lapinneva		Lpn	415+621	Niinisalo–Parkano–Kihniö	Parkano	K		
Lappeenranta	Vilmanstrand	Lr	287+726	Kouvolan–Joensuu, Lappeenranta–Mustolan satama	Lappeenranta	K		
Lappila		Laa	97+695	Riihimäki–Kouvolan	Kärkölä	K		
Lappohja		Lpo	189+639	Karjaan–Hanko	Hanko	K		
Lapua		Lpa	441+094	Seinäjoki–Oulu	Lapua	K		
Larvakyti		Lyö	333+057	Tampere–Seinäjoki	Seinäjoki	K		
Laukaa		Lau	401+193	Jyväskylä–Äänekoski	Laukaa	K		
Laurila		Lla	865+776	Laurilan–Tornio–raja,				

Nimi	Toinen nimi	Lyhenne	Km Hki	Rataosus	Kunta	Liikenteen-ohjaus	Yksityisraiteita	Vaihtoyö-mahdolisuus
Namn	Annat namn	Förkortning		Banavsnitt	Kommun	Trafikledning	Privata spåraniläggningar	Möjlighet till växning
Name	Another name	Abbr.		Section	Municipality	Traffic control	Private sidings	Shunting
Lauritsala		Lrs	292+240	Oulu–Laurila, Laurila–Kemijärvi	Keminmaa	K	K	K
Lautiosaari		Li	863+064	Kouvolा–Joensuu	Lappeenranta	K	K	K
Leikkola		Lkl	276+011	Oulu–Laurila, Lautiosaari–Eijärví	Kemi	K		
Lempäälä		Lpä	165+810	Kouvolा–Pieksämäki	Hirvensalmi	K		
Lepäkoski		Lk	87+830	Riihimäki–Tampere	Lempäälä	K		
Leppävaara	Albergå	Lpv	11+249	Helsingin päärautatieasema–Turku satama	Janakkala	K		
Leteensuo		Lts	123+554	Riihimäki–Tampere	Esbo	K		
Lieksa		Lis	728+122	Joensuu–Nurmeks,	Hattula	K		
Lieksan teollisuuskylä		Ltk	728+847	Lieksa–Pankakoski	Lieksa	K		
Lielaiti		Llh	193+392	Lielaiti–Kokemäki,	Lieksa	K		
Lievestuore		Lvt	402+191	Tampere–Seinäjoki	Tampere	K		
Liminka		Lka	728+483	Jyväskylä–Pieksämäki	Laukaa	K		
Lohiluoma		Luo	463+619	Seinäjoki–Oulu	Liminka	K		
Lohja		Lo	122+965	Hyvinkää–Karjaa, Lohja–Lohjanjärvi	Kurikka	K		
Lohjanjärvi		Loj	128+036	Seinäjoki–Lohjanjärvi	Lohja	K		
Loimaa		Lm	208+870	Toijala–Turku päärautatieasema	Loimaa	K		
Louhela		Loh	13+190	Huopalahti–Vantaankoski	Vantaa	K		
Loukolampi		Loi	360+013	Kouvolा–Pieksämäki	Pieksämäki	K		
Loviisan satama		Lvs	207+209	Lahti–Loviisan satama	Loviisa	M	K	K
Luikonlahti		Lui	557+061	Silttijärvi–Viinijärvi	Kaavi	K		
Luoma		Lma	27+807	Helsingin päärautatieasema–Turku satama	Kirkkonummi	K		
Lusto		Lus	509+170	Savonlinna–Parikkala	Punkaharju	K		
Luumäki		Lä	250+540	Kouvolा–Joensuu, Luumäki–Vainikkala–raja	Luumäki	K		

Nimi	Toinen nimi	Lyhenne	Km Hki	Rataosuuus	Kunta	Liikenteen-ohjaus	Yksityisraiteita	Vaihtotyö-mahdollisuus
Namn	Annat namn	Förkortning		Banavsnitt	Kommun	Trafikledning	Privata spårsläggningar	Möjlighet till växning
Name	Another name	Abbr.		Section	Municipality	Traffic control	Private sidings	Shunting
Lähde mäki		Läh	79+373	Kerava-Hakosilta	Orimattila	K		
Länkipohja		LÄP	255+980	Tampere-Jyväskylä	Jämsä	K		
Maanselkä		Mlk	836+049	Nurmes-Kontiomäki	Sotkamo	M		K
Maaria		Mri	262+070	Toijala-Turku päärautatieasema	Turku	K		
Madesjärvi		Md	291+821	Tampere-Seinäjoki	Jalasjärvi	K		K
Majajärvi		Mjj	216+317	Tampere-Seinäjoki	Ylöjärvi	K		
Malmi		Mli	10+900	Helsingin päärautatieasema-Riihimäki	Helsinki	K		
Malminkartano		Mlo	10+730	Huopalahti-Vantaankoski	Helsinki	K		
Mäkkälä		Mrk	403+737	Pieksämäki-Kontiomäki	Suonenjoki	K		
Martinlaakso		Mrl	14+010	Huopalahti-Vantaankoski	Vantaa	K		
Masa lä		Mas	29+561	Helsingin päärautatieasema-Turku satama	Kirkkonummi	K		
Markanева		Mtv	562+059	Seinäjoki-Oulu	Kokkola	K		
Mattila		Mat	159+906	Riihimäki-Tampere	Lempäälä	K		
Mettola		Mel	149+851	Hyvinkää-Karjaa	Raasepori	K		
Metsäkansa		Msä	155+968	Toijala-Valkeakoski	Valkaakoski	K		
Mikkeli		Mi	305+165	Kouvolta-Pieksämäki	Mikkeli	K		
Misi		Mis	1021+256	Laurila-Kemijärvi	Rovaniemi	M		
Mommila		Mla	91+430	Riihimäki-Kouvola	Hausjärvi	K		
Muhos		Mh	788+424	Oulu-Kontiomäki	Muhos	K		
Mukkula		Muk	140+012	Lahti-Mukkula	Lahti	K		
Murtomäki		Mur	613+166	Murtonäki-Talvivaara, Murtonäki-Otannmäki, Pieksämäki-Kontiomäki	Kajaani	K		K
Mustio		Mso	143+000	Hyvinkää-Karjaa	Raasepori	K		K
Mustolan satama		Mst	296+720	Lappeenranta-Mustolan satama	Lappeenranta	K		
Muukko		Mko	297+112	Kouvola-Joensuu	Lappeenranta	K		
Muurame		Muu	324+768	Tampere-Jyväskylä	Muurame	K		
Muurola		Mul	948+494	Laurila-Kemijärvi	Rovaniemi	K		

Nimi	Toinen nimi	Lyhenne	Km Hki	Rataosuu	Kunta	Liikenteen-ohjaus	Yksityisraiteita	Vaihtoyö-mahdollisuus
Namn	Annat namn	Förkortning		Banavsnitt	Kommun	Trafikledning	Privata spåraniäggningsar	Möjlighet till växning
Name	Another name	Abbr.		Section	Municipality	Traffic control	Private sidings	Shunting
Myllykangas		Mys	815+693	Oulu-Laurila	Ii	K		
Myllykoski		Mki	203+741	Kouvola-Kotka	Kouvola	K		
Myllymäki		My	333+721	Orivesi-Seinäjoki	Ahtiari	K		
Myllyoja		Myl	161+727	Lahti-Heinola	Heinola	K		
Myyntiä		Myt	270+889	Kouvola-Pieksämäki, Mynttilä-Ristiina				
Mymämäki		Myn	229+607	Turku päärautatieasema-Uusikaupunki	Mynämäki	K		
Myrskylä		Myä	169+771	Lahti-Lovisan satama	Lapinjärvi	K		
Myrmäki		Myr	12+130	Huopalahti-Vantaankoski	Vantaa	K		
Mäkkylä		Mäk	9+511	Helsinki päärautatieasema-Turku satama				
Mäntsälä		Mlä	59+210	Kerava-Hakosilta	Mäntsälä	K		
Mänttä		Män	282+740	Vilppula-Mänttä	Mänttä-Vilppula	K		
Mäntyharju		Mr	262+680	Kouvola-Pieksämäki	Mäntyharju	K		
Mäntyluoto		Mn	342+020	Pori-Mäntyluoto	Pori	M		
Nädendal		Nnl	213+193	Raisio-Naantali	Naantali	K		
Naarajärvi		Nri	449+862	Jyväskylä-Pieksämäki	Pieksämäki	K		
Nakkila		Nal	308+091	Kokemäki-Pori	Nakkila	K		
Nastola		Nsl	146+150	Riihimäki-Kouvola	Nastola			
Niemenpää		Nmp	923+605	Tornio-Kolari	Tornio	K		
Niimima		Nii	383+155	Orivesi-Seinäjoki	Alavus			
Niinimäki		Nmä	172+534	Riihimäki-Kouvola	Iitti	K		
Niinisalo		Nns	386+215	Niinisalo-Parkano-Kihniö	Kankaanpää	M		
Niirala		Nrl	555+846	Niirala-raja-Säkäniemi	Tohmajärvi	M		
Niirala-raja		Nrr	554+080	Niirala-raja-Säkäniemi	Tohmajärvi	K		
Niittyjahti		Nth	613+475	Kouvola-Joensuu	Joensuu	K		
Nikkilä		Nlä	39+176	Kerava-Sköldvik	Sipo			
Nivala		Nvi	676+887	Uusalmi-Ylivieska	Nivala	K		

Nimi	Toinen nimi	Lyhenne	Km Hki	Rataosuuus	Kunta	Likenteen-ohjaus	Yksityisraiteita	Vaihtotyö-mahdollisuus
Namn	Annat namn	Förkortning		Banavsnitt	Kommun	Trafikledning	Privata spåranläggningar	Möjlighet till växling
Name	Another name	Abbr.		Section	Municipality	Traffic control	Private sidings	Shunting
Nokia		Noa	204+004	Lielanti–Kokemäki	Nokia	K	K	K
Nummela		Nm	109+368	Hyvinkää–Karjaa	Vihni	K	K	K
Nupputinna		Nup	44+170	Helsingin päärautatieasema–Riihimäki	Tuusula			
Nurmes		Nrm	784+420	Nurmekoski–Kontiomäki, Joensuu–Nurmekoski	Nurmekoski	K	K	K
Näpiö		Närpes	518+255	Seinäjoki–Kaskinen	Näpiö			
Ohennämäki		Ohm	542+264	Pieksämäki–Kontiomäki	Ilsalmi	K	K	K
Olli		Olli	45+734	Olli–Porvoo, Kerava–Sköldvik	Porvoo	K	K	K
Ornitola		Ont	631+177	Pieksämäki–Joensuu	Joensuu	K	K	K
Orimattila		Om	150+407	Lahti–Loviisan satama	Orimattila			
Orivesi		Ov	228+276	Tampere–Jyväskylä, Orivesi–Seinäjoki	Orivesi	K	K	K
Orivesi keskusta		Ovk	231+512	Orivesi–Seinäjoki	Orivesi	K	K	K
Otanmäki		Otm	638+822	Murtomäki–Otanmäki	Kajaani	K	K	K
Otava		Ot	290+521	Kouvola–Pieksämäki, Otava–Otanmäki	Mikkelin kaupunki	K	K	K
Otavan satama		Ots	292+885	Otava–Otavan satama	Mikkelin kaupunki	K	K	K
Oulainen		Ou	657+850	Oulainen	Oulainen	K	K	K
OUULI		Oul	–	Seinäjoki–Oulu, Oulu–Kontiomäki, Oulu–Laurila	M	K	K	K
Oulu Nokela		Nok	750+030	Oulu	Oulu	K	K	K
Oulu Oritkari		Ori	751+180	Oulu	Oulu	K	K	K
Oulu tavara		Olt	751+360	Oulu	Oulu	K	K	K
Oulu asema		Ol	752+778	Oulu	Oulu	K	K	K
Oulu Tuira		Tua	755+510	Helsingin päärautatieasema–Turku satama	Paimio	K	K	K
Paimio		Po	171+885	Helsingin päärautatieasema–Turku satama	Hyvinkää	K	K	K
Palopuro		Pip	54+535	Helsingin päärautatieasema–Oulu–Kontiomäki	Paltamo	K	K	K
Paitta Oy		Poy	905+050					

Nimi	Toinen nimi	Lyhennet	Km Hki	Rataosuuus	Kunta	Liikenteen-ohjaus	Yksityisraiteita	Vaihtotyö-mahdollisuus
Namn	Annat namn	Förkortning		Banavsnitt	Kommun	Trafikledning	Privata spåraniläggningar	Möjlighet till växning
Name	Another name	Abbr.		Section	Municipality	Traffic control	Private sidings	Shunting
Paltamo		Pto	901+579	Oulu–Kontiomäki	Paltamo	K	K	K
Pankkoski		Pas	731+865	Lieksa–Pankkoski	Lieksa	K	K	K
Parikkala		Par	387+302	Kouvolan–Joensuu,				K
Parkano		Pko	262+483	Savonlinna–Parikkala	Parikkala	K		
				Niinisalo–Parkano–Kihniö,				
				Tampere–Seinäjoki	Parkano	K		
				Riihimäki–Tampere	Hattula	K		
				Tornio–Kolari	Pello	K		
Parola		Pri	115+764	Pieksämäki–Kontiomäki	Iisalmi	K		
Pello		Pel	1002+632	Tampere–Seinäjoki	Seinäjoki	K		
Peitonsalmi		Pmi	545+355	Kontiomäki–Ämmänsaari	Suomussalmi	M		
Peräseinäjoki		Psj	318+481	Haapavesi–Jyväskylä	Petäjävesi	K		
Pesiötyrä		Psk	732+752	–	Kouvolan–Pieksämäki,			
Petäjävesi		Pvi	343+357	Jyväskylä–Pieksämäki,	Pieksämäki	M		
PIEKSÄMÄKI		Pie	–	Pieksämäki–Joensuu	Pieksämäki	K		
				Pm	376+000	K		
				Tmu	377+340	K		
				Pmla	378+640	K		
				Pmt	379+960	K		
				Pts	528+780	Pietarsaari–Alholma,		
						Pärranainen–Pietarsaari		
				Ph	312+500	Orivesi–Seinäjoki	Keuruu	K
				Pp	540+605	Äänekoski–Haapajärvi	Pihlupudas	M
				Ptk	182+784	Helsingin päärautatieasema–Turku satama	Kaarina	K
				Pkl	771+765	Oulu–Kontiomäki	Oulu	K
				Pjm	8+474	Helsingin päärautatieasema–Turku satama	Helsinki	
				Skuru	94+907	Helsingin päärautatieasema–		

Nimi	Toinen nimi	Lyhennet	Km Hki	Rataosuuus	Kunta	Liikenteen-ohjaus	Yksityisraiteita	Vaihtotyö-mahdollisuus
Namn	Annat namn	Forkortning		Banavsnitt	Kommun	Trafikledning	Privata spåranläggningar	Möjlighet till växning
Name	Another name	Abbr.		Section	Municipality	Traffic control	Private sidings	Shunting
Pohjois-Haaga	Norra Haga	Poh	8+050	Turku satama	Raahepori	K	K	K
Pohjois-Louko		Plu	329+329	Huopalatti–Yantaankoski	Helsingi	K		
Poikkeus		Pkk	254+744	Tampere–Seinäjoki	Seinäjoki	K		
Poiksila		Poi	416+728	Tampere–Seinäjoki	Parkano	K		
Pori	Björneborg	Pri	322+278	Kouvolala–Joensuu	Kesälahti	K		
				Kokemäki–Pori, Pori–Ruoniemi, Pori–Mäntyluoto	K			
				Nurmesteri	Pori	M	K	K
				Nurmesteri	Nurmesteri	K	K	K
				Olli–Porvoo	Porvoo	K	K	K
		Prv	62+287	Kouvolala–Joensuu	Kitee	K	K	K
		Pus	452+808	Helsingi päärautatieasema–Riihimäki	Helsingi	K		
		Pia	14+262	Helsingi päärautatieasema–Riihimäki	Lappeenranta	K		
		Pmk	9+346	Helsingi päärautatieasema–Riihimäki	Punkaharju	K		
		Pl	262+491	Luumäki–Vainikkala–raja	Helsingi	K		
		Pun	515+111	Savonlinna–Parikkala	Lappeenranta	K		
		Pyk	615+415	Pyhäkumpu erkanemisvaihde– Pyhäkumpu	Punkaharju	K		
		Pys	613+511	Pyhäkumpu erkanemisvaihde– Pyhäkumpu, Iisalmi–Ylivieska	Pyhäjärvi	K		
		Phä	615+939	Iisalmi–Ylivieska	Pyhäjärvi	K		
		Phä	518+604	Seinäjoki–Oulu,	Pedersöre	K		
				Pännäinen–Pietarsaari	Savonlinna	K	K	K
				Savonlinna–Parikkala	Raahe	K	K	K
				Tuomiola–Raahe	Lappeenranta	K	K	K
				Luumäki–Vainikkala–raja	Raisio	K	K	K
				Turku päärautatieasema– Uusikaupunki, Raisio–Naantali	Nurmijärvi	K	K	K
				Hyvinkää–Karjaan	Seinäjoki–Oulu	K	K	K
				448+450	Lapua	K		
				445+165	Rantasalmi	K		

Nimi	Toinen nimi	Lähenne	Km Hki	Rataosuuus	Kunta	Liikenteen-ohjaus	Yksityisraiteita	Vaihtotyö-mahdollisuus
Namn	Annat namn	Förkortning		Banavsnitt	Kommun	Trafikledning	Privata spåränläggningar	Möjlighet till växning
Name	Another name	Abbr.		Section	Municipality	Traffic control	Private sidings	Shunting
Rasin suo				258+510	Kouvola-Joensuu			
Ratikylä		Rilä		284+344	Tampere-Seinäjoki			K
Rauha		Rah		318+490	Kouvola-Joensuu			K
Rauhalanti		Rhl		380+510	Jyväskylä–Pieksämäki			K
Rauma		Rma		331+659	Kokemäki–Rauma			K
Raunio		Rio		464+660	Seinäjoki–Oulu			
Rautaruukki		Rat		730+050	Tuomiola–Raahen			
Rautjärvi		Rjä		345+788	Kouvola–Joensuu			
Rautipohja		Rph		372+829	Haapavesi–Jyväskylä			
Rekola		Rkl		20+615	Helsingin päärautatieasema–Riihimäki			
Retretti		Ree		507+500	Savonlinna–Parikkala			
RIIHIMÄKI		Rii		Helsinki päärautatieasema–Riihimäki, Riihimäki–Kouvola, Riihimäki–Tampere				
				-				
Riihimäki Arolampi		Arp		66+600				
Riihimäki tavara		Rit		68+773				
Riihimäki laittelu		Rila		70+068				
Riihimäki asema		Ri		71+410				
Riijärvi		Rjr		502+597	Seinäjoki–Oulu			
Rippa		Rpa		578+065	Seinäjoki–Oulu			
Ristiina		Rst		291+162	Mynttilä–Ristina			
Ristijärvi		Riv		678+804	Kontiomäki–Ämmänsaari			
Rovaniemi		Roi		971+775	Laurila–Kemijärvi			
Ruuna		Rha		433+128	Seinäjoki–Oulu			
Runni		Rmn		568+522	Iisalmi–Ylivieska			
Ruosniemi		Rsn		330+936	Pori–Ruotsineli			
Ruukki		Rki		705+228	Seinäjoki–Oulu			
Ryttylä		Ry		80+770	Riihimäki–Tampere			

Nimi	Toinen nimi	Lyhenne	Km Hki	Rataosuuus	Kunta	Liikenteen-ohjaus	Yksityisraiteita	Vaihtotyö-mahdollisuus
Namn	Annat namn	Förkortning		Banavsnitt	Kommun	Trafikledning	Privata spåraniläggningar	Möjlighet till växning
Name	Another name	Abbr.		Section	Municipality	Traffic control	Private sidings	Shunting
Röyttä		Röy	893+917	Tornio–Röyttä	Tornio	K	K	K
Saakoski		Saa	305+373	Tampere–Jyväskylä	Jyväskylä	K		
Saari		Sr	405+246	Kouvolan–Joensuu	Parikkala	K		K
Saarijärvi		Srj	452+723	Äänekoski–Haapavesi	Saarijärvi	M		K
Salla		Sll	1121+403	Kemijärvi–Kelloeskä	Salla	M		K
Salminen		Sln	426+718	Piekämäki–Kontiomäki, Piekämäki–Kontiomäki	Suonenjoki	K		K
Salmivaara		Smv	1111+444	Kemijärvi–Kelloeskä	Salla	K		K
Salo		Slo	143+981	Helsingin päärautatieasema– Turku satama	Salo	K		K
Sammalisto		Sam	74+487	Riihimäki–Tampere	Riihimäki	K		
Santala		Sta	196+908	Karjaa–Hanko	Hanko			
Saunamäki		Smä	180+534	Riihimäki–Kouvola	Iitti	K		
Savio		Sav	26+265	Helsingin päärautatieasema–Riihimäki	Kerava			
Savonlinna		Sl	481+772	Huutokoski–Savonlinna, Savonlinna–Parikkala	Savonlinna	K		
Savonlinna-Kauppatori		Slk	482+748	Savonlinna–Parikkala	Savonlinna			
SEINÄJOKI		Sei	–	Tampere–Seinäjoki, Seinäjoki–Oulu, Orivesi–Seinäjoki, Seinäjoki–Vaasa, Seinäjoki–Kaskinen		M		K
Seinäjoki tavarat		Skt	416+580	Seinäjoki		K		K
Seinäjoki asema		Sk	418+001	Seinäjoki		K		K
Selänpää		Spä	209+869	Kouvola–Pleksämäki	Kouvola	K		
Sieppijärvi		Spi	1045+904	Tornio–Kolari	Kolari	K		K
Sievi		Svi	613+592	Seinäjoki–Oulu	Sievi	K		K
Silkamäki		Skä	389+745	Pieksämäki–Joensuu	Pieksämäki	K		K
Sillijärvi		Sjj	489+718	Pieksämäki–Kontiomäki, Sillijärvi–Viljäjärvi	Sillijärvi	K		K

Nimi	Toinen nimi	Lyhenne	Km Hki	Rataosuuus	Kunta	Liikenteen-ohjaus	Yksityisyrityksetta	Vaihtotyö-mahdollisuus
Namn	Annat namn	Förkortning		Banavsnitt	Kommun	Trafikledning	Privata spåranläggningar	Möjlighet till växning
Name	Another name	Abbr.		Section	Municipality	Traffic control	Private sidings	Shunting
Simo		Sim	833+715	Oulu–Laurila	Simo	K	K	K
Simpeli		Spl	368+317	Kouvolala-Joensuu	Rautjärvi	K	K	K
Sipilä		Sip		Kerava–Hakosilta, Kerava–Hakosilta	Mäntsälä	K		
Sisättö		Stö	235+602	Tampere–Seinäjoki	Ikaalinen	K		
Siuntio		Sti	51+285	Helsingin päärautatieasema–Turku satama	Siuntio	K		
Siuro		Siu	213+355	Lielaiti–Kokemäki	Nokia	K		
Skogby		Sgy	184+790	Karjaa–Hanko	Raasepori	M		
Sköldvik		Sld	56+360	Kerava–Sköldvik	Porvoo	K		
Soinlahti		Kilpilahti	559+340	Pieksämäki–Kontiomäki	Ilsalmi	K		
Sorsasalo		Soa	473+775	Pieksämäki–Kontiomäki	Kuopio	K		
Sukava		Sor	589+222	Pieksämäki–Kontiomäki	Sonkajärvi	K		
Suolahti		Skv	417+796	Jyväskylä–Äänekoski	Äänekoski	K		
Suonenjoki		Suo	413+842	Pieksämäki–Kontiomäki,				
		Snj		Suonenjoki–Iisivesi	Suonenjoki	K		
		Snm	220+655	Lielaiti–Kokemäki	Nokia	K		
		Syr	452+865	Pieksämäki–Joensuu	Heinävesi	K		
		Ski	341+621	Tampere–Seinäjoki	Seinäjoki	K		
		Smj	669+601	Sillinnjärvi–Viinijärvi, Sysmäjärvi–Vuonos	Outokumpu	K		
		Säk	315+928	Kiukainen–Säkylä	Eura	K		
		Sä	586+873	Kouvolala-Joensuu, Niirala-raja–Säkyläniemi	Tohmajärvi Nilsjä	K		
		Skm	504+908	Sillinnjärvi–Viinijärvi	Riihimäki–Tampere	K		
		Sj	177+734		Tampere	K		
		Ta	238+589	Kouvolala-Joensuu	Luumäki	K		
		Tko	350+750	Pori–Mäntyluoto	Pori	K		
		Te	537+605	Pieksämäki–Kontiomäki	Ilsalmi	K		
		Tv	247+245	Tampere–Jyväskylä	Orivesi	K		

Nimi	Toinen nimi	Lyhemme	Km Hki	Rataosuuus	Kunta	Liikenteen-ohjaus	Yksityisraiteita	Väitetöymahdollisuus
Namn	Annat namn	Förkortning		Banavsnitt	Kommun	Trafikledning	Privata spåranläggningar	Möjlighet till växning
Name	Another name	Abbr.		Section	Municipality	Traffic control	Private sidings	Shunting
Talvivara		TIV	637+700	Murtomäki–Talviivaara	Kajaani			
Tammisaari	Ekenäs	Trns	174+056	Karjaa–Hanko	Raasepori			
TAMPERE		Tre	–	Riihimäki–Tampere, Tampere–Seinäjoki, Tampere–Jyväskylä	M			
<i>Tampere tavarat</i>								
Tampere Viinikka		Tpet	186+100		Tampere			K
Tampere asema		Vka	185+400		Tampere			K
Tampere Järvensiu		Tpe	187+389		Tampere			K
Tapanila		Jys	187+814	Helsingi päärautatieasema–Riihimäki	Helsinki			
Tapavainoina		Tna	12+548	Kouvola–Joensuu	Lappeenranta			
Tavastila		Tap	270+405	Kouvola–Kotka	Kotka			
Tervioki		Tsl	228+854	Seinäjoki–Vaasa	Isokyrö			
Tervasuo		Tk	460+156	Joensuu–Ilomantsi	Joensuu			
Tervola		Tsu	645+040	Laurila–Kemijärvi	Tervola			
Östermark		Trv	900+521	Seinäjoki–Kaskinen	Teuva	M		
Dickursby		Tuv	497+474	Kouvola–Joensuu	Tohmajärvi	K		
Tikkila		Tkk	592+461	Helsingi päärautatieasema–Riihimäki	Vantaa	K		
Tikkurila		Tkl	15+721	Niirala–raja–Säkäniemi	Tohmajärvi	K		
Tohmajärvi		Toh	571+752	Toijala–Valkeakoski,				
Toijala		Tl	147+339	Toijala–Turku päärautatieasema, Riihimäki–Tampere	Akaa	K		
Toivala		Toi	479+162	Pieksämäki–Kontiomäki	Siilinjärvi	K		
Tolsa		Tol	35+634	Helsingi päärautatieasema–Turku satama	Kirkkonummi			
Tommola				Riihimäki–Kouvola	Hollola	K		
Torkkelii				Tampere–Jyväskylä	Orivesi	K		
Tornio				Laurila–Tornio–raja, Tornio–Röyttä, Tornio–Kolari	Tornio	K		
					Torneå	K		

Nimi	Toinen nimi	Lyhenne	Km Hki	Rataosuu	Kunta	Liikenteen-ohjaus	Yksityisraiteita	Vaihtotyö-mahdolisuus
Namn	Annat namn	Förkortning		Banavsnitt	Kommun	Trafikledning	Privata spåränläggningar	Möjlighet till växning
Name	Another name	Abbr.		Section	Municipality	Traffic control	Private sidings	Shunting
Tornio-Itäinen	Torneå Östra	Tri	883+307	Laurila-Tornio-rajaa	Tornio			
Tornio-rajaa	Torneå gränsen	Trr	837+236	Laurila-Tornio-rajaa	Tornio			
Tuomarila	Domsby	Tri	19+022	Helsingin päärautatieasema-Turku satama	Esbo			
Tuomojia		Tja	698+504	Tuomiola-Raabe, Seinäjoki-Oulu	Siirojoki			
Turenki		Tu	93+771	Riihimäki-Tampere	Janakkala			
TURKU		Tur	-	Helsingin päärautatieasema-Turku satama, Toijala-Turku päärautatieasema, Turku päärautatieasema-Uusikaupunki				
Kupittaa		Kut	196+372		Turku			
	<i>Åbo central station</i>	Tku	199+674		Turku			
	<i>Åbo hamn</i>	Tkut	200+460		Turku			
	<i>Turku tavarat</i>	Tus	202+510		Turku			
	<i>Turku satama</i>	Vie	209+305		Naantali			
	<i>Turku Viheriänen</i>	Tpv	668+672	Joensuu-Ilomantsi	Joensuu			
	<i>Tuupovaara</i>	Tuu	366+982	Orivesi-Seinäjoki	Alavus			
	<i>Turi</i>	Tör	878+075	Laurila-Kemijärvi	Keminmaa			
	<i>Törmä</i>	Trä	264+972	Kouvolan-Joensuu	Lappeenranta			
	<i>Törölä</i>	Uim	674+451	Joensuu-Nurmekoski	Joensuu			
	<i>Uimaharju</i>	Ur	165+588	Toijala-Turku päärautatieasema	Urijala			
	<i>Uunjala</i>	Ulj	810+501	Oulu-Kontiomäki	Uttajarvi			
	<i>Uutti</i>	Uti	204+085	Kouvolan-Joensuu	Kouvolan			
	<i>Uusikaupunki</i>	Ukp	264+795	Uusikaupunki-Hangonsaari, Turku päärautatieasema-Uusikaupunki	Uusikaupunki			
	<i>Uusikylä</i>	Ukä	150+722	Riihimäki-Kouvolan	Nastola			
	<i>Vaajakoski</i>	Vko	384+866	Jyväskylä-Pieksämäki	Jyväskylä			
	<i>Vaala</i>	Vaa	844+671	Oulu-Kontiomäki	Vaala			

Nimi	Toinen nimi	Lyhenne	Km Hki	Rataosuuus	Kunta	Liiikenteen-ohaus	Yksityisraiteita	Vaihtotyö-mahdollisuus
Namn	Annat namn	Förkortning		Banavsnitt	Kommun	Trafikledning	Privata spåranläggningar	Möjlighet till växning
Name	Another name	Abbr.		Section	Municipality	Traffic control	Private sidings	Shunting
Vaarala	Vasa	Vra	981+460	Laurila–Kemijärvi	Rovaniemi	K	K	K
Vaasa	Vasa	Vs	492+588	Seinäjoki–Vasa, Vaasa–Vaskiluoto	Vaasa	K	K	K
Vahojärvi	Vahojärvi	Vjr	244+926	Tapere–Seinäjoki	Parkano	K	K	K
VAINIKKALA		Vai	–	Luumäki–Vainikkala-raja	M	K	K	K
Vainikkala tavara	Vainikkala asema	Vnat	281+700	Luumäki–Vainikkala-raja	Lappeenranta	K	K	K
Vainikkala-raja	Vainikkala-raja	Vna	282+784	Luumäki–Vainikkala-raja	Lappeenranta	K	K	K
Vaimo	Gjuteriet	Vnr	284+862	Helsingi päärautatieasema–Turku satama	Helsinki	M	M	M
Vaimo	Gjuteriet	Vmo	7+480	Helsingi päärautatieasema–Turku satama	Valkeakoski	K	K	K
Valkeakoski	Valkeakosuo	Vi	164+952	Toijala–Valkeakoski	Toijala–Säkänemi	M	M	K
Valkeakoski	Valkeakosuo	Vso	583+976	Toijala–Säkänemi	Tohmajärvi	K	K	K
Valtimo	Valtimo	Vlm	808+636	Nurmes–Kontiomäki	Valtimo	M	M	K
Vammala	Vammala	Vma	245+885	Lielanti–Kokemäki	Sastamala	K	K	K
Vanattara	Vandaorsen	Vtr	172+340	Riihimäki–Tampere	Lempäälä	K	K	K
Vantaankoski	Vantaankoski	Vks	14+907	Huopalahti–Vantaankoski	Vantaa	K	K	K
Varkaus	Varkaus	Var	424+685	Pieksämäki–Joensuu,	Varkaus	K	K	K
Vartius	Vartius	Vus	753+755	Varkaus–Kommila	Kuhmo	M	M	K
Vartius-Paja	Vartius-Paja	Vur	755+856	Kontiomäki–Yartius-raja	Kuhmo	K	K	K
Vasikkahaka	Vasikkahaka	Vkh	31+175	Kontiomäki–Yartius-raja	Helsingi päärautatieasema–Turku satama	Kirkkonummi	K	K
Vaskiluoto	Vaskiluoto	Vsk	496+463	Vasa–Vaskiluoto	Vaasa	K	K	K
Venetmäki	Venetmäki	Vki	433+164	Jyväskylä–Pieksämäki	Pieksämäki	K	K	K
Vesanka	Vesanka	Vn	364+469	Haapavesi–Jyväskylä	Jyväskylä	K	K	K
Vieikki	Vieikki	Vk	753+979	Joensuu–Nurmese	Lieksa	K	K	K
Vierumäki	Vierumäki	Vrm	153+801	Lahti–Heinola	Heinola	K	K	K
Vihanti	Vihanti	Vti	684+573	Seinäjoki–Oulu	Vihanti	K	K	K
Vihanti	Vihanti	Vih	489+889	Pieksämäki–Joensuu	Heinävesi	K	K	K

Nimi	Toinen nimi	Lyhenne	Km Hki	Rataosuu	Kunta	Likenteen-ohjaus	Yksityisraiteita	Vaihtoyö-mahdolisuus
Namn	Annat namn	Förkortning		Banavsnitt	Kommun	Trafikledning	Privata spåraniäggningsar	Möjlighet till växning
Name	Another name	Abbr.		Section	Municipality	Traffic control	Private sidings	Shunting
Viiala		Via	154+237	Riihimäki–Tampere	Akaa	K	K	K
Viinijärvi		Vnj	656+569	Silinjärvi–Viinijärvi, Pieksämäki–Joensuu	Liperi	K	K	K
Villiähde		Vlh	140+442	Riihimäki–Kouvola	Nastola	K	K	K
Viippula		Vlp	274+760	Viippula–Mänttä, Orivesi–Seinäjoki	Mänttä–Viippula	K	K	K
Vinnilä		Vin	131+243	Riihimäki–Tampere	Hämeenlinna	K	K	K
Vottti		Vt	479+402	Seinäjoki–Oulu	Kauhava	K	K	K
Vuohijärvi		Vhj	221+308	Kouvola–Pieksämäki	Kouvolta	K	K	K
Vuojoki		Vjo	318+501	Kokemäki–Rauma	Eurajoki	K	K	K
Vuokatti		Vkt	868+838	Vuokatti–Lahmaslampi, Nurmekoski–Kontiomäki	Sotkamo	M	K	K
Vuonislahti		Vsl	705+240	Joensuu–Nurmekoski	Lieksa	K	K	K
Vuonos		Vns	588+808	Sysmäjärvi–Vuonos	Outokumpu	K	K	K
Vuorten-Vuori		Vv	576+687	Äänekoski–Haapajärvi	Haapajärvi	K	K	K
Vuosaari		Vsa	50+184	Kerava–Vuosaari	Helsinki	K	K	K
Yksiphilaja		Yks	555+428	Kokkola–Yksphilaja	Kokkola	K	K	K
Ylistaro		Yst	439+558	Seinäjoki–Vaasa	Seinäjoki	K	K	K
Ylitornio		Ytr	946+139	Tornio–Kolari	Ylitornio	K	K	K
Ylivalli		Ylv	302+016	Tampere–Seinäjoki	Jalasjärvi	K	K	K
Ylivieska		Yy	630+343	Seinäjoki–Oulu, Iisalmi–Ylivieska	Ylivieska	M	K	K
Yläkoski		Ylk	416+984	Suonenjoki–Iisivesi	Suonenjoki	K	K	K
Ylämäly		Yly	639+019	Pieksämäki–Joensuu	Liperi	K	K	K
Ylöjärvi		Ylö	200+753	Tampere–Seinäjoki	Ylöjärvi	K	K	K
Ypikkävaara		Ypy	729+780	Kontiomäki–Vartiust-raja	Kuhmo	K	K	K
Äetsä		Äs	258+280	Lielaiti–Kokemäki	Sastamala	K	K	K
Ähtäri		Äht	346+067	Orivesi–Seinäjoki	Ähtäri	K	K	K
Ämmänsaari		Äm	750+448	Kontiomäki–Ämmänsaari	Suomussalmi	M	K	K

Nimi	Lyhin laituri-pituus	Pisin laituri-pituus	Laituri-korkeus	Laitureiden lukumäärä	Mitoittava raidepituus (tavaraliikenne)	Sähkövirran saanti	Sivulaituri, suurin pititus	Pääty-laituri	Kuormaus-kenttä	Nosturi	Polito-aine	Henkilö-liikennettä	Tavaraliikennettä
Namn	Kortaste perong-längden	Kortaste perong-längden	Perrong-höjden	Antal spår med perrong	Dimensionerande spårängd (godstrafik)	Tillgång på elström	Sido-perrong	Lastning på samma plan	Perrong i ändan av banan	Lyftkran	Bränsle	Person-trafik	Godstrafik
Name	Min. platform length [m]	Max. platform length [m]	Platform height [mm]	Number of tracks with platforms	Design train length (freight traffic) [m]	Power supply [400 V, A]	Side loading platform length [m]	End loading platform	Loading site	Crane	Fuel	Passenger traffic	Freight traffic
Aavasaksa				0	—	—	—	—	—	—	—	—	—
Ahvenus				0	745	—	—	—	—	—	—	—	—
Airaksela				0	842	—	—	—	—	—	—	—	—
Altitaluoto				0	—	—	—	—	—	—	—	—	—
Ajos				0	—	—	—	—	—	—	—	—	—
Alapitkä				0	650	25 A	—	—	—	—	—	—	—
Alavus	80	203	265	2	743	—	—	—	—	—	—	—	—
Alholma				0	—	—	—	—	—	—	—	—	—
Alvajärvi				0	—	—	—	—	—	—	—	—	—
Arola		70	550	0	1088	25 A	—	24	—	—	—	—	—
Dragsvik				0	925	—	—	—	—	—	—	—	—
Dynamittivaihde				0	—	—	—	—	—	—	—	—	—
Elijärvi				0	—	—	—	—	—	—	—	—	—
Eläinpuisto-Zoo		99	265	1	—	—	—	—	—	—	—	—	—
Eno		80	550	1	—	—	—	—	—	—	—	—	—
Ervälä				0	600	25 A	—	—	—	—	—	—	—
Eskola		(120)	(265)	(1)	778	—	—	13	—	—	—	—	—
Espoo		322	550	4	262	—	—	—	—	—	—	—	—
Esso		240	(51)	(265)	0	—	—	—	—	—	—	—	—
Haapavesi		160	265	1	736	25 A	—	12	—	—	—	—	—
Haapavesi		(51)	(265)	(1)	769	—	—	—	—	—	—	—	—
Haapavesi		188	325	0	—	—	—	—	—	—	—	—	—
Haapavesi		220	220	2	644	25 A 63 A	60	—	—	—	—	—	—
Hakosilta				0	240	—	—	—	—	—	—	—	—
Hakosilta				0	—	—	—	—	—	—	—	—	—
Hakosilta				0	—	—	—	—	—	—	—	—	—

Nimi	Lyytin laituri-pituus	Pisin laituri-pituus	Laituri-korkeus	Laitureiden lukumäärä	Mitoittava raidepituus (tavaraliikenne)	Sähkövirran saanti	Sivulaituri, suurin suurin pituus	Pääty-laituri	Kuormaus-kenttä	Nostruri	Poltto-aine	Henkilö-liikennettä	Tavaraliikennettä
Namn	Kortaste perrong-längden	Kortaste perrong-längden	Perrong-höjden	Antal spår med perrong	Dimensionerande spår längd (godstrafik)	Tillgång till elström	Sido-perrong	Perrong i ändan av banan	Lastning på samma plan	Lyftkran	Bränsle	Person-trafik	Godstrafik
Name	Min. platform length [m]	Max. platform length [m]	Platform height [mm]	Number of tracks with platforms	Design train length (freight traffic) [m]	Power supply [400 V, A]	Side loading platform length [m]	End loading platform	Loading site	Crane	Fuel	Passenger traffic	Freight traffic
Hamina				0	834	25 A	18	K	Y	Y	-	-	T
Hammarslahti				0	688	-	-	K	-	-	-	-	T
Hanala				0	-	-	-	-	-	-	-	-	-
Hangonsaari				0	-	-	-	-	-	-	-	-	-
Hamhikoski				0	-	-	-	K	-	-	-	-	T
Hankasalmi	233	289	265	2	766	25A	20	K	-	-	H	-	T
HANKO	108	108	265	2	289	63 A 25 A	152, Y	K	-	Y	Y	H	T
Hanko asema													
Hanko tavarat													
Hanko-Pohjoinen													
Häjavalta	68	550	1	-	-	-	-	-	-	-	H	-	-
Häiju	250	550	2	766	25 A	-	-	K	-	-	H	-	T
Harjula				0	789	-	-	-	-	-	-	-	-
Harjula				0	-	-	-	-	-	-	-	-	-
Haukipudas				0	833	-	-	K	-	-	-	-	-
Haukipuori				0	894	-	-	K	-	-	-	-	-
HAUSJÄRVI													
Hausjärvi tavarat													
Oitti	102	102	550	2	-	-	-	-	-	-	H	-	-
Haviseva				0	-	-	-	-	-	-	-	-	-
Heikkilä				0	-	-	-	-	-	-	-	-	-
Heinola				0	(1)	605	15	-	-	-	K	-	-
Heinoo				0	745	-	-	-	-	-	K	-	-
Heinävaara				0	-	-	-	-	-	-	-	-	-
Heinävesi	100	206	265	2	570	9	-	H	-	-	-	-	T
HELSINKI													

Nimi	Lyyhin laituri-pituus	Pisin laituri-pituus	Laituri-korkeus	Laitureiden lukumäärä	Mitoittava raidepituus (tavaraliikenne)	Sähkövirran saanti	Sivulaituri, suurin suurin pititus	Pääty-laituri	Kuormaus-kenttä	Nosturi	Politto-aine	Henkilö-liikennettä	Tavaraliikennettä
Namn	Kortaste perrong-längden	Längsta perrong-längden	Perrong-höjden	Antal spår med perrong	Dimensionerande spår längd (godstrafik)	Tillgång på elström	Sido-perrong	Lastning på samma plan	Lyftkran	Bränsle	Person-trafik	Godstrafik	
Name	Min. platform length [m]	Max. platform length [m]	Platform height [mm]	Number of tracks with platforms	Design train length (freight traffic) [m]	Power supply [400 V, A]	Side loading platform length [m]	End loading platform	Crane	Fuel	Passenger traffic	Freight traffic	
Helsinki päärautatieseema	265	477	550	19	473	—	—	—	—	—	H	—	
Pasila alapihä	319	432	550, 265	0	—	25 A	—	—	—	—	T	—	
Pasila asema	270	270	550	10	—	—	—	—	—	—	H	—	
Ilmalan asema	—	—	—	2	—	—	—	—	—	—	H	—	
Helsinki Kivihaka	—	—	—	0	—	—	—	—	—	—	—	—	
Pasila tavaratalo	500	500	265	4	710	63 A	230	—	—	—	T	—	
Ilmalan ratapiha	(278)	336	550 (265)	2 (2)	—	141	—	—	—	—	—	—	
Käpylä	266	266	550	2	—	—	—	—	—	—	H	—	
Oulunkylä	110	110	550	2	—	—	—	—	—	—	H	—	
Herrala	270	526	550	2	—	—	—	—	—	—	H	—	
Hiekkaharju	—	—	—	—	—	—	—	—	—	—	—	—	
Hiirala	120	120	550	2	—	—	—	—	—	—	H	—	
Hikiä	—	(?)	(550)	(1)	—	—	—	—	—	—	—	—	
Hillosensalmi	55	65	265	3	—	800	—	—	—	—	—	—	
Hinthaara	—	—	—	—	—	—	—	—	—	—	—	—	
Hirvineva	249	430	550	3	0	799	25 A	13	—	—	T	—	
Humpila	270	270	550	4	756	25 A	29	—	—	—	T	—	
Huopalahti	—	—	—	—	287	—	—	—	—	—	—	—	
Huutokoski	—	—	—	—	661	—	—	—	—	—	T	—	
Hyrynsalmi	(56)	332	550 (265)	(1)	732	25 A	12	—	—	—	T	—	
Hyvinkää	257	450	550	3	814	25 A	20	—	—	—	T	—	
Hämeenlinna	—	—	—	—	827	25 A	34	—	—	—	T	—	
Härmä	92	265	—	0	819	—	19	—	—	—	T	—	
Höijätkää	—	(92)	(265)	(1)	—	—	—	—	—	—	T	—	
li	—	—	—	—	690	—	—	—	—	—	—	—	

Nimi	Pisin laituri-pituus	Laituri-korkeus	Laitureiden lukumäärä	Mitoitettava raidepituus (tavaraliikenne)	Sähkövirran saanti	Sivulaituri, suurin pititus	Pääty-laituri	Kuormaus-kenttä	Nosturi	Polttoaine	Henkilö-liikennettä	Tavaraliikennettä
Namn	Kortaste perrong-längden	Längsta perrong-längden	Antal spår med perpong	Dimensionerande spår längd (godstrafik)	Tillgång till elström	Sido-perrong	Perrong i ändan av banan	Lastning på samma plan	Lyftkran	Bränsle	Person-trafik	Godstrafik
Name	Min. platform length [m]	Max. platform length [m]	Platform height [mm]	Number of tracks with platforms	Design train length (freight traffic) [m]	Power supply [400 V, A]	Side loading platform length [m]	End loading platform	Crane	Fuel	Passenger traffic	Freight traffic
Isälmen teollisuuskylä												
Isälmen teollisuusraiteet												
Isalmi	162	396	265	3	741	—	—	—	—	—	—	T
Iisvesi						1500 V, 63 A 25 A	58	K	Y	Y	H	T
Iittala	170	170	550	2	—	—	—	—	—	—	—	T
Ii lomantsi						—	—	—	—	—	H	T
IMATRA												
<i>Imatra asema</i>	450	265	1	—	—	—	—	—	—	H	—	T
<i>Imatra tavara</i>	(218)	(265)	(1)	889	1500 V, 63 A 25 A	0	—	—	—	Y	—	T
<i>Imatranksoski</i>				1224	—	18	—	—	—	KY	—	T
<i>Pelkola</i>				0	—	—	—	—	—	K	—	T
Imatranksoki-raja				0	—	—	—	—	—	—	—	T
Inha	(99)	(265)	(1)	—	—	—	—	—	—	—	—	T
Inkeroinen	120	172	265	3	796	—	—	—	—	—	—	T
Ikoo	100	170	550	2	213	25 A	—	14	—	—	—	T
Isokangas				0	—	—	—	—	—	—	—	T
Isokyrö	110	150	550, 265	2	510	—	—	—	—	—	—	T
Jalasjärvi	(51)	(550)	(1)	764	—	—	—	—	—	—	—	T
Jepua				0	825	25 A	19	—	—	—	—	T
JOENSUU												
<i>Joensuu asema</i>	239	329	265	3	561	1500 V, 63 A 25 A	46	—	—	K	—	T
<i>Joensuu Peltola</i>				0	666	—	—	—	—	KY	—	T
<i>Joensuu Sulkulahni</i>				0	702	—	—	—	—	—	—	T
Jokela	320	338	550	3	822	—	—	—	—	—	H	T

Nimi	Lyhin laituri-pituus	Pisin laituri-pituus	Laituri-korkeus	Laitureiden lukumäärä	Mitoittava raidepituus (tavaraliikenne)	Sähkövirran saanti	Sivulaituri, suurin pititus	Pääty-laituri	Kuormaus-kenttä	Nosturi	Polttoaine	Henkilö-liikennettä	Tavaraliikennettä
Namn	Kortaste perrong-längden	Längsta perrong-längden	Perrong-höjden	Antal spår med perrong	Dimensionerande spårängd (godstrafik)	Tillgång på elström	Sido-perrong	Lastning på samma plan	Perrong i ändan av banan	Lyftkran	Bränsle	Person-trafik	Godstrafik
Name	Min. platform length [m]	Max. platform length [m]	Platform height [mm]	Number of tracks with platforms	Design train length (freight traffic) [m]	Power supply [400 V, A]	Side loading platform length [m]	End loading platform	Loading site	Crane	Fuel	Passenger traffic	Freight traffic
Joroinen	97	124	265	0	—	—	—	—	—	—	—	—	T
Jorvas	460	460	550	2	814	—	—	—	—	—	H	—	—
Joutseno	460	—	—	0	—	—	—	—	—	—	H	—	T
Joutsijärvi	—	—	—	0	—	—	—	—	—	—	—	—	T
Juankoski	—	—	—	0	579	25 A	13	—	—	—	—	—	T
Jukajärvi	—	—	—	0	—	—	—	—	—	—	—	—	—
Jutila	—	—	—	0	—	—	—	—	—	—	H	—	—
Juupajoki	80	550	1	—	—	—	—	—	—	—	—	—	—
Juurikkorpi	—	—	—	0	789	—	—	—	—	—	—	—	—
Jyränkö	—	—	—	0	—	—	—	—	—	—	—	—	T
Jyväskylä	57	449	550	6	—	—	—	—	—	—	Y	—	T
Jämsä	194	313	265	3	770	25 A	—	—	—	—	Y	—	T
Jämsänkoski	—	—	—	0	873	25 A	—	—	—	—	H	—	T
Järvelä	122	122	550	3	633	—	—	—	—	—	—	—	T
JÄRVENPÄÄ													
Järvenpää asema	345	440	550	3	—	—	—	—	—	29	K	—	T
Sauvakallio	180	275	550, 265	4	709	—	—	—	—	—	H	—	T
Purola	270	270	550	2	—	—	—	—	—	—	H	—	—
Kaipiainen	—	—	—	0	—	—	—	—	—	—	Y	—	—
Kaipola	—	—	—	0	—	—	—	—	—	—	K	—	—
Kairokoski	—	—	—	0	—	—	—	—	—	—	K	—	—
Kaitjärvi	352	411	265	2	845	—	—	—	—	—	H	—	T
Kajaani	—	—	—	0	—	—	—	—	—	—	K	—	—
Kaleton	—	—	—	0	—	—	—	—	—	—	H	—	—
Kalkku	—	—	—	0	—	—	—	—	—	—	Y	—	—

Nimi	Lyytin laituri-pituus	Pisin laituri-pituus	Laituri-korkeus	Laitureiden lukumäärä (tavaraliikenne)	Mitoittava raidepituus (tavaraliikenne)	Sähkövirran saanti	Sivulaituri, suurin puitus	Pääty-laituri	Kuormaus-kenttä	Nosturi	Polttoaine	Henkilö-liikennettä	Tavaraliikennettä
Namn	Kortaste perrong-längden	Kortaste perrong-längden	Perrong-höjden	Antal spår med perrong	Dimensionerande spårlängd (godstrafik)	Tillgång till elström	Sido-perrong	Perrong i ändan av banan	Lastning på samma plan	Bränsle	Person-trafik	Godstrafik	
Name	Min. platform length [m]	Max. platform length [m]	Platform height [mm]	Number of tracks with platforms	Design train length (freight traffic) [m]	Power supply [400 V, A]	Side loading platform length [m]	End loading platform	Loading site	Crane	Fuel	Passenger traffic	Freight traffic
Kaliovastato				0	—	—	—	—	—	—	—	—	—
Kalissahti				0	—	—	—	—	—	—	—	—	—
Kalvitsa				0	906	—	—	—	—	—	—	—	—
Kangas				0	782	—	—	—	—	—	—	—	—
Kannelmäki	226	226	550	2	—	25 A	—	—	—	—	—	—	—
Kannonkoski				0	—	—	—	—	—	—	—	—	—
Kannus	339	420	265	2	818	25 A	19	—	—	—	—	—	—
Karhejärvi				0	778	25A	7	—	—	—	—	—	—
Karthukangas				0	840	—	—	—	—	—	—	—	—
Kariaa	248	352	550	4	766	63 A/25A	—	—	—	—	—	—	—
Karkku		143	265 (265)	1 (1)	852	—	—	—	—	—	—	—	—
Karviainen				0	747	—	—	—	—	—	—	—	—
Kaskinen				0	871	—	—	—	—	—	—	—	—
Kattilaharju				0	—	—	—	—	—	—	—	—	—
Kauhajoki				0	—	—	—	—	—	—	—	—	—
Kauhava				0	838	—	—	—	—	—	—	—	—
KAUKLAHTI													
Kauklahdi asema	270	270	550	3	447	—	—	—	—	—	—	—	—
Mankki	126	136	265	2	—	—	—	—	—	—	—	—	—
Kaulinranta				0	—	—	—	—	—	—	—	—	—
Kaunainen	194	204	265	3	279	—	—	—	—	—	—	—	—
Kauppiilanmäki				0	634	—	—	—	—	—	—	—	—
Kausala	120	(41)	550 (265)	2 (1)	—	—	—	—	—	—	—	—	—
Kauttua				0	14	—	—	—	—	—	—	—	—
Keitelepohja					9	—	—	—	—	—	—	—	—

Nimi	Lyyhin laituri-pituus	Pisin laituri-pituus	Laituri-korkeus	Laitureiden lukumäärä	Mitoittava raidepituus (tavaraliikenne)	Sähkövirran saanti	Sivulaituri, suurin suurin pititus	Pääty-laituri	Kuormaus-kenttä	Nosturi	Poltoaine	Henkilö-liikennettä	Tavaraliikennettä
Namn	Kortaste perrong-längden	Längsta perrong-längden	Perrong-höjden	Antal spår med perrong	Dimensionerande spår längd (godstrafik)	Tillgång på elström	Sido-perrong	Perrong i ändan av banan	Lastning på samma plan	Lyftkran	Bränsle	Person-trafik	Godstrafik
Name	Min. platform length [m]	Max. platform length [m]	Platform height [mm]	Number of tracks with platforms	Design train length (freight traffic) [m]	Power supply [400 V, A]	Side loading platform length [m]	End loading platform	Loading site	Crane	Fuel	Passenger traffic	Freight traffic
Kekomäki				0	—	—	—	—	—	—	—	—	—
Keijo				0	—	—	—	—	—	—	—	—	—
Kelkkämäki				0	—	—	—	—	—	—	—	—	—
Kelloselkä				0	471	—	—	—	—	—	—	—	T
Kemi	450	450	550	3	1015	25 A 63 A	148	—	—	Y	H	T	T
Kemijärvi		352	265	1	547	1500 V, 63 A	6	K	KY	—	H	T	T
Kemira		(119)	(265)	(1)	501	—	—	—	—	—	—	—	T
Kempeli		216	224	265	2	762	25 A	9	—	K	—	—	—
Kera					—	—	—	—	—	H	—	—	—
KERAVA													
Kerava asema	270	392	550	4	1335	25 A	—	—	—	Y	H	—	—
Kytömaa				0	790	—	—	—	—	—	—	—	—
Kerimäki		108	265	1	399	—	—	—	—	K	—	—	—
Kesälahti		322	265	1	671	—	—	—	—	—	H	—	T
Keuruu		111	550	1	678	—	—	—	—	K	—	H	T
Kihniö				0	646	—	—	—	—	K	—	H	T
Kiala				0	—	—	—	—	—	—	—	—	—
Kilo		270	550	2	—	—	—	—	—	—	—	—	—
Kilpua				0	750	25 A	—	—	—	—	—	—	—
Kinahmi				0	—	—	—	—	—	—	—	—	—
Kirni				0	776	—	—	—	—	K	—	—	—
Kirkkonummi	316	322	550	3	608	—	—	—	—	—	—	H	T
Kirkniemi				0	590	—	—	—	—	—	—	H	T
Kitee		355	265	1	668	25 A	18	—	—	—	—	—	—
Kiukainen				0	764	—	14	—	—	—	—	—	—

Nimi	Lyytin laituri-pituus	Pisin laituri-pituus	Laituri-korkeus	Laitureiden lukumäärä	Mittoittava raidepituus (tavaraliikenne)	Sähkövirran saanti	Sivulaituri, surun pititus	Pääty-laituri	Kuormaus-kenttä	Nosturi	Polttoaine	Henkilö-liikennettä	Tavaraliikennettä
Namn	Kortaste perrong-längden	Längsta perrong-längden	Perrong-höjden	Antal spår med perrong	Dimensionerande spårslängd (godstrafik)	Tillgång till elström	Stdoperrong	Perrong i ändan av banan	Lastning på samma plan	Lyftkran	Bränsle	Person-trafik	Godstrafik
Name	Min. platform length [m]	Max. platform length [m]	Platform height [mm]	Number of tracks with platforms	Design train length (freight traffic) [m]	Power supply [400 V, A]	Side loading platform length [m]	End loading platform	Loading site	Crane	Fuel	Passenger traffic	Freight traffic
Kiuruvesi	126	265	1	675	25 A	80	—	—	KY	—	H	T	—
Kivesjärvi	(54)	(265)	(1)	1114	—	—	—	—	—	—	—	—	—
Kontavaara	55	265	1	—	—	—	—	—	—	—	H	T	—
Koivu	(40)	(265)	(1)	617	—	—	32	—	—	—	—	—	—
Koivuhovi	278	278	550	2	—	—	—	—	—	—	H	T	—
Koivukylä	270	270	550	2	—	—	—	—	—	—	H	T	—
Kokemäki	249	249	550	3	904	25 A	29	—	K	—	—	—	—
Kokkola	150	482	265	4	829	1500 V, 63 A 25 A	8, Y	Y	Y	—	H	T	—
Kolari	224	675	550/265 (265)	2 (1)	792	63 A	22	K	KY	—	H	T	—
Kolho	(120)	(265)	(1)	0	—	—	—	—	—	—	—	—	—
Kolppi					768	—	—	—	—	—	—	—	—
Kommila					724	25 A	—	—	—	—	—	—	—
Komu					0	—	—	—	—	—	—	—	—
Kontiolahti	(96)	(265)	(1)	—	580	25 A	—	—	K	—	—	—	—
Kontiomäki	350	350	265	3	903	25 A 63 A	31	—	K	—	—	—	—
Koppnäs					0	—	7	—	K	—	—	—	—
Koria	120	120	550	2	0	—	—	—	K	—	—	—	—
Korkeakoski	(72)	(265)	(1)	—	747	—	—	—	K	—	—	—	—
Korsö	270	270	550	2	—	—	—	—	—	—	—	—	—
Korvensuo					0	—	—	—	—	—	—	—	—
Koskenkorva					0	—	—	—	—	—	—	—	—
KOTKA						25 A 63 A	85	—	—	—	—	—	—
<i>Kotka Hovinsaari</i>						0	—	—	—	—	—	—	—
<i>Kotka tavarat</i>						0	—	—	—	—	—	—	—
<i>Paimenportti</i>	53	265	—	—	—	—	—	—	—	—	—	—	H

Nimi	Lyyhin laituri-pituus	Pisin laituri-pituus	Laituri-korkeus	Laitureiden lukumäärä	Mitoittava raidepituus (tavaraliikenne)	Sähkövirran saanti	Sivulaituri, suurin pititus	Pääty-laituri	Kuormaus-kenttä	Nosturi	Polttoaine	Henkilö-liikennettä	Tavaraliikennettä
Namn	Kortaste perrong-längden	Kortaste perrong-längden	Perrong-höjden	Antal spår med perrong	Dimensionerande spårflängd (godstrafik)	Tillgång på elström	Sido-perrong	Lastning på samma plan	Lastning i ändan av banan	Lyftkran	Bränsle	Person-trafik	Godstrafik
Name	Min. platform length [m]	Max. platform length [m]	Platform height [mm]	Number of tracks with platforms	Design train length (freight traffic) [m]	Power supply [400 V, A]	Side loading platform length [m]	End loading platform	Loading site	Crane	Fuel	Passenger traffic	Freight traffic
Kotka asema	193	265	1	270	63 A	—	—	—	—	H	—	—	—
Kotkan satama	110	265	1	539	25 A 63 A	280	—	—	—	H	—	—	—
Kotka Mussalo			0	1005	—	Y	—	—	—	Y	—	—	—
KOUVOLA													
Kouvola asema	230	428	550	7	620	1500 V, 63 A 25 A	0	—	—	K	—	—	—
Kouvola lajittelu				0	865	25 A	175	—	—	—	—	—	—
Kouvola Olkoraide				0	—	—	—	—	—	—	—	—	—
Kouvola tavara				0	1008	—	—	—	—	—	—	—	—
Kullasaara				0	1418	—	—	—	—	—	—	—	—
Kovjoki				0	847	—	—	—	—	—	—	—	—
Kruunupyyn				0	774	—	—	—	—	—	—	—	—
Kuivasaari				0	781	—	—	—	—	—	—	—	—
KUOPIO													
Kuopio asema	90	387	265	4	370	63 A 25 A	130	—	—	K	Y	—	—
Kuopio tavara				0	766	1500 V, 63 A	100	—	—	—	Y	—	—
Kurkimäki				0	778	—	—	—	—	—	—	—	—
Kursu				0	—	—	—	—	—	—	—	—	—
Kuurila				0	—	—	—	—	—	—	—	—	—
Kuusankoski				0	803	—	—	—	—	—	—	—	—
Kylänlahti	57	265	1	—	—	—	—	—	—	—	—	—	—
Kymi	32	66	265	2	744	—	—	—	—	—	—	—	—
Kymminlinna		55	265	1	—	—	—	—	—	—	—	—	—
Kyrö				0	742	—	—	—	—	—	—	—	—
Kyrölä	270	270	550	2	—	—	—	—	—	—	—	—	—
Kälviä		(130)	(265)	(1)	1040	25 A	18						

Nimi	Lyytin-laituri-pituus	Pisin laituri-pituus	Laituri-korkkeus	Laitureiden lukumäärä	Mitoittava raitdepitus (tavaraliikenne)	Sähkövirran saanti	Sivulaituri, suurin sijaintipituus	Pääylaituri	Kuormauskenttä	Nostruri	Poittoaine	Hankilö-liikennettä	Tavaraliikennettä
Namn	Kortaste perrong-längden	Kortaste perrong-längden	Perrong-höjden	Antal spår med perrong	Dimensionerande spårängd (godstrafik)	Tillgång till elström	Sido-perrong	Perrong i ändan av banan	Lastning på samma plan	Lyftkran	Bränsle	Person-trafik	Godstrafik
Name	Min. platform length [m]	Max. platform length [m]	Platform height [mm]	Number of tracks with platforms	Design train length (freight traffic) [m]	Power supply [400 V, A]	Side loading platform length [m]	End loading platform	Loading site	Crane	Fuel	Passenger traffic	Freight traffic
Köykkäri													
Lahdenperä													
Lannashampi													
Lahti	194	450	550, 265	0	—	25 A	—	—	—	—	—	—	—
Laihia		201	265	5	710	25 A 63 A	7	K	Y	Y	H	T	T
Lakiala				1	469	25 A	—	—	—	—	—	—	—
Lamminkoski				0	727	—	12	K	—	—	—	—	—
Lammintieniemi				0	742	—	—	K	—	—	—	—	—
Lapinjärvi				0	—	—	—	—	—	—	—	—	—
Lapinlahti	301	355	265	2	739	25 A	—	—	—	—	—	—	—
Lapinniva				0	—	—	—	—	—	—	—	—	—
Lappeenranta	430	450	550, 265	3	743	25 A	—	K	Y	Y	H	T	T
Lappila	60	60	550	2	—	—	—	—	—	—	—	—	—
Lappohja		70	550	1	750	—	—	—	—	—	—	—	—
Lapua		438	265 (265)	1 (1)	766	—	—	K	—	—	—	—	—
Larvakyö				0	911	—	—	—	—	—	—	—	—
Laukaa				0	—	—	—	—	—	—	—	—	—
Laurila				0	619	—	—	—	—	—	—	—	—
Lauritsala				0	659	—	—	—	—	—	—	—	—
Leikkola				0	804	—	—	—	—	—	—	—	—
Lempäälä	170	170	550	2	780	—	—	—	—	—	—	—	—
Leppäkoski				0	—	—	—	—	—	—	—	—	—
Leppävaara	266	292	550	4	—	—	—	—	—	—	—	—	—
Leeteensuo				0	—	—	—	—	—	—	—	—	—

APPENDIX 2 Rail Traffic Operating Point Register /
Traffic Operating Point Information

Nimi	Lyytin laituri-pituus	Pisin laituri-pituus	Laituri-korkeus	Laitureiden lukumäärä	Mitoittava raidepituus (tavaraliikenne)	Sähkövirran saanti	Sivulaiturin suurin pititus	Pääty-laituri	Kuormaus-kenttä	Nosturi	Polttoaine	Henkilö-liikennettä	Tavaraliikennettä
Namn	Kortaste perrong-längden	Längsta perrong-längden	Perrong-höjden	Antal spår med perrong	Dimensionerande spärängd (godstrafik)	Tillgång på elström	Sido-perrong	Lastning på sammansatta plan	Lyftkran	Bränsle	Persontrafik	Godstrafik	
Name	Min. platform length [m]	Max. platform length [m]	Platform height [mm]	Number of tracks with platforms	Design train length (freight traffic) [m]	Power supply [400 V, A]	Side loading platform length [m]	End loading platform	Crane	Fuel	Passenger traffic	Freight traffic	
Liekasaari	151	265	1	680	25 A	24	K	-	Y	H	T	T	
Liekasan teollisuuskylä			0	-		20	-	-	-	-	-	T	
Lielahdi			0	826		8	-	-	-	-	-	T	
Lievestuore	259	265	1	827	25 A	23	K	-	-	H	T	T	
Liminka	(147)	(265)	(1)	753	25 A	23	K	-	-	-	-	-	
Lohiluoma			0	-		-	-	-	-	-	-	T	
Lohja			0	-	25 A	25	K	-	-	-	-	T	
Lohjanjärvi	252	450	2	785	-	-	K	-	-	H	T	T	
Loimaa	238	238	2	-	-	-	-	-	-	-	-	T	
Louhela		550	2	-	-	-	-	-	-	-	-	T	
Loukolampi			0	886	-	-	-	-	-	-	-	T	
Loviisan satama			0	325	25 A	28	Y	KY	KY	-	-	T	
Luukonlahti	216	216	2	-	-	-	-	-	-	-	-	T	
Luoma	216	124	265	1	-	-	-	-	-	-	-	T	
Lusto			-	-	-	-	-	-	-	-	-	T	
Luumäki			0	1275	-	-	-	-	-	-	-	T	
Lähde mäki			0	998	-	-	-	-	-	-	-	T	
Länkipohja			0	802	-	-	-	-	-	-	-	T	
Maanselkä			0	631	-	-	-	-	-	-	-	T	
Maria			0	743	-	-	-	-	-	-	-	T	
Madesjärvi			0	777	25 A	8	-	-	-	-	-	T	
Majajärvi			0	717	-	-	-	-	-	-	-	T	
Malmi			0	-	-	-	-	-	-	-	-	T	
Märiminkartano	(300)	(265)	550	2	-	-	-	-	-	-	-	T	
Markkala	284	284	0	751	-	-	-	-	-	-	-	T	

Nimi	Lyhin laituri-pituus	Pisin laituri-pituus	Laituri-korkeus	Laitureiden lukumäärä (tavaraliikenne)	Mitoittava raidepituus (tavaraliikenne)	Sähkövirran saanti	Sivulaituri, suurin pititus	Pääty-laituri	Kuormaus-kenttä	Nostruri	Polttoaine	Henkilö-liikennettä	Tavaraliikennettä
Namn	Kortaste perrong-längden	Kortaste perrong-längden	Perrong-höjden	Antal spår med perrong	Dimensionerande spårlängd (godstrafik)	Tillgång till elström	Sido-perrong	Perrong i ändan av banan	Lastning på samma plan	Lyftkran	Bränsle	Person-trafik	Godstrafik
Name	Min. platform length [m]	Max. platform length [m]	Platform height [mm]	Number of tracks with platforms	Design train length (freight traffic) [m]	Power supply [400 V, A]	Side loading platform length [m]	End loading platform	Loading site	Crane	Fuel	Passenger traffic	Freight traffic
Martinlaakso	236	236	550	2	—	—	—	—	—	—	—	—	—
Masala	267	267	550	2	—	—	—	—	—	—	H	H	—
Matkaneva				0	845	—	—	—	—	—	—	—	—
Mattiila				0	—	—	—	—	—	—	—	—	—
Meltoala				0	—	—	—	—	—	—	—	—	—
Metsäkansa				0	—	—	—	—	—	—	—	—	—
Mikkeli	352	452	550	3	757	25 A	5	—	—	—	KY	—	—
Misi		352	265	1	760	63 A	52	—	—	—	K	—	—
Mommila	120	120	550	2	—	—	—	—	—	—	—	—	—
Muhos	151	212	265	2	670	25 A	24	—	—	—	K	—	—
Mukkula				0	—	—	—	—	—	—	—	—	—
Murtomäki				0	764	—	—	—	—	—	K	—	—
Mustio				0	—	—	—	—	—	—	K	—	—
Mustolan satama				0	—	—	—	—	—	—	—	—	—
Munkko				0	—	—	—	—	—	—	—	—	—
Murame				0	787	—	—	—	—	—	—	—	—
Muuroja				0	838	25 A	—	—	—	—	—	—	—
Myllykangas				0	851	—	—	—	—	—	—	—	—
Myllykoski	110	110	265	2	—	—	—	—	—	—	—	—	—
Myllymäki		216	265	1	—	—	—	—	—	—	—	—	—
Myllyjoja				0	512	—	—	—	—	—	—	—	—
Mynttilä				0	—	—	—	—	—	—	—	—	—
Myrämäki				(1)	496	—	—	—	—	—	—	—	—
Myrskylä				0	—	—	—	—	—	—	—	—	—
Myyrmäki	232	232	550	2	—	—	—	—	—	—	H	—	—

Nimi	Lyhin laituri-pituus	Pisin laituri-pituus	Laituri-korkeus	Laitureiden lukumäärä	Mitoittava raidepituus (tavaraliikenne)	Sähkövirran saanti	Sivulaituri, sururin pititus	Pääty-laituri	Kuormaus-kenttä	Nosturi	Polttoaine	Henkilö-liikennettä	Tavaraliikennettä
Namn	Kortaste perrong-längden	Längsta perrong-längden	Perrong-höjden	Antal spår med perrong	Dimensionerande spår längd (godstrafik)	Tillgång på elstörm	Sido-perrong	Lastning på samma plan	Lastning i ändan av banan	Lyftkran	Bränsle	Person-trafik	Godstrafik
Name	Min. platform length [m]	Max. platform length [m]	Platform height [mm]	Number of tracks with platforms	Design train length (freight traffic) [m]	Power supply [400 V, A]	Side loading platform length [m]	End loading platform	Loading site	Crane	Fuel	Passenger traffic	Freight traffic
Mäkkylä	270	288	550	2	—	—	—	—	—	—	H	—	—
Mäntsälä	220	220	550	2	999	—	—	—	—	—	H	—	—
Mänttä				0	—	—	—	—	—	—	—	—	T
Mäntyharju	457	457	550	2	992	—	159	—	—	K	—	—	T
Mäntyluoto				0	798	—	Y	—	—	—	—	—	T
Naantali				0	—	—	20	—	—	—	—	—	T
Naarajarvi				0	770	—	—	—	—	K	—	—	—
Nakkila				0	733	—	—	—	—	—	—	—	—
Nastola	120	120	550	2	—	—	—	—	—	—	H	—	—
Niemenpää				0	—	—	—	—	—	—	—	—	—
Niinimaa				0	—	—	—	—	—	—	—	—	—
Niinimäki				0	1250	—	—	—	—	—	—	—	—
Niinisalo				0	668	63 A	22	K	—	—	—	—	—
Niirala				(42)	(265)	(1)	929	25 A	—	—	—	—	—
Niirala-raja				0	—	—	—	—	—	—	—	—	—
Niittylahti				0	697	—	—	—	—	—	—	—	—
Nikkilä				1	—	—	—	—	—	—	—	—	—
Nivala				1	825	—	—	—	—	—	—	—	—
Nokia				1	865	—	—	—	—	—	—	—	—
Nummela				0	—	—	—	—	—	—	—	—	—
Nuppulinnan	210	240	550	2	—	—	—	—	—	—	—	—	—
Nurmnes	73	205	265	2	—	—	—	—	—	—	—	—	—
Närpiö				0	851	—	25 A	50	—	—	—	—	—
Ohemäki				0	—	—	—	—	—	—	—	—	—
Olli				0	—	—	—	—	—	—	—	—	—

Nimi	Lyhin laituri-pituus	Pisin laituri-pituus	Laituri-korkeus	Laitureiden lukumäärä	Mittoittava raidepituus (tavaraliikenne)	Sähkövirran saanti	Sivulaituri, suurin pititus	Pääty-laituri	Kuormaus-kenttä	Nostruri	Politoaine	Henkilö-liikennettä	Tavaraliikennettä
Namn	Kortaste perrong-längden	Längsta perrong-längden	Perrong-höjden	Antal spår med perrong	Dimensionerande spår längd (godstrafik)	Tillgång till elström	Sido-perrong	Perrong i ändan av banan	Lastning på samma plan	Lyftkran	Bränsle	Person-trafik	Godstrafik
Name	Min. platform length [m]	Max. platform length [m]	Platform height [mm]	Number of tracks with platforms	Design train length (freight traffic) [m]	Power supply [400 V, A]	Side loading platform length [m]	End loading platform	Crane	Fuel	Passenger traffic	Freight traffic	
Onttoala				0	—	—	—	—	—	—	—	—	T
Orimattila	297	380	550	0	—	—	—	12	—	—	—	—	T
Orivesi		80	550	3	763	25 A	—	—	—	—	H	—	T
Orivesi keskusta				1	—	—	—	—	—	—	H	—	T
Otanmäki				0	—	—	—	—	—	—	—	—	T
Otava		(152)	(265)	(1)	735	—	—	—	—	—	—	—	T
Otavan satama				0	—	—	—	—	—	—	—	—	T
Oulainen	427	428	265	3	940	25 A	80	—	—	—	H	—	T
OULU													
Oulu Nokela				0	990	25 A 63 A	—	—	—	—	Y	—	T
Oulu Oritkari				0	—	63 A	200, Y	—	—	—	Y	—	T
Oulu tavaralaiva				0	761	25 A	6	—	—	—	—	—	T
Oulu asema	366	458	550, 265	3	475	1500 V, 63 A 25 A	—	K	—	H	—	—	T
Oulu Tuira				0	759	—	66	—	—	—	—	—	T
Paimio				0	751	—	—	—	—	—	—	—	T
Palopuro				0	—	—	—	—	—	—	—	—	T
Palta Oy				0	—	—	—	—	—	—	—	—	T
Paltamo	230	265	1	664	25 A	—	—	—	—	—	K	—	T
Pankakoski	210	379	265	0	390	—	—	—	—	—	KY	—	T
Parikkala				3	793	25 A	30	—	—	—	H	—	T
Parkano	600	600	550	3	943	25 A	10	—	—	—	Y	—	T
Parola	192	196	550	2	920	—	31	—	—	—	H	—	T
Pello		454	265	1	585	25 A	35	—	—	—	H	—	T
Peltosalmi				0	—	25 A	—	—	—	—	K	—	T
Perässäinäjoki				0	765	—	16	—	—	—	K	—	T

Nimi	Lyhin laituri-pituus	Pisin laituri-pituus	Laituri-korkeus	Laitureiden lukumäärä	Mitoittava raideliipitus (tavaraliikenne)	Sähkövirran saanti	Stuvlaituri, suurin pititus	Pääty-laituri	Kuormaus-kenttä	Nosturi	Polttoto-aine	Henkilö-liikennettä	Tavaraliikennettä
Namn	Kortaste perrong-längden	Kortaste perrong-längden	Perrong-höjden	Antal spår med perrong	Dimensionerande spårängd (godstrafik)	Tillgång på elström	Sido-perrong	Lastning på samma plan	Lyftkran	Bränsle	Person-trafik	Godstrafik	
Name	Min. platform length [m]	Max. platform length [m]	Platform height [mm]	Number of tracks with platforms	Design train length (freight traffic) [m]	Power supply [400 V, A]	Side loading platform length [m]	End loading platform	Crane	Fuel	Passenger traffic	Freight traffic	
Pesilökylä		(74)	(265)	(1)	748	—	—	—	—	—	—	—	—
Pettäjävesi	142	265	1	762	—	—	—	—	—	H	—	T	—
PIEKSÄMÄKI	332	611	265	4	499	1500 V, 63 A 25 A	5	Y	—	H	—	—	—
Pietsämäki asema	332	611	265	0	947	25 A 63 A	—	YY	—	Y	—	—	—
Pietsämäki Temu				0	954	—	—	—	—	—	—	—	—
Pietsämäki laittelelu				0	752	—	—	—	—	—	—	—	—
Piertsämäki tavarat				0	752	—	—	—	—	—	—	—	—
Pietarsaari	99	120	550, 265	2	494	25 A	—	—	—	H	—	T	—
Pihlajavesi				0	541	—	6	—	—	—	—	—	—
Pihlajipudas				0	—	—	—	—	—	—	—	—	—
Piikkiö				0	302	—	—	—	—	—	—	—	—
Pirkkala				0	759	—	—	—	—	—	—	—	—
Pitäjänmäki	270	306	550	2	—	—	—	—	—	—	—	—	—
Pohjankuru				0	300	—	—	—	—	—	—	—	—
Pohjois-Haaga	240	240	550	2	—	—	—	—	—	—	—	—	—
Poikkeus				0	715	—	—	—	—	—	—	—	—
Poiksila				0	—	—	—	—	—	—	—	—	—
Pori	251	251	550	2	746	1500 V, 63 A 25 A	11	YY	—	K	—	T	—
Porokylä		218	265	0	—	—	—	—	—	—	—	—	—
Porvoo				1	—	—	—	—	—	—	—	—	—
Puhos	274	274	550	2	650	25 A	13	—	—	H	—	T	—
Puistola	273	279	550	2	—	—	—	—	—	H	—	T	—
Pukinmäki				0	1839	—	—	—	—	H	—	—	—
Pulsa													—

Nimi	Lyytin laituri-pituus	Pisim laituri-pituus	Laituri-korkeus	Laitureiden lukumäärä	Mitoittava raidepituus (tavaraliikenne)	Sähköviran saanti	Sivulaituri, suurin pititus	Pääty-laituri	Kuormaus-kenttä	Nosturi	Polttoaine	Henkilö-liikennettä	Tavaraliikennettä
Namn	Kortaste perrong-längden	Kortaste perrong-längden	Perrong-höjden	Antal spår med perrong	Dimensionerande spårlängd (godstrafik)	Tillgång till elström	Sido-perrong	Perrong i ändan av banan	Lastning på samma plan	Lyftkran	Bränsle	Person-trafik	Godstrafik
Name	Min. platform length [m]	Max. platform length [m]	Platform height [mm]	Number of tracks with platforms	Design train length (freight traffic) [m]	Power supply [400 V, A]	Side loading platform length [m]	End loading platform	Loading site	Crane	Fuel	Passenger traffic	Freight traffic
Punkaharju	201	265	1	435	25 A	—	—	—	—	—	H	—	T
Pyhäkumpu				0	342	—	9	—	—	—	—	—	T
Pyhäkumpu erkanemisvaihde				0	—	—	—	—	—	—	—	—	—
Pyhäsalmi	105	265	1	668	25 A	—	—	—	—	—	H	—	T
Päinäinen	338	440	265	2	765	25 A	20	—	—	—	H	—	T
Pääskylähti				0	653	—	36	—	—	—	—	—	T
Raahe				0	1123	63 A 25 A	53	—	—	—	—	—	T
Raippa				0	1855	—	144	—	—	—	—	—	T
Raisio	(111)	(168)	(265)	(3)	—	—	—	—	—	—	—	—	T
Rajamäki				0	—	—	—	—	—	—	—	—	T
Rajaperkiö				0	746	—	—	—	—	—	—	—	T
Rantasalmi				0	787	—	—	—	—	—	—	—	T
Rasinsuo				0	742	—	—	—	—	—	—	—	T
Raitikylä				0	750	—	—	—	—	—	—	—	T
Rauha				0	793	—	—	—	—	—	—	—	T
Rauhalanti				0	—	—	—	—	—	—	—	—	T
Rauma				0	940	25 A	15	—	—	—	—	—	T
Raunio				0	759	—	—	—	—	—	—	—	T
Rautaruukki				0	—	—	—	—	—	—	—	—	T
Rautjärvi				0	787	—	—	—	—	—	—	—	T
Rautpohja	270	270	550	0	—	—	—	—	—	—	—	—	H
Rekola				2	—	—	—	—	—	—	—	—	H
Rettetti				1	265	—	—	—	—	—	—	—	H
RIIHIMÄKI													

APPENDIX 2 Rail Traffic Operating Point Register /
Traffic Operating Point Information

Nimi	Lyhin laituri-pituus	Pisin laituri-pituus	Laituri-korkeus	Laitureiden lukumäärä	Mitoittava raidepituus (tavaraliikenne)	Sähkövirran saanti	Stuvlaituri, sturin pitius	Pääty-laituri	Kuormaus-kenttä	Nosturi	Polttoaine	Henkilö-liikennettä	Tavaraliikennettä
Namn	Kortaste perrong-längden	Längsta perrong-längden	Perrong-höjden	Antal spår med perong	Dimensionerande spårängd (godstrafik)	Tillgång på elström	Sido-perpong	Lastning på samma plan	Lyftkran	Bränsle	Personstrafik	Godstrafik	
Name	Min. platform length [m]	Max. platform length [m]	Platform height [mm]	Number of tracks with platforms	Design train length (freight traffic) [m]	Power supply [400 V, A]	Side loading platform length [m]	End loading platform	Crane	Fuel	Passenger traffic	Freight traffic	
Riihimäki Arolanpi				0	—	—	—	—	—	—	—	—	—
Riihimäki lajittelu				0	978	—	—	—	—	—	—	—	T
Riihimäki tavarala				0	997	—	—	—	—	—	—	—	T
Riihimäki asema	392	392	265	2	643	1500 V, 63 A 25 A	26, Y	—	KY	—	—	—	—
Riijärvi				0	—	—	—	—	—	—	—	—	—
Rilppa				0	842	—	—	—	—	—	—	—	—
Ristiina				0	768	—	—	—	K	—	—	—	—
Ristijärvi				0	—	—	—	—	—	—	—	—	—
Rovaniemi	312	485	550, 265	4	736	1500 V, 63 A 25 A	188	KY	—	—	—	—	—
Ruha				0	850	—	—	—	—	—	—	—	—
Runni	36	550	1	—	—	—	—	—	—	H	—	—	—
Ruotsniemi		(105)	(265)	(1)	—	—	—	—	K	—	—	—	—
Ruukki	430	448	265	2	760	25 A	8	—	KY	—	—	—	—
Ryttylä	171	173	550	2	—	—	7	—	K	—	—	—	—
Röyttä				0	—	25 A	—	—	K	—	—	—	—
Saakoski				0	819	25 A	5	—	—	—	—	—	—
Saari		(201)	(265)	(1)	693	—	—	—	K	—	—	—	—
Saarijärvi		(69)	(265)	(1)	—	25 A	40	—	K	—	—	—	—
Salla				0	501	—	—	—	K	—	—	—	—
Salmisen				0	764	—	—	—	K	—	—	—	—
Salmivaara				0	764	—	—	—	K	—	—	—	—
Salo	306	310	550	3	381	—	—	—	K	—	—	—	—
Sammalisto				0	—	—	—	—	H	—	—	—	—
Santala		70	550	1	—	—	—	—	H	—	—	—	—

Nimi	Lyytin laituri-pituus	Pisim laituri-pituus	Laituri-korkeus	Laitureiden lukumäärä	Mitoittava raiidepituus (tavaraliikenne)	Sähköviran saanti	Sivulaituri, suurin pituus	Pääty-laituri	Kuormaus-kenttä	Nostruri	Poistto-aine	Henkilö-liikennettä	Tavaraliikennettä
Namn	Kortaste perrong-längden	Kortaste perrong-längden	Perrong-höjden	Antal spår med perrong	Dimensionerande spårlängd (godstrafik)	Tillgång till elström	Sido-perrong	Perrong i ändan av banan	Lastning på samma plan	Lyftkran	Bränsle	Person-trafik	Godstrafik
Name	Min. platform length [m]	Max. platform length [m]	Platform height [mm]	Number of tracks with platforms [m]	Design train length (freight traffic) [m]	Power supply [400 V, A]	Side loading platform length [m]	End loading platform	Loading site	Crane	Fuel	Passenger traffic	Freight traffic
Sauvanmäki	270	270	550	0	—	—	—	—	—	—	—	—	—
Savio	165	165	265	2	557	63 A 25 A	124	—	—	—	H	H	—
Savonlinna				0	—	—	—	—	—	—	Y	H	—
Savonlinna-Kauppatori											—	—	—
SEINÄJOKI													
Seinäjoki tavarat	146	463	550, 265	0	861	25 A	40	—	—	—	—	—	—
Seinäjoki asema			(78)	5	656	1500 V, 63 A 25 A	65	—	—	—	Y	H	—
Selänpää			(265)	0	772	—	—	—	—	—	—	—	—
Sieppijärvi			(1)	0	—	—	—	—	—	—	—	—	—
Sievi			(265)	0	743	—	—	—	—	—	—	—	—
Silkkämäki			(88)	0	—	—	—	—	—	—	—	—	—
Sililjärv	156	360	265	2	703	25 A	—	—	—	—	—	—	—
Simo			(265)	(1)	990	—	46	—	—	—	—	—	—
Simpele	272	305	265	3	845	25 A	17	—	—	—	—	—	—
Sipilä			(265)	0	—	—	—	—	—	—	—	—	—
Sisättö			(113)	0	757	—	—	—	—	—	—	—	—
Stuntio	112	178	550	2	480	—	—	—	—	—	—	—	—
Siuro			(265)	(1)	703	—	—	—	—	—	—	—	—
Skogby	68	550	1	—	—	—	—	—	—	—	—	—	—
Sköldvik			(265)	0	929	25 A	—	—	—	—	—	—	—
Soinlahti			(147)	0	—	—	—	—	—	—	—	—	—
Sorsasalo	100	239	265	2	625	—	—	—	—	—	—	—	—
Sukeva			(265)	(2)	682	25 A	—	—	—	—	—	—	—
Suolahti	(80)												

Nimi	Lyytin laituri-pituus	Pisin laituri-pituus	Laituri-korkeus	Laitureiden lukumäärä	Mitoittava raideleipitus (tavaraliikenne)	Sähkövirran saanti	Sivulaiturin suurin pititus	Pääty-laituri	Kuormaus-kenttä	Nosturi	Polttoaine	Henkilö-liikennettä	Tavaraliikennettä
Namn	Kortaste perrong-längden	Kortaste perrong-längden	Perrong-höjden	Antal spår med perrong	Dimensionerande spär längd (godstrafik)	Tillgång på elström	Sido-perrong	Lastning på samma plan	Lyftkran	Bränsle	Person-trafik	Godstrafik	
Name	Min. platform length [m]	Max. platform length [m]	Platform height [mm]	Number of tracks with platforms	Design train length (freight traffic) [m]	Power supply [400 V, A]	Side loading platform length [m]	End loading platform	Crane	Fuel	Passenger traffic	Freight traffic	
Suonenjoki	250	341	265	3	825	16 A 25 A	—	—	K	—	Y	H	T
Suoniemi				0	743	—	—	—	—	—	—	—	—
Syrjä				0	—	—	5	—	—	—	—	—	—
Syrjämäki				0	—	—	—	—	—	—	—	—	T
Sysmäjärvi				0	—	—	—	—	—	—	—	—	T
Säkylä				0	—	—	—	—	—	—	—	—	T
Säkänniemi				0	—	—	—	—	—	—	—	—	T
Säkkimäki				0	—	—	—	—	—	—	—	—	T
Sääksjärvi				0	—	—	—	—	—	—	—	—	T
Taavetti				0	695	—	—	—	—	—	—	—	T
Tahkoluoto				0	—	—	—	—	—	—	—	—	T
Taijale				0	818	—	—	—	—	—	—	—	T
Talvilahti				0	732	25 A	—	—	—	—	—	—	T
Talvivaara				0	—	—	—	—	—	—	—	—	T
Tammisaari	80	550	1	—	—	—	—	—	—	—	—	—	T
TAMPERE													
Tampere tavaratila				0	767	1500 V, 25 A 63 A	15	—	—	—	—	—	T
Tampere Viinikka				0	966	25 A	134	K	Y	Y	—	—	T
Tampere asema	500	500	550	5	693	1500 V, 63 A	—	K	—	—	—	—	H
Tampere Järvensivu	272	272	550	0	—	—	—	—	—	—	—	—	H
Tapaniila				2	—	—	—	—	—	—	—	—	H
Tapavainola				0	750	—	—	—	—	—	—	—	H
Tavastila	47	265	1	—	—	—	—	—	—	—	—	—	H
Tervejoki	171	265	1	—	—	—	—	—	—	—	—	—	H
Tervasuo				0	—	—	—	—	—	—	—	—	Y

Nimi	Lyhin laituri-pituus	Pisin laituri-pituus	Laituri-korkeus	Laitureiden lukumäärä	Mitoittava raidepituuus (tavaraliikenne)	Sähkövirran saanti	Sivulaituri, suruin pituus	Pääty-laituri	Kuormaus-kenttä	Nostruri	Polttoaine	Henkilö-liikennettä	Tavaraliikennettä
Namn	Kortaste perrong-längden	Längsta perrong-längden	Perrong-höjden	Antal spår med perrong	Dimensionerande spår längd (godstrafik)	Tillgång till elström	Sido-perrong	Perrong i ändan av banan	Lastning på samma plan	Lyftkran	Bränsle	Person-trafik	Godstrafik
Name	Min. platform length [m]	Max. platform length [m]	Platform height [mm]	Number of tracks with platforms	Design train length (freight traffic) [m]	Power supply [400 V, A]	Side loading platform for m	End loading platform	Loading site	Crane	Fuel	Passenger traffic	Freight traffic
Tervola	231	301	265	2	709	25 A	11	—	K	—	H	—	—
Teuva				0	—	25 A	—	—	K	—	—	—	T
Tikkala				0	1031	25 A	—	—	K	—	—	—	—
Tikurila	257	444	550	7	413	—	30	—	K	—	H	—	T
Tohmajärvi				0	742	—	—	—	K	—	—	—	T
Toijala	450	450	550	4	690	25 A	—	—	K	—	H	—	T
Toivala	109	109	265	0	753	25 A	—	—	K	—	H	—	T
Tolosa				2	—	—	—	—	K	—	—	—	—
Tommola				0	—	—	—	—	K	—	—	—	—
Torkkeli				0	788	—	—	—	K	—	—	—	—
Tornio	(101)	(157)	(265)	(2)	434	25 A 63 A	24	—	K	—	—	—	—
Tornio-Itäinen		297	550	1	—	—	—	—	K	—	—	—	—
Tornio-raja				0	—	—	—	—	K	—	—	—	—
Tuomarila	220		222	550	2	—	—	—	K	—	—	—	—
Tuomiola			(198)	(265)	(1)	799	25 A	—	K	—	—	—	—
Turenki	170	170	550	2	1212	—	—	—	K	—	—	—	—
TURKU													
Kupittaa	420	550	550	2	633	—	—	—	H	—	—	—	—
Turku päärautatieasema	315	466	550	6	756	1500 V, 63 A 25 A	—	K	H	—	Y	—	T
Turku tavarat		(200)	(265)	(1)	383	25 A	10, Y	—	KY	—	—	—	T
Turku satama				0	411	63 A	—	—	H	—	—	—	—
Turku Viherlännen				0	—	—	—	—	Y	—	—	—	—
Tuupovaara				0	—	—	—	—	K	—	—	—	—
Tuuri	66	550	550	1	—	—	—	—	K	—	H	—	—
Törmä				0	856	—	—	—	—	—	—	—	—

Nimi	Lyhin laituri-pituus	Pisin laituri-pituus	Laituri-korkeus	Laitureiden lukumäärä	Mitoittava raidepituus (tavaraliikenne)	Sähkövirran saanti	Sivulaituri, suurin pititus	Pääty-laituri	Kuormaus-kenttä	Nosturi	Polttoaine	Henkilö-liikennettä	Tavaraliikennettä
Namn	Kortaste perrong-längden	Längsta perrong-längden	Perrong-höjden	Antal spår med perrong	Dimensionerande spår längd (godstrafik)	Tillgång på elström	Sido-perrong	Lastning på samma plan	Perrong i ändan av banan	Lyftkran	Bränsle	Person-trafik	Godstrafik
Name	Min. platform length [m]	Max. platform length [m]	Platform height [mm]	Number of tracks with platforms	Design train length (freight traffic) [m]	Power supply [400 V, A]	Side loading platform length [m]	End loading platform	Loading site	Crane	Fuel	Passenger traffic	Freight traffic
Törölä													
Uimaharju	98	550	0	0	760	—	—	—	—	—	—	—	—
Urjala	174	265	1	808	25 A	—	—	—	—	—	H	—	T
Uttajarvi	163	0	0	732	—	8	—	—	—	—	—	—	T
Utti		(265)	2	716	—	—	25	—	—	—	—	—	T
Uusikaupunki	(66)	(1)	0	—	—	—	101	—	—	—	—	—	T
Uusikyä	120	550	2	681	1458	—	—	—	—	—	K	—	T
Vaajakoski	183	236	0	726	—	—	57	—	—	—	Y	—	T
Vaala		265	2	1069	25 A	—	14	—	—	—	K	—	T
Vaarala	290	550	0	—	—	—	25	—	—	—	H	—	T
Vaasa		—	1	450	—	—	—	—	—	—	H	—	T
Vahojärvi		0	0	716	—	—	—	—	—	—	—	—	T
VAINIKKALA													
Vainikkala tavara		0	1083	—	25 A	—	—	—	—	—	Y	—	T
Vainikkala asema	482	484	550, 265	952	—	—	—	—	—	—	K	—	T
Vainikkala-raja		0	—	—	—	—	—	—	—	—	H	—	T
Valimo	270	270	550	2	—	—	—	—	—	—	K	—	T
Valekoski		(44)	(265)	(1)	—	—	54	—	—	—	Y	—	T
Valkeasuo		251	550	0	—	—	—	—	—	—	—	—	T
Valimo		276	550	2	759	—	—	—	—	—	H	—	T
Vammala		213	265	0	841	—	128	—	—	—	H	—	T
Varattara		276	550	2	728	—	—	—	—	—	H	—	T
Vantaankoski	180	213	2	1094	63 A	—	124	—	—	—	H	—	T
Varkaus		0	0	25 A	—	—	—	—	—	—	K	—	T
Vartius													

Nimi	Lyhin laituri-pituus	Pisin laituri-pituus	Laituri-korkeus	Laitureiden lukumäärä	Mitoitava raidepituus (tavaraliikenne)	Sähköviran saanti	Sivulaatuiru, suurin pituus	Pääty-laituri	Kuormaus-kenttä	Nosturi	Polito-aine	Henkilö-liikennettä	Tavaraliikennettä
Namn	Kortaste perrong-längden	Längsta perrong-längden	Perrong-höjden	Antal spår med perrong	Dimensionerande spårlängd (godstrafik)	Tillgång på elström	Sido-perrong	Perrong i ändan av banan	Lastning på samma plan	Bränsle	Person-trafik	Godstrafik	
Name	Min. platform length [m]	Max. platform length [m]	Platform height [mm]	Number of tracks with platforms	Design train length (freight traffic) [m]	Power supply [400 V, A]	Side loading platform lenght [m]	End loading platform	Loading site	Crane	Fuel	Passenger traffic	Freight traffic
Vartius-Raja				0	—	—	—	—	—	—	—	—	—
Värikkahaka				0	—	—	—	—	—	—	—	—	—
Vaskiluoto				0	—	838	—	—	—	—	—	—	—
Veretmäki				0	—	—	—	—	—	—	—	—	—
Vesanka				0	—	—	—	—	—	—	—	—	—
Vieikki				0	—	—	—	—	—	—	—	—	—
Vierumäki				0	—	—	—	—	—	—	—	—	—
Vihanti	395	455	265	2	699	25 A	—	—	—	—	—	—	—
Vihanti	58	103	265	2	551	25 A	134	—	—	—	—	—	—
Vihanti	170	170	550	2	286	—	—	—	—	—	—	—	—
Viiala	136	211	265	2	692	25 A	—	—	—	—	—	—	—
Viljijärvi	120	120	550	2	—	—	—	—	—	—	—	—	—
Viljände				110	550	1	697	—	—	—	—	—	—
Vilppula				0	—	—	—	—	—	—	—	—	—
Vimilä				0	—	—	—	—	—	—	—	—	—
Voltti				0	846	—	—	—	—	—	—	—	—
Vuohijärvi				0	713	—	—	—	—	—	—	—	—
Vuojoki				0	760	—	—	—	—	—	—	—	—
Vuokatti				0	638	25 A	—	—	—	—	—	—	—
Vuonisahti	(110)	(141)	(265)	(2)	—	—	—	—	—	—	—	—	—
Vuorten-Vuori		94	265	1	—	—	—	—	—	—	—	—	—
Vuosaari				0	—	—	—	—	—	—	—	—	—
Yksphlaja				0	927	—	—	—	—	—	—	—	—
Ylistaro	176	265	1	—	—	—	—	—	—	—	—	—	—
Ylitornio	167	265	1	—	—	—	—	—	—	—	—	—	—
Ylivalli				0	1013	—	—	—	—	—	—	—	—

Nimi	Lyytin-laituri-pituus	Pisin laituri-pituus	Laituri-korkeus	Laitureiden lukumäärä	Mittoittava raidpituus (tavaraliikenne)	Sähkövirran saanti	Sivulaituri, suurin pititus	Pääty-laituri	Kuormaus-kenttä	Nosturi	Polito-aine	Henkilö-liikennettä	Tavaraliikennettä
Namn	Kortaste perrong-längden	Kortaste perrong-längden	Perrong-höjden	Antal spår med perrong	Dimensionerande spårängd (godstrafik)	Tillgång på elström	Sido-perrong	Lastning på sammna plan	Lyftkran	Bränsle	Person-trafik	Godstrafik	
Name	Min. platform length [m]	Max. platform length [m]	Platform height [mm]	Number of tracks with platforms	Design train length (freight traffic) [m]	Power supply [400 V, A]	Side loading platform length [m]	End loading platform	Crane	Fuel	Passenger traffic		Freight traffic
Ylivieska	315	482	265	3	767	63 A 25 A	113	—	K Y	—	Y	H	T
Yläkoski				0	—	—	—	—	Y	—	—	—	T
Ylämäly				0	—	—	—	—	K	—	—	—	T
Ylöjärvi				0	714	—	77	—	K	—	—	—	T
Ypikkävaara				0	753	—	62	—	K	—	—	—	T
Äetsä	(157)	(265)	(1)	916	—	—	—	—	K	—	—	—	T
Ähtäri	85	225	265	2	617	—	—	—	H	—	—	—	T
Ämmänsaari				0	633	25 A	—	—	K	—	—	—	T
Äänekoski	(35)	(75)	(265)	(2)	860	25 A	14	—	K	—	—	—	T

Nimi	Toinen nimi	Lyhenne	Km Hki	Rataosuuus	Kunta	Liikenteen-ohjaus	Yksityisraiteita	Vaihtoyö-mahdollisuus
Namn	Annat namn	Förkortning		Banavsnitt	Kommun	Trafikledning	Privata spåranläggningar	Möjlighet till växning
Name	Another name	Abbr.		Section	Municipality	Traffic control	Private sidings	Shunting
Ahontpää		Aho	690+468	Seinäjoki – Oulu	Vihanti	K		
Aviapolis		Ayp		Tikkurila – Vantaankoski	Vantaa	K		
Haimoo		Hmo	87+700	Hyvinkää – Kärsämäki	Vihanti	K		
Haujuskoski		Hvk	18+050	Helsingin päärautatieasema –				
Jäniskorpi			32+950	Riihimäki Vantaankoski-Haujuskoski	Vantaa	K		
Kiilinkangas		Jnk	586+856	Seinäjoki – Oulu	Kannus	K		
Kivistö		Kkg	299+490	Kouvolan Joensuu	Lappeenranta	K		
Kuminkaanmäki		Knm	38+500	Tikkurila – Vantaankoski	Vantaa	K		
Leinelä		Lnä		Kerava – Vuosaari	Vantaa	K		
Lentoasema		Len		Tikkurila – Vantaankoski	Vantaa	K		
Limipuro		Lmp	864+750	Oulu – Kontiomäki	Vaala	K		
Niska		Nsk	826+880	Oulu – Kontiomäki	Utajärvi	K		
Pappilankangas		Pkg	308+633	Kouvolan Joensuu	Lappeenranta	K		
Petas		Pet	665+680	Tikkurila – Vantaankoski	Vantaa	K		
Puikkokoski		Pui		Kontiomäki – Vartius-raja	Paltamo	K		
Ruoneva		Rnv		Seinäjoki – Oulu	Siljajoki	K		
Ruskeasanta		Rs		Tikkurila – Vantaankoski	Vantaa	K		
Saarela		Srl	594+546	Seinäjoki – Oulu	Kannus	K		
Salmensmäki		Sal		Seinäjoki – Oulu	Vihanti	K		
Tikkaperä		Tkp		Seinäjoki – Oulu	Liminka	K		
Temmesjoki		Trj		Seinäjoki – Oulu	Liminka	K		
Tuomaanvaara		Tva	682+300	Kontiomäki – Vartius-raja	Ristijärvi	K		
Tupavuori		Tvu	260+100	Kouvolan Joensuu	Lappeenranta	K		
Vehkala		Veh		Tikkurila – Vantaankoski	Vantaa	K		
Viinikkala		Vkl		Tikkurila – Vantaankoski	Vantaa	K		
Yliikkälä		Yll	268+500	Kouvolan Joensuu	Lappeenranta	K		

Nimi	Lyhin laituri-pituus	Pisin laituri-pituus	Laituri-korkeus	Laitureiden lukumäärä	Mitoittava raidepituus (tavaraliikenne)	Sähkövirran saanti	Sivulaituri, suurin pituus	Pääty-laituri	Kuormaus-kenttä	Nosturi	Poltoaine	Henkilö-liikennettä	Tavaraliikennettä
Namn	Kortaste perrong-längden	Kortaste perrong-längden	Perrong-höjden	Antal spår med perrong	Dimensionerande spårflängd (godstrafik)	Tillgång på elstörm	Sido-perrong	Lastning i ändan av banan	Lyftkran	Bränsle	Person-trafik	Godstrafik	
Name	Min. platform length [m]	Max. platform length [m]	Platform height [mm]	Number of tracks with platforms	Design train length (freight traffic) [m]	Power supply [400 V, A]	Side loading platform lenght [m]	End loading platform	Crane	Fuel	Passenger traffic	Freight traffic	
Ahonpää													
Aviapolis													
Haimoo													
Havukoski													
Jäniskorpi													
Kiihinkangas													
Kivistö													
Kuninkaannäsäki													
Leinevä													
Lentoasema													
Liminpuro													
Niska													
Pappilankangas													
Petas													
Puikkokoski													
Ruoneva													
Ruskeasanta													
Saarela													
Salmennäki													
Tikkaperä													
Temmesjoki													
Tuomaanvaara													
Tupavuori													
Vehkala													
Viinikkala													
Ylikkälä													

Nimi	Toinen nimi	Lyhennet	Km Hki	Rataosuuus	Kunta	Kauko-ohjaus manuaalinen	Yksityisraiteita	Vainiotyö-mahdolisuus
Namn	Annat namn	Förkortning		Banavsnitt	Kommun	Trafikledning	Privata spårändgningar	Möjlighet till växling
Name	Another name	Abbr.		Section	Municipality	Traffic control	Private sidings	Shunting
Buslovskaja				288+000	Vainikkala-raja-Vijupuri			
Haaparanta	Haaparanta	Hpa	888+130	Tornio-raja-Boden	Haaparanta	K		
Kivijärvi		Kiv	759+800	Vartius-raja-Kostamus		K		
Svetogorsk			338+200	Imatrakoski-raja-Kamennogorsk (Antrea)		K		
Väntsilä		Vär	553+300	Niirala-raja-Matkaselkä		K		

Nimi	Lyhin laituri-pituus	Pisin laituri-pituus	Laituri-korkeus	Laitureiden lukumäärä	Mitoittava raidepituus (tavaraliikenne)	Sähkövirran saanti	Sivulaituri, surin pititus	Pääty-laituri	Kuormaus-kenttä	Nosturi	Polttoaine	Henkilö-liikennettä	Tavaraliikennettä
Namn	Kortaste perrong-längden	Långsta perrong-längden	Perrong-höjden	Antal spår med perrong	Dimensionerande spår längd (godstrafik)	Tillgång på elström	Sido-perrong	Perrong i ändan av banan	Lastning på samma plan	Lyftkran	Bränsle	Person-trafik	Godstrafik
Name	Min. platform length [m]	Max. platform length [m]	Platform height [mm]	Number of tracks with platforms [m]	Design train length (freight traffic) [m]	Power supply [400 V, A]	Side loading platform length [m]	End loading platform	Crane	Fuel	Passenger traffic	Freight traffic	
Buslovskaja													
Haaparanta													
Kivijärvi													
Svetogorsk													
Väntsilä													

Appendix 3

Transport Operation Regulations for Cross-Border Movements in Tornio-Haaparanta Area

Introduction

Appendix 3 is obsolete. It is based on an agreement between Finnish Rail Administration and Banverket which had not yet been renewed when the Network Statement went into print. Appendix 3 will be updated in its entirety on the Network Statement website.

At the national border the area between signals HP 6/3 and T 832 is called as a "Common zone", which is jointly reserved by the Swedish and Finnish traffic control operators.

In principle, only one train movement is allowed at a time within the common zone, with the exception of irregular situations, such as engine failure or accident.

These regulations have been made in co-operation between Banverket's North Swedish area and the Finnish Rail Administration.

Scope

The regulations are applicable to cross-border movements between Tornio and Haaparanta, and within the common zone.

Reference Documents

- **TRI (BVF 900.3)** (Safety Regulation / Traffic Safety Instructions)
- **JT** (Train Safety Regulation)

Definitions

- **Common zone**

The area to be jointly reserved by the Swedish and Finnish traffic control operators and limited on the Swedish side by the 6/3 intermediate signal and on the Finnish side by the T 832 ground signal.

- **Cross-border movement**

Movements entirely or partly operated within the common zone.

- **Movement**

Refers to railway work and shunting.

- **Permission**

Refers to permission to allow movement to begin.

- **Swedish movement**

Shunting or railway work started in Sweden.

- **Finnish movement**

Shunting or railway work started in Finland.

General

The regulations are drafted in Swedish and Finnish with an identical content.

No movement is allowed within the common zone without the Swedish and Finnish traffic control operators having reserved the relevant section of line.

More than one movement is allowed in the common zone only in irregular situations, such as engine failure or accident. In such cases, the work of several movements shall be agreed at the time.

Tornio-Haaparanta Cross-border Movements

General

Movements are operated as specified in the Finnish Jt, as "shunting" operations, and as specified in the Swedish TRI (BVF 900.3), as "shunting" or "small-wagon shunting" operations.

Messages and message transmission

The Finnish staff shall be in contact with the Finnish traffic control operators, who will deliver message to the Swedish traffic control operators.

The Swedish staff shall be in contact with the Swedish traffic control operators, who will deliver the message to the Finnish traffic control operators.

Haaparanta-Tornio

Prior to the commencement of a Swedish cross-border shunting operation Haaparanta–Tornio direction, permission by the traffic control operators in Haaparanta is required.

Prior to the commencement of a Finnish cross-border shunting operation Haaparanta–Tornio direction, permission by the traffic control operators in Tornio is required.

The traffic control unit that granted a permission shall be notified of the completion of the movement.

Tornio-Haaparanta

Prior to the commencement of a Finnish cross-border shunting operation Tornio–Haaparanta direction, permission by the traffic control operators in Tornio is required.

Prior to the commencement of a Swedish cross-border shunting operation Tornio–Haaparanta direction, permission by the traffic control operators in Haaparanta is required.

The traffic control unit that granted permission shall be notified of the completion of the movement.

Railway Work within the Common Zone

General

The Finnish staff shall be in contact with the Finnish traffic control operators transmitting possible messages to and from the Swedish traffic control operators.

The Swedish staff shall be in contact with the Swedish traffic control operators transmitting possible messages to and from the Finnish traffic control operators.

Swedish staff

The permission of the Haaparanta traffic control operators is required for work carried out by the Swedish staff within the common zone.

Prior to the granting permission, the Haaparanta and Tornio traffic control operators shall reserve the common zone.

The Haaparanta traffic control operators shall be notified of the completion of the work.

Finnish staff

The permission of the Tornio traffic control operators is required for work carried out by the Finnish staff within the common zone.

Prior to granting permission, the Tornio and Haaparanta traffic control operators shall reserve common zone.

The Tornio traffic control operators shall be notified of the completion of the work.

Safety Calls and Documentation

Safety calls

The safety calls between the Swedish and Finnish traffic control operators shall be conducted either in Swedish or in Finnish.

There is a word list with translations in Appendix 5, while Appendix 6 includes examples of phrases to be used.

The safety calls shall be repeated.

Train Log

A train log shall be used according to the instructions and regulations of the traffic control.

Reservation of Common Zone

The reservation of the common zone shall be operated jointly by the Swedish and Finnish traffic control operators.

The clearance of the occupancy of the common zone shall be operated jointly by the Swedish and Finnish traffic control operators.

Maximum Permitted Speed

The maximum permitted speeds are specified in the speed signs, which are described in Appendix 2.

Accidents

Any accident or risk of accident shall be reported to traffic control operators.

Manual Signalling

The Swedish shunting staff shall implement manual signalling as specified in BVF 900.3, irrespective of whether the activity takes place on the Swedish or Finnish side of the border.

The Finnish shunting staff shall implement manual signalling as specified in Jt, irrespective of whether the activity takes place on the Finnish or Swedish side of the border.

A "stop" signal shall always be followed, irrespective of whether it is operated in conformity with the Swedish or Finnish regulations.

Appendix 1

Signals and Signal Aspects

The signals are applicable in conformity with the regulations of the country concerned.

Haaparanta-Tornio direction

From Finnish tracks, intermediate signal (main ground signal) 1/6 km 1310.845.



"Stop"



"Proceed"



"Proceed – check clearance"



"Proceed – check turnouts and clearance"

From Swedish tracks, intermediate signal 5/6 km 1310.697



"Stop"



"Proceed –
check turnouts and
clearance"

Swedish and Finnish tracks, intermediate signal 6/8 km 1311.006



"Stop"



"Proceed"

Common track, Tornio T 832, km 886.8



"Stop"



"Proceed with caution"

Tornio–Haaparanta direction

No optical signals are used in Tornio for movements towards Sweden.

Intermediate signal 6/3, km 1311.012



"Stop"




"Proceed – check turnouts and clearance"

Appendix 2

Speed Signs

In conformity with JT



Maximum permitted speed
(the example displaying max. 30 km/h)

In conformity with BVF 900.3




Maximum permitted speed
(the example displaying max. 30 km/h)

Appendix 3

"Stop" Signalling

In conformity with BVF 900.3




Read: **Stop**

In conformity with Jt




Read: **Stop**



Read: **Danger (emergency stop)**

Appendix 4

Drawing of Haaparanta-Tornio Area



Appendix 5

Translation Table

Should any language problems arise, the below table may be implemented.

Swedish	Finnish	English
Växling	Vaihtotyö	Shunting work
Arbete	Työ	Work
Reserverad zon	Varaus	Reserved / Occupied
Upphävande	Peruuttaminen	Clearance of occupancy
Tägklarerare	Junasuorittaja	Dispatcher
Trafikledning	Liikenteenohjaus	Traffic control
Station	Asema	Station
Fara	Vaara	Danger
Stoppsignal	Seis-opaste	Stop aspect
Passage av en signal	Opastimen ohittaminen	Passing of signal
Signal	Opastin/Opaste	Signal / Signal aspect
Repetera	Toistaa	Repeat
Rätt uppfattat	Oikein ymmärretty	Correctly read

Appendix 6

Example Phrases

Zone reservation request for shunting work

- Swe:** Tågklareraren _____, reserverad zon Haparanda–Torneå, växling.
Fin: Liikenteenohjaus _____, varaus Haaparanta–Tornio välille, vaihtotyö.
Eng: Traffic control _____, reservation Haaparanta–Tornio, shunting.

Zone reservation request for railway work

- Swe:** Tågklareraren _____, reserverad zon Haparanda–Torneå, arbete.
Fin: Liikenteenohjaus _____, varaus välille Haaparanta–Tornio, työ.
Eng: Traffic control _____, reservation Haaparanta–Tornio, work.

Clearence of occupied zone

- Swe:** Tågklareraren _____, upphävande reserverad zon _____ - _____.
Fin: Liikenteenohjaus _____, varauksen peruuttaminen välille _____ - _____.
Eng: Traffic control _____, clearance of occupied zone _____ - _____

Request for reservation in dangerous situation

- Swe:** Tågklareraren _____, Fara Haparanda–Torneå.
Fin: Liikenteenohjaus _____, vaara Haaparanta–Tornio.
Eng: Traffic control _____, danger Haaparanta–Tornio.

Permission to pass stop signal aspect, Haaparanta

- Swe:** Tågklareraren Haparanda, medgivande att passera signal (ett-sex) och/eller (åtta-tre) och/eller (sex-åtta).
Fin: Liikenteenohjaus Haaparanta, lupa ohittaa opastin (yksi-kuusi) ja/tai (kahdeksan-kolme) ja/tai (kuusi-kahdeksan).
Eng: Traffic control Haaparanta, permission to pass signal (one-six) and/or (eight/three) and/or (six-eight).

Permission to pass stop signal aspect, Tornio

- Swe:** Tågklareraren Torneå, växling, medgivande att passera signal (T åtta-tre-två).
Fin: Liikenteenohjaus Tornio, vaihtotyö, lupa ohittaa opastin (T kahdeksan-kolme-kaksi).
Eng: Traffic control Tornio, shunting, permission to pass signal (T eight-three-two).

Correctly read

- Swe:** Rätt uppfattat.
Fin: Oikein ymmärretty.
Eng: Correctly read.

Repeat

- Swe:** Repetera.
Fin: Toista.
Eng: Repeat.

Appendix 4

Loading Gauge

The loading gauge (KU) refers to the space inside which the load on an open wagon shall remain, when the wagon is in the centre position on a straight, even track.




Figure 1. Principal dimensions of the loading gauge.

Use of the Loading Gauge

The loading gauge is valid on the whole rail network with the exceptions mentioned below.

The loading gauge may be used for wagons in which the wheelbase or the distance between bogie centres is max. 17.5 m and the length of the loading area of the wagon outside the wheelbase or the distance between bogie centres max. 0.2 times the length of the wheelbase or the distance between bogie centres. In other cases, loading shall be examined separately.

If there is a risk that the load may be displaced laterally outside the loading gauge during transportation, the width of the load shall be reduced correspondingly. If the displacement of the load may increase the height of some parts of the load so that they extend outside the loading gauge, the height of the load shall be reduced correspondingly.

If the load extends below the floor level of the wagon, the regulations concerning the vehicle gauge (LKU) are applied or the load is carried as a special transport.

Loading Gauge Restrictions

The bridges on the line section Helsinki Central Railway Station (passenger railway yard)-Pasila (passenger railway yard)-Ilmala (depot) restrict the loading gauge. The loading gauge valid on these bridges is marked with dashed line (-----) on the loading gauge drawing (Figure 1).

On several industrial and other sidings, there are loading gauge restrictions, which shall be taken into account in local traffic operating.

Transports Exceeding the Loading Gauge

Lorries, lorry trailers and containers exceeding the loading gauge may be transported on separately specified line sections on the conditions laid down in the transport permit. Transports exceeding the loading gauge can be transported on the sections of line mentioned in the network description, according to the conditions based on the Finnish Transport Safety Agency's regulations.


Other transports exceeding the loading gauge are transported as special transports.

Appendix 5

Structure Gauge

The form and dimensions of the structure gauge (ATU) on a straight track, on open line and in the railway yard are shown in Figure 1. The space required for the mounting of the catenary structure and for the passage of the pantograph on electrified lines is marked by the broken line D-E-F-G-H-L. The widths of the structure gauge in curves, restrictions and more detailed instructions are presented in the Rata tekniset objekti (RATO) publication, part 2 "Radan geometria" (Track geometry).

Figure 1. Principal dimensions of the structure gauge.



Effective Passing Clearance

The structure gauge is used as a guideline for building and mounting new structures and installations in the vicinity of the track. The structure gauge or the deviations from it constitute the so-called effective available structure gauge, i.e. the passing clearance, for special consignments. Information on the passing clearance is collected for each line section and continuously updated by the track maintainers.

Appendix 6

Superstructure Categories, EN Categories and Permitted Speeds for Different Axle Loads

Division of Lines into Line Categories

The lines are divided into line categories according to the superstructure as follows:

Table 1. Division of lines into categories.

Category		Superstructure		
Finnish Transport Infrastructure Agency	SFS-EN 15528	Rails	Sleepers	Ballast
A	C4	K30, K33	wooden	gravel or equivalent
B ₁	D4	K43, 54 E1, K60, 60 E1	wooden	gravel or equivalent
B ₂	D4	K43, K60	wooden, concrete	railway ballast
C ₁	D4 / E4	54 E1	wooden, concrete before 1987	railway ballast
C ₂	D4 / E4	54 E1	concrete 1987 and after	railway ballast
D	D4 / E4	60 E1	concrete	railway ballast

The border of the line category is marked in the middle of the station building in the traffic operating point, unless another point is indicated by the kilometre marking.

The line categories for sections of lines are also presented in Figure 1.

Responsibility of the Track Maintainer

Track maintainer has the right to issue, at their discretion, regulations restricting the permitted axle load and speed depending on the condition of the track superstructure.

Table 2. Superstructure Categories and EN Categories of the main lines and permitted speeds for different axle loads.

Section of line	Category		Passenger trains		Freight trains			
	Finnish Transport Infrastructure Agency	SFS-EN 15528	locomotive hauled	motor cars	16t	20t	22.5t	25t
Helsinki–Riihimäki								
Helsinki päärautatieasema–Pasila asema	C ₁	D4	80	80	80	80	80	—
Pasila asema–Tikkurila läntisin raide	D	E4	160	160	120	120	100	100
Pasila asema–Tikkurila läntinen keskiraide	D	E4	160	160	120	120	100	100
Pasila asema–Tikkurilan itäinen keskiraide	D	E4	120	120	120	120	100	100
Pasila asema–Tikkurilan itäisin raide	D	E4	120	120	120	120	100	100
Tikkurila–Kerava asema läntisin raide	D	E4	200	200	120	120	100	100
Tikkurila–Kerava asema läntinen keskiraide	D	E4	200	200	120	120	100	100
Tikkurila–Kerava asema itäinen keskiraide	D	E4	120	120	120	120	100	100
Tikkurila–Kerava asema itäisin raide	D	E4	120	120	120	120	100	100
Kerava asema–Kytömaa läntisin raide	D	E4	120	120	120	120	100	100
Kerava asema–Kytömaa läntinen keskiraide	D	E4	200	200	120	120	100	100
Kerava asema–Kytömaa itäinen keskiraide	D	E4	200	200	120	120	100	100
Kerava asema–Kytömaa itäisin raide	D	E4	120	120	120	120	100	100
Kytömaa–Kyrölä	D	E4	200	200	120	120	100	100
Kyrölä–Purola läntinen raide	D	E4	200	200	120	120	100	100
Kyrölä–Purola keskiraide	D	E4	200	200	120	120	100	100
Kyrölä–Purola itäinen raide	D	E4	120	120	120	120	100	100
Purola–Riihimäki asema	D	E4	200	200	120	120	100	100
Riihimäki–Tampere								
Riihimäki asema–Sääksjärvi	D	E4	200	200	120	120	100	100
Sääksjärvi–Tampere tavara läntinen raide	D	E4	200	200	120	120	100	100
Sääksjärvi–Tampere tavara keskiraide	D	E4	200	200	120	120	100	100
Sääksjärvi–Tampere tavara itäinen raide	D	E4	100	100	100	100	100	100
Tampere tavara–Tampere asema	D	E4	200	200	120	120	100	100
Kerava–Sköldvik								
Kytömaa–Sköldvik	D	D4	80	80	80	80	80	—
Olli–Porvoo								
Olli–Porvoo	A	C4	35 ³	50 ³	35 ³	20 ³	—	—
Kerava–Vuosaari								
Kerava asema–Vuosaari	D	D4	—	—	80	80	80	80
Helsinki–Turku satama								
Helsinki päärautatieasema–Leppävaara	D	D4	120	120	120	120	100	—
Leppävaara–Kirkkonummi	C ₂	D4	120	120	120	120	100	—
Kirkkonummi–Karjaa	C ₁	D4	160	180	120	120	100	—
Karjaa–Pohjankuru	D	D4	160	200	120	120	100	—
Pohjankuru–km 103,6	C ₁	D4	160	180	120	120	100	—
km 103,6–km 116,0	C ₂	D4	160	200	120	120	100	—
km 116,0–km 121,3	D	D4	160	200	120	120	100	—
km 121,3–km 158,0	C ₂	D4	160	200	120	120	100	—
km 158,0–Turku päärautatieasema	C ₁	D4	160	180	120	120	100	—
Turku päärautatieasema–Turku satama	C ₁	D4	40	40	40	40	40	—
Huopalahti–Vantaankoski								
Huopalahti–Vantaankoski	C ₁	D4	120	120	120	120	100	—
Turku–Uusikaupunki								
Turku päärautatieasema–Raisio (km 207,4)	C ₁	D4	60	60	60	60	60	—
Raisio (km 207,4)–Uusikaupunki	B ₁	D4	60	60	60	60	50	—
Raisio–Naantali								
Raisio–Naantali	B ₁	D4	50	50	50	50	50	—
Uusikaupunki–Hangonsaari								
Uusikaupunki–km 269,0	C ₁	D4	—	—	30 ²	30 ²	30 ²	—
km 269,0–km 269,7	B ₁	D4	—	—	30 ²	30 ²	30 ²	—
km 269,7–Hangonsaari	C ₁	D4	—	—	30 ²	30 ²	30 ²	—
Hyvinkää–Karjaa								
Hyvinkää–km 133,1	C ₁	D4	80	80	80	80	80	—
km 133,1–Kirkniemi	D	D4	80	80	80	80	80	—
Kirkniemi–km 152,2	D	E4	80	80	80	80	80	80
km 152,2–Karjaa	C ₁	E4	80	80	80	80	80	60

Section of line	Category		Passenger trains		Freight trains			
	Finnish Transport Infrastructure Agency	SFS-EN 15528	locomotive hauled	motor cars	16t	20t	22.5t	25t
Lohja–Lohjanjärvi	B ₁	D4	—	—	35 ²	35 ²	35 ²	—
Karjaa–Hanko Karjaa-km 205,7 km 205,7–Hanko-Pohjoinen Hanko-Pohjoinen–Hanko asema	D C ₁ B ₁	E4 E4 D4	120 60 35	120 60 35	120 60 35	120 60 35	100 60 35	100 60 35
Toijala–Turku Toijala-km 256,7 km 256,7–km 268,5 km 268,5–km 269,3 km 269,3–km 274,1 km 274,1–Turku päärautatieasema	D D D D D	D4 D4 D4 D4 D4	140 140 120 100 80	140 140 120 100 80	120 120 120 100 80	120 120 120 100 80	100 100 100 100 80	— — — — —
Toijala–Valkeakoski	C ₁	D4	50	50	50	50	50	—
Lielahdi–Kokemäki	C ₁	E4	140	140	120	120	100	60
Kokemäki–Pori Kokemäki–Harjavala Harjavala–Pori	D D	E4 E4	140 140	140 140	120 120	120 120	100 100	100 100
Pori–Mäntyluoto	C ₁	E4	70	70	70	70	70	50
Mäntyluoto–Tahkoluoto	B ₂	D4	50	50	50	50	50	—
Pori–Ruosniemi	B ₁	D4	—	—	20 ²	20 ²	20 ²	—
Kokemäki–Rauma	D	E4	100	100	100	100	100	80
Tampere–Seinäjoki Tampere asema–Lielahdi Lielahdi–Seinäjoki asema	D D	E4 D4	120 200	120 200	120 120	120 120	100 100	100 —
Niinisalo–Parkano–Kihniö Niinisalo–Parkano Parkano–Kihniö	A A	C4 C4	30 30	30 30	30 30	30 30	— —	— —
Tampere–Jyväskylä Tampere Järvensivu–Orivesi Orivesi–km 287,4 km 287,4–km 308,2 km 308,2–Jyväskylä	C ₂ D D C ₁	E4 E4 D4 D4	140 120 160 160	140 140 160 160	120 120 120 120	120 120 120 120	100 100 100 100	100 80 — —
Jämsä–Kaipola	B ₁	D4	—	—	50 ²	50 ²	50 ²	—
Jyväskylä–Pieksämäki Jyväskylä–Pieksämäki asema	C ₁	D4	140	140	120	120	100	—
Orivesi–Seinäjoki Orivesi–Haapamäki Haapamäki–km 301,1 km 301,1–Pihlajavesi Pihlajavesi–Seinäjoki	B ₁ B ₁ C ₂ B ₁	D4 D4 D4 D4	100 90 100 100	100 90 100 100	100 90 100 100	70 60 100 60	60 50 100 50	— — — —
Vilppula–Mänttä	B ₁	D4	50	50	50	50	50	—
Seinäjoki–Kaskinen Seinäjoki–km 452,0 km 452,0–km 530,0 km 530,0–Kaskinen	B ₁ ¹⁾ B ₁ ¹⁾ B ₁ ¹⁾	D4 D4 D4	80 60 80	80 60 80	80 60 80	60 50 60	50 40 50	— — —
Seinäjoki–Vaasa	C ₂	D4	120	120	120	120	100	—
Vaasa–Vaskiluoto	A	C4	—	—	30 ²	30 ²	20 ²	—

Section of line	Category		Passenger trains		Freight trains			
	Finnish Transport Infrastructure Agency	SFS-EN 15528	locomotive hauled	motor cars	16t	20t	22.5t	25t
Seinäjoki–Oulu								
Seinäjoki asema–km 419,0	C ₂	D4	140	140	120	120	100	—
km 419,0–km 422,9	D	D4	140	140	120	120	100	—
km 422,9–km 441,8	C ₂	D4	140	140	120	120	100	—
km 441,8–km 551,1	D	D4	140	140	120	120	100	—
km 551,1–km 553,1	C ₂	D4	70	70	70	70	70	—
km 553,1–Oulu asema	D	D4	140	140	120	120	100	—
Pännäinen–Pietarsaari	C ₂	D4	60	60	60	60	60	—
Pietarsaari–Alholma	C ₂	D4	—	—	35 ²	35 ²	35 ²	—
Kokkola–Ykspihlaja	B ₁	D4	—	—	35	35	35	—
Tuomioja–Raahe	C ₂	D4	80	80	80	80	80	—
Raahe–Rautaruukki	C ₂	D4	—	—	35 ²	35 ²	35 ²	—
Oulu–Laurila								
Oulu asema–Laurila	C ₂	D4	140	140	120	120	100	—
Kemi–Ajos	B ₁	D4	—	—	50 ²	50 ²	50 ²	—
Laurila–Kemijärvi								
Laurila–Koivu	D	D4	140	140	120	120	100	—
Koivu–Rovaniemi	D	D4	120	120	120	120	100	—
Rovaniemi–Misi	C ₂	D4	100	100	100	100	100	—
Misi–km 1037,1	C ₁	D4	100	100	100	100	100	—
km 1037,1–Kemijärvi	B ₁	D4	100	100	60	60	50	—
Kemijärvi–Kelloselkä								
Kemijärvi–Isokylä	B ₁	D4	50	50	50	50	50	—
Isokylä–Kelloselkä	A	C4	50	50	40	—	—	—
Laurila–Tornio-raja								
Laurila–Tornio	C ₂	D4	120	120	120	120	100	—
Tornio–Tornio-raja	C ₁	D4	40	40	40	40	40	—
Tornio–Röyttä	B ₁	D4	—	—	50 ²	50 ²	50 ²	—
Tornio–Kolari								
Tornio–km 885,6	B ₂	D4	80	80	80	80	80	—
Km 885,6–km 1011,6	D	D4	80	80	80	80	80	—
km 1011,6–Kolari	D	D4	100	100	100	100	100	—
Kerava–Hakosilta								
Kytömaa–Hakosilta	D	D4	200	220	120	120	100	100
Riihimäki–Kouvola								
Riihimäki asema–Hakosilta	D	D4	140	140	120	120	100	—
Hakosilta–Lahti	D	D4	160	200	120	120	100	80
Lahti–Kouvola asema	D	D4	200	200	120	120	100	100
Lahti–Heinola	B ₁	D4	60	60	60	60	50	—
Lahti–Mukkula	B ₁	D4	—	—	35 ²	35 ²	35 ²	—
Lahti–Loviisan satama	B ₁	D4	60	60	60	60	50	—
Kouvola–Pieksämäki								
Kouvola asema–km 245,9	D	D4	140	140	120	120	100	—
km 245,9–Otava	D	D4	160	200	120	120	100	—
Otava–Pieksämäki asema	D	D4	140	140	120	120	100	—
Mynttilä–Ristiina	A	C4	50	50	50	35	20	—
Otava–Otavan satama	B ₁	D4	—	—	35 ²	35 ²	35 ²	—

Section of line	Category		Passenger trains		Freight trains			
	Finnish Transport Infrastructure Agency	SFS-EN 15528	locomotive hauled	motor cars	16t	20t	22.5t	25t
Pieksämäki–Kontiomäki								
Pieksämäki asema–Kuopio	C ₂	D4	140	140	120	120	100	—
Kuopio–lisalmi	D	D4	140	140	120	120	100	—
lisalmi–Murтомäki	C ₂	D4	140	140	120	120	100	—
Murtomäki–Kajaani	C ₁	D4	140	140	120	120	100	—
Kajaani–Kontiomäki	C ₁	D4	140	140	140	140	100	—
Kajaani–Lamminniemi	B ₁	D4	—	—	35 ²	35 ²	35 ²	—
Suonenjoki–lisvesi	B ₁	D4	—	—	35 ²	35 ²	35 ²	—
Murtomäki–Otanmäki	A	C4	—	—	50 ²	40 ²	—	—
Kouvola–Kuusankoski								
Kouvola asema–Kuusankoski	C ₂	D4	80	80	80	80	80	—
lisalmi–Ylivieska								
lisalmi–km 555,8	C ₁	D4	120	120	120	120	100	—
km 555,8–km 613,1	D	D4	120	120	120	120	100	—
km 613,1–Ylivieska	C ₂	D4	120	120	120	120	100	—
Pyhäkumpu erk. vh–Pyhäkumpu	B ₁	D4	35	35	35	35	35	—
Kontiomäki–Vartius								
Kontiomäki–km 662,3	C ₁	D4	80	80	80	80	80	—
km 662,3–km 664,0	C ₂	D4	80	80	80	80	80	—
km 664,0–km 665,1	C ₁	D4	80	80	80	80	80	—
km 665,1–km 666,2	C ₂	D4	80	80	80	80	80	—
km 666,2–km 672,0	C ₁	D4	80	80	80	80	80	—
km 672,0–km 680,9	C ₂	D4	80	80	80	80	80	—
km 680,9–km 682,0	C ₁	D4	80	80	80	80	80	—
km 682,0–km 686,5	C ₂	D4	80	80	80	80	80	—
km 686,5–km 687,5	C ₁	D4	80	80	80	80	80	—
km 687,5–km 709,0	C ₂	D4	80	80	80	80	80	—
km 709,0–km 747,0	C ₁	D4	80	80	80	80	80	—
km 747,0–km 754,7	C ₂	D4	80	80	80	80	80	—
km 754,7–Vartius-raja	C ₂	D4	80	80	80	80	80	—
Kontiomäki–Ämmänsaari	A	C4	50	50	50	40	—	—
Siilinjärvi–Viinijärvi	C ₂	D4	100	100	100	100	100	—
Sysmäjärvi–Vuonos	B ₂	D4	—	—	35 ²	35 ²	35 ²	—
Haapamäki–Jyväskylä	B ₁	D4	100	100	100	70	60	—
Jyväskylä–Äänekoski	C ₁	D4	100	100	100	100	100	—
Äänekoski–Haapajärvi	A	C4	60	60	60	40	—	—
Kouvola–Kotka								
Kouvola tavara–Juurikorpi läntinen raittie	D	D4	120	120	120	120	100	—
Kouvola Oikoraide–Inkeroinen itäinen raittie	C ₁	D4	120	120	120	120	100	—
Inkeroinen–Juurikorpi itäinen raittie	D	D4	120	120	120	120	100	—
Juurikorpi–Paimenportti	D	D4	120	120	120	120	100	—
Paimenportti–Kotka asema	C ₁	D4	80	80	80	80	80	—
Kotka asema–Kotkan satama	C ₁	D4	35	35	35	35	35	—
Kotka Hovinsaari–Kotka Mussalo	C ₁	D4	50	50	50	50	50	—
Juurikorpi–Hamina	C ₁	D4	100	100	100	100	100	—
Luumäki–Vainikkala	D	D4	120	140	120	120	100	100
Lappeenranta–Mustolan satama	C ₁	D4	—	—	50 ²	50 ²	50 ²	—
Imatra tavara–Imatranksoski-raja	D	D4	50	50	50	50	50	—

Section of line	Category		Passenger trains		Freight trains			
	Finnish Transport Infrastructure Agency	SFS-EN 15528	locomotive hauled	motor cars	16t	20t	22.5t	25t
Kouvola–Joensuu								
Kouvola asema–Luumäki	D	D4	200	200	120	120	100	100
Luumäki–km 395,5	D	D4	140	140	120	120	100	—
km 395,5–Säkäniemi	D	D4	140	140	120	120	100	—
Säkäniemi–Joensuu Sulkuniemi	D	D4	140	140	120	120	100	—
Joensuu Sulkuniemi–Joensuu asema	C ₁	D4	90	90	90	90	90	—
Niirala–Säkäniemi								
Niirala raja–Säkäniemi	D	D4	100	100	100	100	100	—
Joensuu–Ilomantsi								
Joensuu Sulkulahti–Heinävaara	B ₁	D4	60	60	60	60	60	—
Heinävaara–km 660,4	A	C4	50	50	40	—	—	—
km 660,4–km 664,1	B ₁	D4	50	50	40	—	—	—
km 664,1–km 678,4	A	C4	50	50	40	—	—	—
km 678,4–km 683,8	B ₁	D4	50	50	40	—	—	—
km 683,8–km 687,9	A	C4	50	50	40	—	—	—
km 687,9–km 692,5	B ₁	D4	50	50	40	—	—	—
km 692,5–Ilomantsi	A	C4	50	50	40	—	—	—
Pieksämäki–Joensuu								
Pieksämäki–Varkaus	C ₂	D4	120	120	120	120	100	—
Varkaus–Joensuu asema	C ₂	D4	120	120	120	120	100	—
Varkaus–Kommila								
	B ₂	D4	50	50	50	50	50	—
Huutokoski–Savonlinna								
	C ₂	D4	120	120	120	120	100	—
Savonlinna–Parikkala								
	B ₂ ¹⁾	D4	110	110	110	90	80	—
Joensuu–Nurmekoski								
Joensuu asema–Uimaharju	C ₂	D4	120	120	120	100	—	—
Uimaharju–Lieksa	C ₂	D4	100	100	100	100	—	—
Lieksa–Nurmekoski	B ₂	D4	110	110	90	80	—	—
Lieksa–Pankakoski								
	A	C4	—	—	30 ²⁾	30 ²⁾	20 ²⁾	—
Nurmekoski–Kontiomäki								
Nurmekoski–Porokylä	B ₂	D4	80	80	80	80	80	—
Porokylä–Maanselkä	C ₂	D4	80	80	80	80	80	—
Maanselkä–Vuokatti	A	C4	50	50	40	—	—	—
Vuokatti–Kontiomäki	B ₁	D4	80	80	60	50	—	—
Vuokatti–Lahnaslampi								
	B ₂	D4	—	—	50 ²⁾	50 ²⁾	50 ²⁾	—
Oulu–Kontiomäki								
Oulu Nokela–Utajärvi	C ₁	D4	120	120	120	100	—	—
Utajärvi–km 874,0	C ₁	D4	140	140	120	100	—	—
km 874,0–Paltamo	C ₁	D4	120	120	120	100	—	—
Paltamo–Kontiomäki	C ₁	D4	140	140	120	100	—	—

¹⁾ Bridge restrictions, see Appendix 10

²⁾ Shunting traffic only

³⁾ Finnish Rail Agency regulation/museum traffic 295/411/2008

Wagons with Axle Loads above the Accepted Limit

- 1) A wagon whose axle weight exceeds the maximum axle weight given for the different line sections in the table in section 3.3 of the Network Description is overweight for that line section.
- 2) The load specified in the wagon load table may not be exceeded intentionally. Any excess load must be unloaded at the first possible traffic operating point if the load exceeds the permitted load by more than 5% when the maximum axle load is 225 kN or by more than 2% when the maximum axle load is 250 kN.
- 3) When the maximum axle load of a domestic wagon or a wagon under COTIF agreement is 225 kN, wagons bearing excess weight may be transported at no more than the following speeds:

Superstructure Category	Max. axle load [t]	Speed [km/h]
A ⁽¹⁾	225 ⁽¹⁾	20 ⁽¹⁾
B ₁	235	35
B ₂	235	50
C ₁ , C ₂ , D	235	80

(1) On main lines and secondary tracks belonging to the superstructure category A individual overweight wagons with axle loads exceeding 200 kN but not 225 kN may be transported only on a temporary basis at a speed of 20 km/h. It is not permitted to operate on main lines and secondary tracks of superstructure category A at axle loads exceeding 225 kN.

- 4) Overweight wagons must be transported in line with the regulations governing exceptional transport. Before transport the wagon's wheel sets and the rest of the bogie structure must be inspected.
- 5) Temporary transport of overweight wagons can be considered in case of ad hoc need. Any temporary transport of overweight loads must be notified to the track's maintenance operator with a view to monitoring the condition of the track superstructure.
- 6) Overweight wagons conforming to Russian standards, with maximum axle loads of 245 kN, may be transported on separately specified line sections as exceptional transport on the terms specified in the transport licence. The Network Description lays down the line sections concerned as well as the terms and conditions of operation. It is prohibited to operate on main lines and branch lines belonging to the superstructure category A.
- 7) Transport of overweight loads other than those referred to in points 3, 4 and 5, which have not obtained a permanent transport licence, will be deemed exceptional load transport.

Permitted Speed on Points and Track Crossings

Table 2. Permitted speed on points and track crossings.

	Superstructure category					
	A	B ₁	B ₂	C ₁	C ₂	D
Straight track						
Single points, 60 E 1, short	70	100	110	180	200	200
Single points, 60 E 1, long	—	100	110	180	200	220
Single points, 54 E 1, long	70	100	110	140	140	140
Single points, other	70	100	110	160	160	60
Three-throw points	70	100	110	120	120	120
Diamond crossings	35	90	90	90	90	90
Track crossings	35 ¹⁾	90 ¹⁾	90 ¹⁾	90 ¹⁾	90 ¹⁾	90 ¹⁾
Deflecting section						
Short points R = 165 m	20 ¹⁾	20 ¹⁾	20 ¹⁾	20 ¹⁾	20 ¹⁾	20 ¹⁾
Short points	35	35	35	35	35	35
Short points when axle load is over 22.5 t	—	10	20	20	20	35
Long points						
R = 500 m	—	—	—	60	60	60
R = 530 m	70	70	70	—	—	—
R = 900 m, when axle load max. 22.5 t	—	80	80	80	80	80
R = 900 m, when axle load over 22.5 t	—	—	—	60	60	60
R = 1600 m	—	—	—	110	110	110
R = 2500 m	—	—	—	140	140	140
R = 3000 m	—	—	—	—	—	160
Non-interlocked points						
Straight track and deflecting section	30 ¹⁾	30 ¹⁾	30 ¹⁾	30 ¹⁾	30 ¹⁾	30 ¹⁾
Trailable points						
	30	30	30	30	30	30

1) Indicated with a speed board

Päälysrakenneluokka Överbyggnadsklass Superstructure Category	ei sähköistetty icke-elektrifierad non-electrified	sähköistetty elektrifierad electrified	kiskotus räler rails	pölkyt sliprar sleepers	tukikerros ballast ballast
A	—		K30, K33	puu trä wooden	raidesora tai vastaava ballastgrus eller motsvarande gravel or equivalent
B ₁	—		K43, K60, K54 E1, 60 E1	puu trä wooden	raidesora tai vastaava ballastgrus eller motsvarande gravel or equivalent
B ₂	—	—	K43, K60	puu, betoni trä, betong wooden, concrete	raidesepeli makadamballast railway ballast
C ₁	—	—	54 E1	puu, betoni trä, betong wooden, concrete < 1987	raidesepeli makadamballast railway ballast
C ₂	—	—	54 E1	betoni betong concrete ≥ 1987	raidesepeli makadamballast railway ballast
D	—	—	60 E1	betoni betong concrete	raidesepeli makadamballast railway ballast

----- Ei liikennöintiä
Trafikeras inte
No traffic

— Yksityinen rata
Privat bana
Private line

— Museorata
Museibana
Museum line




Figure 1. Superstructure category and electrification.

Appendix 7

Signalling Systems

The signalling systems used on the lines are represented in the figures in this appendix.




Figure 1. Lines with a section blocking system.




Figure 2. Lines with a centralised traffic control systems.

Junan
kulunvalvontajärjestelmällä
varustettu rataosa
Linje med automatisk
tågkontroll
Line with ATP

() = liikennepaikka ei kuulu
kulunvalvontajärjestelmän
rataosaan
Trafikplats utan
automatisk tågkontroll
Station without ATP

Ei liikennointia
Trafikeras inte
No traffic

Yksityinen rata
Privat bana
Private line

Museorata
Museibana
Museum line

Mäntyluoto (Pori)

Rauma

Uusikaupunki

Naantali

Turku satama

Karja

Hanko

Tornio

Kemi

Raahe

Kokkola

Pietarsaari

Vaasa

Seinäjoki

Kaskinen

Parkano

Mäntyluoto

(Pori)

Toijala

Tampere

Orivesi

Haapamäki

Jyväskylä

Äänekoski

Siilinjärvi

Kuopio

Pieksämäki

Joensuu

Säkäniemi

Niirala

(Savonlinna)

Mikkeli

Parikkala

Imatra

Uusikaupunki

Naantali

Turku satama

Karja

Hanko

Tornio

Kemi

Raahe

Kokkola

Pietarsaari

Vaasa

Seinäjoki

Kaskinen

Parkano

Mäntyluoto

(Pori)

Toijala

Tampere

Orivesi

Haapamäki

Jyväskylä

Äänekoski

Siilinjärvi

Kuopio

Pieksämäki

Joensuu

Säkäniemi

Niirala

(Savonlinna)

Mikkeli

Parikkala

Imatra

Uusikaupunki

Naantali

Turku satama

Karja

Hanko

Tornio

Kemi

Raahe

Kokkola

Pietarsaari

Vaasa

Seinäjoki

Kaskinen

Parkano

Mäntyluoto

(Pori)

Toijala

Tampere

Orivesi

Haapamäki

Jyväskylä

Äänekoski

Siilinjärvi

Kuopio

Pieksämäki

Joensuu

Säkäniemi

Niirala

(Savonlinna)

Mikkeli

Parikkala

Imatra

Uusikaupunki

Naantali

Turku satama

Karja

Hanko

Tornio

Kemi

Raahe

Kokkola

Pietarsaari

Vaasa

Seinäjoki

Kaskinen

Parkano

Mäntyluoto

(Pori)

Toijala

Tampere

Orivesi

Haapamäki

Jyväskylä

Äänekoski

Siilinjärvi

Kuopio

Pieksämäki

Joensuu

Säkäniemi

Niirala

(Savonlinna)

Mikkeli

Parikkala

Imatra

Uusikaupunki

Naantali

Turku satama

Karja

Hanko

Tornio

Kemi

Raahe

Kokkola

Pietarsaari

Vaasa

Seinäjoki

Kaskinen

Parkano

Mäntyluoto

(Pori)

Toijala

Tampere

Orivesi

Haapamäki

Jyväskylä

Äänekoski

Siilinjärvi

Kuopio

Pieksämäki

Joensuu

Säkäniemi

Niirala

(Savonlinna)

Mikkeli

Parikkala

Imatra

Uusikaupunki

Naantali

Turku satama

Karja

Hanko

Tornio

Kemi

Raahe

Kokkola

Pietarsaari

Vaasa

Seinäjoki

Kaskinen

Parkano

Mäntyluoto

(Pori)

Toijala

Tampere

Orivesi

Haapamäki

Jyväskylä

Äänekoski

Siilinjärvi

Kuopio

Pieksämäki

Joensuu

Säkäniemi

Niirala

(Savonlinna)

Mikkeli

Parikkala

Imatra

Uusikaupunki

Naantali

Turku satama

Karja

Hanko

Tornio

Kemi

Raahe

Kokkola

Pietarsaari

Vaasa

Seinäjoki

Kaskinen

Parkano

Mäntyluoto

(Pori)

Toijala

Tampere

Orivesi

Haapamäki

Jyväskylä

Äänekoski

Siilinjärvi

Kuopio

Pieksämäki

Joensuu

Säkäniemi

Niirala

(Savonlinna)

Mikkeli

Parikkala

Imatra

Uusikaupunki

Naantali

Turku satama

Karja

Hanko

Tornio

Kemi

Raahe

Kokkola

Pietarsaari

Vaasa

Seinäjoki

Kaskinen

Parkano

Mäntyluoto

(Pori)

Toijala

Tampere

Orivesi

Haapamäki

Jyväskylä

Äänekoski

Siilinjärvi

Kuopio

Pieksämäki

Joensuu

Säkäniemi

Niirala

(Savonlinna)

Mikkeli

Parikkala

Imatra

Uusikaupunki

Naantali

Turku satama

Karja

Hanko

Tornio

Kemi

Raahe

Kokkola

Pietarsaari

Vaasa

Seinäjoki

Kaskinen

Parkano

Mäntyluoto

(Pori)

Toijala

Tampere

Orivesi

Haapamäki

Jyväskylä

Äänekoski

Siilinjärvi

Kuopio

Pieksämäki

Joensuu

Säkäniemi

Niirala

(Savonlinna)

Mikkeli

</div




Figure 4. Lines with a radio-controlled traffic system.

- Kuumakäynti-ilmaisin keskusyksikkö
Varmgångsdetektor centralenhet
Hot box detector central processing unit
- Kuumakäynti-ilmaisin mittausasema
Varmgångsdetektor mätenhet
Hotbox detector measuring point
- Virroitinvalvontakamera
Strömvägaredetektor
Pantograph detector
- Varaus pyörävoimailmaisimelle
Option för en hjulkraftdetektor
Option for a wheel load checkpoint
- Varaus kuumakäynti-ilmaisimelle
Option för en varmgångsdetektor
Option for a hot box detector

- Ei liikennöintiä
Trafikeras inte
No traffic
- Yksityinen rata
Privat bana
Private line
- Museorata
Museibana
Museum line
- Rakenteilla
Under byggnad
Under construction



Figure 5. Control equipment for rolling stock.

Appendix 8

Vibration-related Speed Restrictions

Table 1. Vibration-related speed restrictions.

Operating point	Operating point	km-stretch	Valid since	Speed restriction
Seinäjoki–Oulu	Liminka	726+900–729+200	1998	≥ 3000-ton trains 50 km/h
Riihimäki–Kouvola	Koria	182+900–186+400	2001	≥ 3000-ton trains 30 km/h
Seinäjoki–Oulu	Kempele	740+600–741+700	7/1/2002	≥ 3000-ton trains 50 km/h
Riihimäki–Kouvola	Hollola	116+200–118+500	2001	≥ 3000-ton trains 40 km/h
Riihimäki–Lahti	Lahti	125+000–125+400	7/1/2002	≥ 3000-ton trains 40 km/h
Helsinki–Riihimäki	Jokela	47+950–49+950	1999	≥ 3000-ton trains 40 km/h
Kerava–Sköldvik	Nikkilä	38+850–40+160	1997	all trains 40 km/h
Kouvola–Kotka	Myllykoski	201+500–203+100	2000	≥ 3000-ton trains 40 km/h
Seinäjoki–Kaskinen	Kurikka	450+500–452+000	1999	all trains 40 km/h
Oulu–Kontiomäki	Muhos	786+000–790+000	5/11/2002	≥ 3000-ton trains 60 km/h
Oulu–Kontiomäki	Oulu (Ol–Kon)	762+800–763+800	16/1/2004	≥ 3000-ton trains 40 km/h
Toijala–Turku	Loimaa	208+000–210+600	9/1/2005	≥ 3000-ton trains 40 km/h
Toijala–Turku	Turku (Tl–Tku)	271+900–273+700	1/10/2006	≥ 3000-ton trains 40 km/h
Kerava–Sköldvik	Kerava (Ke–Sld)	30+800–31+350	11/9/2007	≥ 3000-ton trains 40 km/h
Kerava–Lahti	Järvenpää	35+800–36+200	15/10/2008	≥ 3000-ton freight trains 40 km/h

Appendix 9

Maximum Train Speeds in Tunnels

This table presents the tunnels with a speed limit. The speed limit of the track section in question is applied for all other tunnels.

Table 1. Maximum train speeds in tunnels.

Tunnel	Km – location	Maximum speed [km/h]		
		Single-deck	Double-deck	Motorised trains
Helsinki–Karjaa				
Lillgård	46+791–46+977	160	120	180
Riddarbacken	47+769–48+043	160	120	180
Karjaa–Salo				
Bäljars	88+920–89+230	160	140	200
Köpskog	90+490–90+535	160	140	200
Åminne	92+390–92+500	160	140	200
Högbacka	94+365–94+565	160	140	200
Kaivosmäki	113+962–114+060	160	140	200
Haukkamäki	114+304–114+740	160	140	200
Harmaamäki	115+150–115+418	160	140	200
Lemunmäki	125+870–126+590	160	160	180
Märjänmäki	126+940–128+180	160	160	180
Lavianmäki	137+720–138+260	160	160	180
Tottola	139+249–139+777	160	120	180
Salo–Turku				
Halikko	150+207–150+395	160	140	200
Pepallomäki	152+420–152+950	160	140	200
Orivesi–Jyväskylä				
Keljonkangas	335+301–335+526	140	140	140

Appendix 10

Bridge Restrictions

On the movable bridges mentioned below, axle loads and speed impose restrictions on the running of rail vehicles. The speed restrictions are indicated by speed signs.

Bridges with Weight Restrictions

- 1) Kyrönsalmi bridge on the Parikkala–Savonlinna section of line:
 - Axle load restriction 22.5 t
 - Maximum permitted speed on the bridge is 20 km/h
- 2) Seinäjoki, Kyrönjoki, Nenätönjoki, Kainastonjoki, Teuvanjoki, Närpiönjoki and Kaskistensalmi bridges on the Seinäjoki–Kaskinen section of line.
 - Axle load restriction 22.5 t
 - Maximum speed on the bridges is 60 km/h, unless a lower speed limit is otherwise ordered.

The axle loads mentioned here shall not be exceeded, and the excess load shall be unloaded at the station where it is discovered.

These regulations do not apply to 6- or 8-axle wagons built according to the Russian standard, which can be carried over the above-mentioned bridges only as special transport on the conditions laid down in the transport permit.

Movable Bridges

Table 1. Restrictions related to movable bridges.

Bridge	Railway section	Permitted speed [km/h]
Pohja	Karjaa–Hanko	50
Kyrönsalmi	Savonlinna–Parikkala	20 ¹
Pirttiniemi	Pieksämäki–Joensuu	40 ²
Taipale Canal	Pieksämäki–Joensuu	30 ²
Pielisjoki	Pieksämäki–Joensuu, Joensuu–Nurmes	50
Päiväranta	Pieksämäki–Kontiomäki	60
Uimasalmi	Joensuu–Nurmes	60
Tahkoluoto	Mäntyluoto–Tahkoluoto	50

¹ See Bridges with Weight Restrictions.

² The bridge and the rail joints can be locked, in which case the permitted speed is 60 km/h.

Appendix 11

Significant and Other Track Works Affecting Traffic in 2011

This appendix presents an estimate of those rail maintenance works that will be carried out during the 2011 timetable period and that may affect traffic. The information in the appendices may change once the details of funding and planning become clear. The updated list will be published on the Finnish Transport Infrastructure Agency website.

Locations	Affects traffic	Break description
SOUTHERN FINLAND		
Karjaa–Turku: Relocation to the old track base at Ervelä, Piikkiö underpass bridge embankment work	x	Total weekend break from Fri evening to Su afternoon
Kirkkonummi–Karjaa: Repair of pile hat area at Kela, Jeppas underpass bridge	x	Weekend break 16 h
Leppävaara–Kirkkonummi track work at stations: Tolsa and Jorvas	x	Single track, weekend break. Commuter traffic arrangements
Leppävaara: Säterinpolku underpass	x	Single track, weekend break. Commuter traffic arrangements
Ilmala railway yard renovation work	-	-
Hiekkaharju–Koivukylä: Ring Rail line, moving easternmost track, bridge work	x	Easternmost track: 34 h.
Hiekkaharju–Koivukylä: Ring Rail line, moving easternmost track, bridge work	x	Easternmost track: 34 h. East middle track: 34 h. Also weeknight and weekend breaks. Commuter traffic arrangements.
Keski-Pasila: Pasila station track 5b change, Pasila Tavara track changes, construction of vehicle train tracks and of the Helsinki–Käpylä additional western track	x	Weeknight and weekend breaks. Commuter traffic arrangements
Pasila: replacement of V401 points	x	Coordination with Keski-Pasila works.
Huopalahti–Vantaankoski: Repair of bridge waterproofing	x	Single track, weekend breaks. Commuter traffic arrangements
EASTERN FINLAND		
Vainikkala: Track changes	x	Altering track usage
Luumäki–Lappeenranta: Mainline points Rasinsuo, Törölä, Tapavainola	x	9 h breaks at weekends
Kouvola–Mikkeli: Underpass bridges	x	16–24 h total break at weekend
Mikkeli–Pieksämäki: Underpass bridges	x	16–24 h total break at weekend
Pieksämäki–Kuopio: underpass bridges, rock and tunnel strengthening, screening of the ballast, rail replacement, track work at Suonenjoki station	x	16 h total breaks, 8 h work breaks late summer / autumn. Coordination with renovation work at Kuopio railway yard.
Renovation of railway yard at Kuopio: Passenger railway yard and Iloharju	x	Changes to track use. Coordination with Pieksämäki–Kuopio work.
Kuopio–Siilinjärvi: Vt 5 Päiväranta–Vuorela	x	8 h break in wk 18, 65 h total break in wk 25/26. 8 h break in wk 27
Construction of Kotolahti railway yard, installing mainline points. Points change at Kivilahti	x	4 x 10 h and 2 x 24 h work breaks
Kouvola–Inkeroinen: Screening of the ballast, eastern track	x	Total break on eastern track for two weeks
Kouvola–Kuusankoski: Replacement of superstructure	x	8 h work breaks
Savonlinna: VT 14	-	-
Parikkala–Joensuu: Underpass bridges	x	16–24 h total break at weekend

Locations	Affects traffic	Break description
WESTERN FINLAND		
Hämeenlinna: Vaneri underpass	x	8 h work breaks, breaks required for piling and moving bridge, single track in use
Lielahti–Kokemäki: Replacing superstructure 88km	x	8 h work breaks
Pori–Mäntyluoto: Replacing superstructure	x	8 h work breaks at night and weekends
Jämsänkoski–Jyväskylä: Tunnel superstructure.	x	Total break two weeks. No simultaneous Hy-Kr-Tku breaks
Orivesi–Haapamäki: Removing level crossings, bridges	x	16–24 h total break
Tampere–Orivesi: Screening of the ballast, rail replacement	x	Single track
Vilppula–Mänttä: Replacing superstructure	x	8 h work breaks at night
Seinäjoki–Oulu: Improving level of service: Pännäinen–Kokkola bridge works: Moving three bridges. Pännäinen, Kolppi and Kruunupyy operating point work, Seinäjoki–Ruhja: Double-rail jointing work, Riijärvi new operating point. Coordination with work on Tuomioja–Liminka and Kokkola–Ylivieska.	x	5 x total break, Midsummer break
Kokkola points replacement: V561	x	Coordination with work on Seinäjoki–Oulu
Kokkola–Ylivieska: double-rail, three bridges	x	2 x 12 h Sat-Sun at night and Midsummer break 24 h. Not simultaneously with breaks on Seinäjoki–Kokkola.
Seinäjoki–Vaasa: electrification	x	3 h work break 7.00–18.00 hours on four workdays per week between October 2010 and June 2011
Yksipihlaja: Adoption of safety device at intermediate railway yard	x	Track reservations
Tampere passenger railway yard: Rongankatu underpass	x	Changes to track usage for 4 x 36 h
NORTHERN FINLAND		
Seinäjoki–Oulu improving level of service: Tuomioja–Liminka substructure and superstructure, points and railway bridges. New operating points at Ahonpää (Vihanti–Tuomioja stretch) and Tikkaperä (Liminka–Hirvineva stretch). Coordination with work on Seinäjoki–Kokkola and Kokkola–Ylivieska sections.	x	8 h work break June, breaks: 8 x 12 h, 2 x 20 h, Midsummer break 24 h. Not simultaneously with Kokkola–Ylivieska breaks. Coordination with breaks on Kontiomäki–Vartius.
Tornio–Kolari: Superstructure replacement	x	Wk 22–30 Mon-Wed total break, Thu-Sun 10 h daily breaks.
Kontiomäki–Vartius: Sleeper replacement (ca. 40,000 sleepers)	x	Wk 22–32: 8 h work break in two phases
Oulu–Kemi: Myllykangas level crossing/underpass bridge, Toppila light traffic underpass	x	16–24 h total break
Rovaniemi–Kemijärvi: Electrification	–	–
Äänekoski–Saarijärvi: Replacing superstructure	x	Eight week total break
OTHER BREAKS		
Tree maintenance investments	–	–
Replacement of individual points in railway yards: Helsinki, Kouvola, Kotka, Hamina, Kuusankoski, Vainikkala, Lappeenranta, Joensuu, Pieksämäki, Uimaharju, Tampere, Seinäjoki, Jyväskylä, Turku, Riihimäki, Oulu	x	8–16 h work breaks
Maintenance investment, incl. replacing superstructure, bridge and drum repair	x	–
Track check-ups on tracks with speeds over 140 km/h	x	–
Piling maintenance tracks and points	x	–
Rail maintenance work to be ordered separately, e.g. replacing single sleepers and worn-out curved rails	x	–

Map of Traffic Planning Areas

Coordination of track work and traffic according to the traffic planning areas shown on the map below.

CONTACTS

Traffic Control Center, Southern Finland

Helsinki

liikennesuunnittelu.helsinki@vr.fi

Kovanen Timo 040 866 3839
Miikkola Reijo 040 866 3840
Burman Raimo (4h/arkipäivä) 040 866 3846

Traffic Control Center, Western Finland

Tampere

liikennesuunnittelu.tampere@vr.fi

Jalanto Esko 040 863 0570
Kunelius Juha 040 863 1118

Oulu

liikennesuunnittelu.oulu@vr.fi

Meripaasi Sakari 040 864 5450
Aherto Raija 040 864 5446

Traffic Control Center, Eastern Finland

Kouvola

liikennesuunnittelu.kouvola@vr.fi

Sirén Markku 040 863 4197
Lahtinen Juha 040 863 4271

Pieksämäki

liikennesuunnittelu.pieksamaki@vr.fi

Nykänen Aimo 040 863 7002

Joensuu

liikennesuunnittelu.joensuu@vr.fi

Papunen Arto 040 864 0379

Traffic and track work co-ordination areas

- Helsinki
- Tampere
- Oulu
- Kouvola
- Pieksämäki
- Joensuu



Appendix 12

Passenger Information at the stations of the State-owned Rail Network

RHK has acquired a new passenger information system (MIKU) that will replace the older information systems. MIKU allows the info staff to control display devices and provide passengers with up-to-date information.

A new Information Centre established in the 2009 timetable period, will among other things notify the passengers about disturbances and exceptions. More information can be found at the Finnish Transport Infrastructure Agency website.

Table 1 shows passenger information at operating points. If information changes, updated appendix will be published at the Network Statement website.

Table 1. Passenger information at operating points

Station	Swedish name of Station	No information system	Only an announcement system	Track displays	Main displays	Special displays (bridge and other displays)	LCD-monitors	Tunnel displays	TFT displays	Total
Alavus		15	85	272	37	7	89	3	287	771
Dragsvik	Dragsvik	X	1	0	0	0	0	0	0	0
Eläinpuisto-Zoo	Eläinpuisto-Zoo		1	0	0	0	0	0	0	0
Eno	Eno		1	0	0	0	0	0	0	0
Espoo	Esbo			6	0	0	0	0	18	24
Haapajärvi	Haapajärvi		1	0	0	0	0	0	0	0
Haapamäki	Haapamäki			0	0	0	0	0	2	2
Haarajoki	Haarajoki			4	0	0	0	0	4	8
Hankasalmi	Hankasalmi		1	0	0	0	0	0	0	0
Hanko	Hangö		1	0	0	0	0	0	0	0
Hanko-Pohjoinen	Hangö Norra	X		0	0	0	0	0	0	0
Harjavalta	Harjavalta		1	0	0	0	0	0	0	0
Haukivuori	Haukivuori		1	0	0	0	0	0	0	0
Heinävesi	Heinävesi		1	0	0	0	0	0	0	0
Helsinki päärautatieasema	Helsingfors Centralstation			19	4	2	10	3	38	76
Herralta	Herralta		1	0	0	0	0	0	0	0
Hiekkaharju	Sandkulla			4	0	0	0	0	2	6
Hikiä	Hikiä		1	0	0	0	0	0	0	0
Humppila	Humppila			0	0	0	0	0	2	2
Huopalahti	Hoplax			8	0	0	4	0	6	18

Station	Swedish name of Station	No information system	Only an announcement system	Track displays	Main displays	Special displays (bridge and other displays)	LCD-monitors	Tunnel displays	TFT displays	Total
Hyvinkää	Hyvinge			4	0	0	2	0	3	9
Hämeenlinna	Tavastehus			5	2	0	0	0	2	9
Höljäkkä	Höljäkkä	X		0	0	0	0	0	0	0
Iisalmi	Idensalmi			0	0	0	0	0	3	3
Iittala	Iittala			2	0	0	0	0	0	2
Ilmala	Ilmala			2	0	0	2	0	3	7
Imatra	Imatra			0	0	0	0	0	3	3
Inkeroinen	Inkeroinen	1		0	0	0	0	0	0	0
Inkoo	Ingå	1		0	0	0	0	0	0	0
Isokyrö	Storkyro	1		0	0	0	0	0	0	0
Joensuu	Joensuu			0	0	0	0	0	3	3
Jokela	Jokela			3	0	0	1	0	1	5
Jorvas	Jorvas	1		0	0	0	0	0	0	0
Joutseno	Joutseno			0	0	0	0	0	0	0
Juupajoki	Juupajoki	1		0	0	0	0	0	0	0
Jyväskylä	Jyväskylä			3	2	0	11	0	0	16
Jämsä	Jämsä			0	0	0	0	0	1	1
Järvelä	Järvelä	1		0	0	0	0	0	0	0
Järvenpää	Träskända			7	0	0	3	0	1	11
Kajaani	Kajana			0	0	0	0	0	2	2
Kannelmäki	Gamlas			2	0	0	0	0	2	4
Kannus	Kannus	1		0	0	0	0	0	0	0
Karja	Karis			7	0	0	1	0	3	11
Karkku	Karkku	1		0	0	0	0	0	0	0
Kauhava	Kauhava	1		0	0	0	0	0	0	0
Kauklahti	Köklax			3	0	0	0	0	1	4
Kauniainen	Grankulla			3	0	0	0	0	2	5
Kausala	Kausala	1		0	0	0	0	0	0	0
Kemi	Kemi			0	0	0	0	0	2	2
Kemijärvi	Kemijärvi	1		0	0	0	0	0	0	0
Kera	Kera	1		0	0	0	0	0	0	0
Kerava	Kervo			10	0	0	8	0	3	21
Kerimäki	Kerimäki	1		0	0	0	0	0	0	0
Kesälahti		1		0	0	0	0	0	0	0
Keuruu	Keuru	1		0	0	0	0	0	0	0
Kilo	Kilo			4	0	0	0	0	0	4
Kirkkonummi	Kyrkslätt			3	0	0	0	0	6	9
Kitee	Kitee	1		0	0	0	0	0	0	0
Kiuruvesi	Kiuruvesi	1		0	0	0	0	0	0	0

Station	Swedish name of Station	No information system	Only an announcement system	Track displays	Main displays	Special displays (bridge and other displays)	LCD-monitors	Tunnel displays	TFT displays	Total
Kohtavaara	Kohtavaara	X		0	0	0	0	0	0	0
Koivuhovi	Björkgård			2	0	0	0	0	0	2
Koivukylä	Björkby			4	0	0	0	0	1	5
Kokemäki	Kumo			0	0	0	0	0	1	1
Kokkola	Karleby			0	0	0	0	0	2	2
Kolari	Kolari		1	0	0	0	0	0	2	2
Kolho	Kolho		1	0	0	0	0	0	0	0
Kontiomäki	Kontiomäki			0	0	0	0	0	2	2
Koria	Koria		1	0	0	0	0	0	0	0
Korso	Korso			4	0	0	2	0	0	6
Kotka	Kotka		1	0	0	0	0	0	0	0
Kotka Satama	Kotka Satama		1	0	0	0	0	0	0	0
Kouvola	Kouvola			11	2	0	4	0	0	17
Kuopio	Kuopio			4	2	0	0	0	4	10
Kupittaa	Kuppis			4	0	2	2	0	4	12
Kuusivaara	Kuusivaara	X		0	0	0	0	0	0	0
Kylälähti	Kylälähti	X		0	0	0	0	0	0	0
Kymi	Kymi	X		0	0	0	0	0	0	0
Kyminlinna	Kyminlinna	X		0	0	0	0	0	0	0
Kyrölä	Kyrölä			2	0	0	0	0	0	2
Käpylä	Kottby			4	0	0	0	0	2	6
Lahti	Lahtis			12	2	0	0	0	4	18
Laihia	Laihela		1	0	0	0	0	0	0	0
Lapinlahti	Lapinlahti		1	0	0	0	0	0	0	0
Lappeenranta	Villmanstrand			0	0	0	6	0	1	7
Lappila	Lappila		1	0	0	0	0	0	0	0
Lappohja	Lappvik	X		0	0	0	0	0	0	0
Lapua	Lappo		1	0	0	0	0	0	0	0
Lempäälä	Lempäälä			2	0	0	0	0	0	2
Leppävaara	Alberga			8	0	0	5	0	0	13
Lieksta	Lieksta		1	0	0	0	0	0	0	0
Lievestuore	Lievestuore		1	0	0	0	0	0	0	0
Loimaa	Loimaa		1	0	0	0	0	0	0	0
Louhela	Klippsta			2	0	0	0	0	2	4
Luoma	Bobäck		1	0	0	0	0	0	0	0
Lusto	Lusto		1	0	0	0	0	0	0	0
Malmi	Malm			4	0	0	0	0	8	12
Malminkartano	Malmgård			2	0	0	0	0	2	4
Mankki	Mankby		1	0	0	0	0	0	0	0


Station	Swedish name of Station	No information system	Only an announcement system	Track displays	Main displays	Special displays (bridge and other displays)	LCD-monitors	Tunnel displays	TFT displays	Total
Martinlaakso	Mårtensdal			2	0	0	0	0	2	4
Masala	Masaby			4	0	0	0	0	0	4
Mikkeli	St Michel			5	0	2	0	0	5	12
Misi	Misi	X		0	0	0	0	0	0	0
Mommila	Mommila		1	0	0	0	0	0	0	0
Muhos	Muhos		1	0	0	0	0	0	0	0
Muurola	Muurola		1	0	0	0	0	0	0	0
Myllykoski	Myllykoski		1	0	0	0	0	0	0	0
Myllymäki	Myllymäki		1	0	0	0	0	0	0	0
Myyrmäki	Myrbacka			2	0	0	0	0	2	4
Mäkkylä	Mäkkylä			2	0	0	2	0	0	4
Mäntsälä	Mäntsälä			4	0	0	0	0	4	8
Mäntyharju	Mäntyharju			2	0	0	0	0	3	5
Nastola	Nastola		1	0	0	0	0	0	0	0
Nivala	Nivala		1	0	0	0	0	0	0	0
Nokia	Nokia		1	0	0	0	0	0	0	0
Nuppulinna	Nuppulinna			2	0	0	0	0	0	2
Nurmes	Nurmes		1	0	0	0	0	0	0	0
Oitti	Oitti		1	0	0	0	0	0	0	0
Orivesi	Orivesi			0	0	0	0	0	2	2
Orivesi Keskusta	Orivesi Keskusta			0	0	0	0	0	1	1
Oulainen				0	0	0	0	0	1	1
Oulu	Uleåborg			6	2	0	0	0	3	11
Oulunkylä	Åggelby			4	0	0	0	0	4	8
Paimenportti	Paimenportti	X		0	0	0	0	0	0	0
Paltamo	Paltamo		1	0	0	0	0	0	0	0
Parikkala	Parikkala			0	0	0	0	0	2	2
Parkano	Parkano			0	0	0	0	0	2	2
Parola	Parola			2	0	0	0	0	0	2
Pasila	Böle			28	4	1	0	0	32	65
Pello	Pello		1	0	0	0	0	0	0	0
Petäjävesi	Petäjävesi		1	0	0	0	0	0	0	0
Pieksämäki	Pieksämäki			9	2	0	0	0	2	13
Pihlajavesi	Pihlajavesi		1	0	0	0	0	0	0	0
Pitäjänmäki	Sockenbacka			4	0	0	3	0	0	7
Pohjois-Haaga	Norra-Haga			0	0	0	0	0	1	1
Pori	Björneborg			0	0	0	0	0	2	2
Puistola	Parkstad			4	0	0	0	0	4	8

Station	Swedish name of Station	No information system	Only an announcement system	Track displays	Main displays	Special displays (bridge and other displays)	LCD-monitors	Tunnel displays	TFT displays	Total
Pukinmäki	Bocksbacka			6	0	0	0	0	3	9
Punkaharju	Punkaharju	1	0	0	0	0	0	0	0	0
Purola	Purola			2	0	0	0	0	0	2
Pyhäsalmi	Pyhäsalmi	1	0	0	0	0	0	0	0	0
Pännäinen	Bennäs			0	0	0	0	0	1	1
Rekola	Räckhals			2	0	0	1	0	0	3
Retretti	Retretti	1	0	0	0	0	0	0	0	0
Riihimäki	Riihimäki			11	4	0	7	0	1	23
Rovaniemi	Rovaniemi			3	0	0	0	0	3	6
Runni	Runni	1	0	0	0	0	0	0	0	0
Ruukki	Ruukki	1	0	0	0	0	0	0	0	0
Ryttylä	Ryttylä			2	0	0	0	0	0	2
Salo	Salo			6	0	0	3	0	3	12
Santala	Sandö	X		0	0	0	0	0	0	0
Saunakallio	Saunakallio			3	0	0	0	0	0	3
Savio	Savio			4	0	0	0	0	1	5
Savonlinna	Nyslott	1	0	0	0	0	0	0	0	0
Savonlinna	Savonlinna			0	0	0	0	0	0	0
Kauppatori	Kauppatori									
Seinäjoki	Seinäjoki			7	2	0	6	0	0	15
Siilinjärvi	Siilinjärvi			0	0	0	0	0	2	2
Simpele	Simpele	1	0	0	0	0	0	0	0	0
Siuntio	Sjundeå	1	0	0	0	0	0	0	0	0
Skogby	Skogby	X		0	0	0	0	0	0	0
Sukeva	Sukeva	1	0	0	0	0	0	0	0	0
Suonenjoki	Suonenjoki			0	0	0	0	0	1	1
Tammisaari	Ekenäs	1	0	0	0	0	0	0	0	0
Tampere	Tammerfors			13	2	0	0	0	13	28
Tapanila	Mosabacka			4	0	0	0	0	2	6
Tavastila	Tavastila	X		0	0	0	0	0	0	0
Tervajoki	Tervajoki	1	0	0	0	0	0	0	0	0
Tervola	Tervola	1	0	0	0	0	0	0	0	0
Tikkurila	Dickursby			12	0	0	0	0	24	36
Toijala	Toijala			4	2	0	0	0	2	8
Tolsa	Tolls	1	0	0	0	0	0	0	0	0
Tornio	Torneå	1	0	0	0	0	0	0	0	0
Tuomarila	Domsby			3	0	0	0	0	0	3
Turenki	Turenki			2	0	0	0	0	0	2

Station	Swedish name of Station	No information system	Only an announcement system	Track displays	Main displays	Special displays (bridge and other displays)	LCD-monitors	Tunnel displays	TFT displays	Total
Turku päärautatieasema	Åbo Centralstation			9	3	0	5	0	0	17
Turku Satama	Åbo Hamn			2	0	0	0	0	3	5
Tuuri	Tuuri	1	0	0	0	0	0	0	0	0
Uimaharju	Uimaharju	1	0	0	0	0	0	0	0	0
Utajärvi	Utajärvi	1	0	0	0	0	0	0	0	0
Vaala	Vaala	1	0	0	0	0	0	0	0	0
Vaasa	Vasa			2	2	0	0	0	3	7
Vainikkala	Vainikkala	1	0	0	0	0	0	0	0	0
Valimo	Gjuteriet			4	0	0	1	0	0	5
Vammala	Vammala	1	0	0	0	0	0	0	0	0
Vantaankoski	Vandaforsen			0	0	0	0	0	1	1
Varkaus	Varkaus			1	0	0	0	0	2	3
Vihanti	Vihanti	1	0	0	0	0	0	0	0	0
Vihtari	Vihtari	1	0	0	0	0	0	0	0	0
Viiala	Viiala			2	0	0	0	0	0	2
Viinijärvi	Viinijärvi	1	0	0	0	0	0	0	0	0
Vika	Vika	X		0	0	0	0	0	0	0
Vilppula	Vilppula	1	0	0	0	0	0	0	0	0
Vuoniskahti	Vuoniskahti	1	0	0	0	0	0	0	0	0
Ylistaro	Ylistaro	1	0	0	0	0	0	0	0	0
Ylitornio	Ylitornio	1	0	0	0	0	0	0	0	0
Ylivieska	Ylivieska			0	0	0	0	0	2	2
Ähtäri			1	0	0	0	0	0	0	0

GSM-R (RAILI) Network

The Finnish Rail Administration's GSM-R network, RAILI for short, acts as the railways' integrated communication system, serving primarily traffic controllers, drivers and train guards as well as shunting managers and those responsible for track work. The network covers track and railway yards over a distance of about 5,000 km. More information is available in chapter 3.3.3.3 (Traffic Control and Communications Systems) of the Network Statement as well as on the Finnish Transport Infrastructure Agency's website.



Appendix 14

Network Statements of Other Countries

Table 1 shows the Internet addresses of the Network Statements published by the infrastructure managers of other countries, and the names used for the Network Statement. The information in the table is subject to change.

Table 1. Network Statement of other countries

Infrastructure manager	Country	Name used	Internet address
Administrador de Infraestructuras Ferroviarias (ADIF)	Spain	Declaración sobre la Red	http://www.adif.es
Banedanmark	Denmark	Netredegörelse	http://www.bane.dk
Banverket (BV)	Sweden	Järnvägsnätsbeskrivning	http://www.banverket.se
BLS AG (BLS)	Switzerland	Network Statement	http://www.blis.ch
Communauté de Transports – Accès Réseau	Luxembourg	Document de Reference du Reseau	http://www.railinfra.lu
Compania Natională de Căi Ferate SA	Rumania	Documentul de referinta al retelei	http://www.cfr.ro
DB Netz AG	Germany	Schienennetz-Nutzungsbedingungen	http://www.db.de
Eurotunnel	France/England	Eurotunnel Network Statement	http://www.eurotunnel.com
HZ Infrastruktura d.o.o.	Croatia	Izvjesce o mrezi	http://www.railneteurope.com
Infrabel	Belgium	Netverklaring	http://www.railaccess.be
Jernbaneverket	Norway	Network Statement	http://www.jernbaneverket.no
Keyrail	Netherlands	Netverklaring	http://www.keyrail.nl
National Manager of Railway Infrastructure (EDISY S.A.)	Greece	Network Statement	http://www.osenet.gr
National Railway Infrastructure Company (NRIC)	Bulgaria	Network Statement	http://www.rail-infra.bg
Network Rail	Great Britain	Network Statement	http://www.networkrail.co.uk
PKP Polskie Linie Kolejowe S.A. (PKP PLK)	Poland	Network Statement	http://www1.plk-sa.pl
ProRail B.V.	Netherlands	Netverklaring	http://www.prorail.nl
Public Agency for Rail Transport of RS (AŽP)	Slovenia	Network Statement	http://www.azp.si
Raaberbahn AG/GYSEV Zrt. (GYSEV/Raaberbahn)	Austria/Hungary	A GySEV Zrt. Üzletszabályzata	http://www.gysev.hu
Rede Ferroviária Nacional, E.P. E. (REFER)	Portugal	Directorio da Rede	http://www.refer.pt
Réseau Ferré de France (RFF)	France	Document de référence du réseau ferré national	http://www.rff.fr
Rete Ferroviaria Italiana SpA (RFI)	Italy	Prospetto Informativo della Rete	http://www.rfi.it
Slovenske zeleznice d.o.o. (SZ)	Slovenia	Network Statement	http://www.azp.si
Správa Železniční dopravní cesty (CD) / SZDC	The Czech Republic	Network Statement	http://www.szdc.cz
Swiss Federal Railways SBB-Infrastructure (SBB CFF FFS)	Switzerland	Network Statement	http://www.mct.sbb.ch
Vasúti Pályakapacitás-elosztó Kft. (VPE)	Hungary	Network Statement	http://www2.vpe.hu
Železnice Slovenskej Republiky	Slovakia	Sietové vyhlášenie	http://www.zsr.sk
ÖBB Infrastruktur Betrieb AG	Austria	Schienennetznutzungsbedingungen	http://www.railnetaustria.at

PUBLICATION OF FINNISH RAIL ADMINISTRATION ON F SERIES

- | | |
|--------|--|
| 1/2003 | Verkkoselostus 2004 |
| 2/2003 | Luettelo rautatieliikenepaikoista 1.6.2003 |
| 3/2003 | Finnish Network Statement 2004 |
| 4/2003 | Beskrivning av Finlands Bannät 2004 |
| 5/2003 | Verkkoselostus 2005 |
| 6/2003 | Finnish Network Statement 2005 |
| 7/2003 | Beskrivning av Finlands bannät 2005 |
| 1/2004 | Verkkoselostus 2006 |
| 2/2004 | Finnish Network Statement 2006 |
| 3/2004 | Beskrivning av Finlands bannät 2006 |
| 1/2005 | Luettelo rautatieliikenepaikoista 5.6.2005 |
| 2/2005 | Verkkoselostus 2007 |
| 3/2005 | Finnish Network Statement 2007 |
| 4/2005 | Beskrivning av Finlands bannät 2007 |
| 1/2006 | Verkkoselostus 2008 |
| 2/2006 | Finnish Network Statement 2008 |
| 3/2006 | Beskrivning av Finlands bannät 2008 |
| 1/2007 | Luettelo rautatieliikenepaikoista 3.6.2007 |
| 2/2007 | Verkkoselostus 2009 |
| 3/2007 | Finnish Network Statement 2009 |
| 4/2007 | Beskrivning av Finlands bannät 2009 |
| 1/2008 | Rataverkon kuvaus 7.1.2008 |
| 2/2008 | Rataverkon kuvaus 1.6.2008 |
| 3/2008 | Verkkoselostus 2010 |
| 4/2008 | Luettelo rautatieliikenepaikoista 1.1.2009 |
| 5/2008 | Finnish Network Statement 2010 |
| 1/2009 | Beskrivning av Finlands bannät 2010 |
| 2/2009 | Rataverkon kuvaus 1.1.2009 |
| 3/2009 | Rautatieliikenteen täsmällisyys 2008 |
| 4/2009 | Rataverkon kuvaus 1.7.2009 |
| 5/2009 | Verkkoselostus 2011 |



**FINNISH RAIL
ADMINISTRATION**

Publisher:

Finnish Rail Administration (RHK)
PO Box 185, Kaivokatu 8, FI-00101 Helsinki
tel. +358 (0)20 751 5111, fax +358 (0)20751 5108
www.rhk.fi/english

ISBN 978-952-445-317-2

ISSN 1459-3831